กรมพัฒนาพลังงานทดแทน
และอนุรักษ์พลังงาน
กระทรวงพลังงาน

โครงการไฟฟ้าพลังน้ำขนาดเล็กคลองทุ่งเพล 2
KLONG THUNG PHEN 2 HYDROPOWER PROJECT

จังหวัดจันทบุรี
CHANTHABURI PROVINCE

เอกสารหมายเลข 2
VOLUME 2

ข้อกำหนดทางด้านเทคนิค (2/2)
TECHNICAL SPECIFICATIONS (2/2)

ส่วนที่ 2 : งานอุปกรณ์เครื่องจักรกล-ไฟฟ้า
PART 2 : ELECTRO-MECHANICAL EQUIPMENT

PCM บริษัท พี แอนด์ ซี แมเนจเมนท์ จำกัด

KLONG THING PHEN 2 HYDROPOWER PROJECT

CONTRACT C2

SUPPLY, DELIVERY, INSTALLATION AND COMMISSIONING OF ELECTRO-MECHANICAL EQUIPMENT

VOLUME 2: TECHNICAL SPECIFICATIONS

CONTENTS

		PAGE
SECTION 1	GENERAL	1-1
SECTION 2	TURBINES AND GOVERNORS	2-1
SECTION 3	INLET VALVES	3-1
SECTION 4	TESTS FOR TURBINE, GOVERNOR INLET VALVE AND AUXILIARIES, TURBINE MODEL TEST, TURBINE FIELD EFFICIENCY TEST	4-1
SECTION 5	MECHANICAL AUXILIARY EQUIPMENT	5-1
SECTION 6	TESTS FOR MECHANICAL AUXILIARY EQUIPMENT	6-1
SECTION 7	GENERATORS AND AUXILIARIES	7-1
SECTION 8	AC STATION SERVICE TRANSFORMER AND AC SWITCH BOARD	8-1
SECTION 9	TRANFORMER TERMINAL CUBICLES, GENERATOR TERMINAL CUBICLES, BUS DUCTS AND NEUTRAL CUBICLES	9-1
SECTION 10	DC STATION SERVICES	10-1
SECTION 11	CONTROL, PROTECTION AND ALARM SYSTEM	11-1
SECTION 12	MAIN TRANSFORMER	12-1
SECTION 13	LINE PROTECTION AND SWITCHYARD EQUIPMENT	13-1
SECTION 14	GROUNDING SYSTEM	14-1
SECTION 15	ELECTRICAL AUXILIARY EQUIPMENT	15-1

SECTION 1 - GENERAL

S1.01 GENERAL

(1) These General Specifications apply to all equipment, materials, devices & components, including pre-engineering or bought-out items, procedures, methods, techniques, and workmanship contained in the other Technical Specifications whether referred to specifically or not.

(2) Where the other Technical Specifications conflict with these General Specifications, the Technical Specifications shall prevail.

(3) All works shall be subject to a quality control program developed by the Contractor which shall be designed to prevent and readily detect and correct non-conformities in quality of the work as specified in this section, or internationally recognized equivalent. The Contractor shall make available to the Engineer details of the quality control program of Manufacturer's plants which are applicable to the works before manufacturing begins.

(4) The Engineer will be the sole judge of materials and workmanship, among all things, furnished and supplied by the Contractor. No patching, plugging, shimming or other such means to overcome defects, discrepancies or errors shall be employed without the written agreement of the Engineer. Failure to comply with this requirement shall constitute grounds for rejection of the item in question.

(5) Material and equipment not covered by these Specifications shall be subject to acceptance by the Department.

S1.02 SERVICE CONDITIONS

All the equipment shall be designed and manufactured for its particular location for continuous operation at the extremes of climate as listed in Clause 7.02 of Volume 1. Specifically, all equipment to be installed inside the powerhouse shall be designed and manufactured for satisfactory continuous operation at ambient temperature of 40˚C and all equipment to be installed outside of the powerhouse shall be designed and manufactured for satisfactory continuous operation at ambient temperature of 45˚C. Equipment supplied between ceiling and the roofs shall be designed for satisfactory operation at an ambient temperature of 60˚C.

S1.03 REGULATIONS AND STANDARDS

The supply must conform to the laws and regulations existing in the Kingdom of Thailand, in addition to the particular prescription given in this Technical Specifications.

All materials and equipment to be incorporated in the Works and the fabrication of same except as otherwise provided shall conform to the latest edition of the Standards given in the following list:

AFBMA	Anti-Friction Bearing Manufacturers Association
AGMA	American Gear Manufacturers Association
AISI	American Iron and Steel Institute
AISC	American Institute of Steel Construction
ANSI	American National Standards Institute
ASME	American Society of Mechanical Engineer
ASTM	American Society for Testing and Materials
ASHRAE	American Society of Heating, Refrigeration and Air-Conditioning Engineers
AWS	American Welding Society
AWWA	American Water Works Association
BS	Britain National Standard
CMAA	Crane Manufacturer's Association of America
DEMA	Diesel Engine Manufacturers Association
DIN	German National Organization for standardization
EN IEC	European implementation of an IEC Standard are designated
ISA	Instrument Society of America
ISO	International Organization for Standardization
IEEE	Institute of Electrical Electronic Engineers
ICEA	Insulated Cable Engineer's Association
IEC	International Electrotechnical Commission
JIS	Japanese Industrial Standards
NEC	National Electrical Code
NFPA	National Fire Protection Association
NEMA	National Electrical Manufacturers Association
SSPC	Steel Structures Painting Council

The latest edition of each standard shall be applicable at the date of signature of the Contract.

Other equivalent standards shall also be acceptable, and the Contractor shall provide the comparison table for such standards with equivalent to the standards mentioned as above together with the Bid before the award of the Contract.

The Contractor shall submit the standards compliance of the equivalent accepted standards only in English showing the correspondence comparisons with the specified Standards together with the Bid.

The changes of standards after the Bid proposal or after the Contract award shall not be acceptable and it shall be considered that the Contractor intends not to comply with the technical specifications of this Contract.

S1.04 UNITS OF MEASUREMENTS

Units of measurements shall be in the metric and Celsius systems, using the following abbreviations.

Quantity	Unit	Symbol	Remarks
Length	meter	m	
Time	second	s	
	hour	h	
	day	d	
	minute	min	
Volume	liter	L	
Temperature	degree Celsius	˚C	
Force (weight)	gram	g	
	kilogram	kg	
	ton	t	kg x 10^3
Pressure	kilogram per square centimeter	kg / cm^2	
Material Strength	Kilogram per square centimeter	f (y)	minimum yield point
		f (u)	minimum ultimate strength
Power	watt	W	
Frequency	hertz.	Hz	
Electric potential	volt	V	
Electric resistance	ohm	Ω	

Quantity	Unit	Symbol	Remarks
Electric Current	ampere	A	

The following is a list of prefixes used in conjunction with the basic units.

Multiplying Factor	Prefix	Symbol
10^9	giga	G
10^6	mega	M
10^3	kilo	k
10^{-2}	centi	c
10^{-3}	milli	m
10^{-6}	micro	μ

S1.05 MAINTENANCE TOOLS AND INSTRUMENTS

(1) The Contractor shall supply all maintenance tools and instruments required or likely to be required for the proper maintenance of the Plant during its service life. The maintenance tools and instruments shall be sufficient to enable full dismantling and reassemble of the Plant, testing for wear or distortion of all wearing parts, diagnosing, and locating faults in electronic equipment and replacement of all spare parts ordered.

(2) The maintenance tools and instruments shall include but not be confined to:

a) Portable ladders and platforms to permit maintenance service

b) One (1) set of special tools and appliances to enable all maintenance tasks to be performed.

c) One (1) grease gun (if grease lubrication is required) for each type of grease used in the plant with attachments to suit each size of grease nipple

d) One (1) complete set of hand tools and appliances sufficient for all maintenance tasks associated with the plant. The set shall include, but not be confined to:
   (i) spanners to fit every size of nut and bolt used in the plant, screwdrivers, scrapers, files, hammers, pliers, wrenches, wiring tools, etc., as appropriate.
   (ii) gauges, levels, and other measuring instruments for checking clearances and dimensions.
   (iii) insulation testers 500V and 1,000V 1 set (electronic type).
   (iv) multi-meter, digital type 1 set
   (v) clip-amp for AC current measurement 0-1000A, 50 Hz digital type 1 set
   (vi) Tachometer, digital type, 0-2,000 rpm, 1 set
   (vii) Phase rotation tester, 1 set
   (viii) Vibration measuring device (Digital type), 1 set

(ix) any tools necessary for changing lamps for instruments of control panels.

(e) One (1) set of AC-DC arc welder, 300A, AC 1∅, 230V, 50Hz with power improvement capacitor and cable (50 m.), holder and earth clamp.

(f) One (1) of complete set Oxy-Acetylene Welder.

(g) One (1) set of disc grinder 100 mm∅, AC 1∅, 230 V, 50 Hz.

(h) One (1) set of portable electric drill 20 mm∅, AC 1∅ , 230 V, 50 Hz.

(i) One (1) set of electric hammer drill 19 mm∅, AC 1∅ , 230 V, 50 Hz

(j) One (1) set of vacuum cleaners, industrial heavy-duty type, AC 1∅, 230V, 50Hz, 1.5 kW

(k) One (1) set of air compressor, 7 kgf/cm^2, 200 liter/min, AC 1∅, 230V, 50Hz with wheels

(3) The individual tools and appliances shall be listed in price schedule. The prices of the tools and appliances shall be included in the Contract Price.

(4) Any additional maintenance tools and appliances which are required for the proper maintenance of the Plant as defined in this Clause and which are not listed in Price Schedule, shall be included in the Contract Price.

(5) The Contractor may use the mechanical handling equipment for initial erection of the Plant but shall make good any wear or damage before handing over.

a) Maintenance equipment shall be suitably arranged in metal toolboxes of cabinets each fitted with a padlock and 2 keys. Each toolbox or cabinet shall be clearly and permanently marked with the name of the plant to which the maintenance tools and instruments applies and with a list of the equipment it contains.

b) Large tools shall be mounted on a suitable shadow board arranged for wall mounting.

S1.06 SPARE PARTS

(1) All spare parts to be supplied by the Contractor are listed in each technical specification section with each quantity. The spare parts offered shall include all parts subject to normal wear and tear and also such major sub-assemblies as may be subject to accidental damage.

(2) The Department may order all or any of the spare parts at his discretion. The Contractor shall supply the specified spare parts at the individual equipment prices stated in the price schedule provided.

(3) All spare parts ordered shall be interchangeable and suitable for use in place of corresponding parts supplied. They shall comply with the equipment supplied under this Contract and shall be clearly and permanently marked with their descriptions and identification members both on the parts and on the outside of the packages and prepared for permanent storage in an approved manner to prevent deterioration.

(4) The Contractor shall provide descriptions of spare part with their identification numbers, description, and quantity for the Department to add his own identification number.

S1.07 ERECTION, OPERATION AND MAINTENANCE INSTRUCTIONS

(1) Scope

(a) The Contractor shall provide erection, operation and maintenance instructions and the related procedures, the scope of which shall be performed after the equipment delivery at site to the Department for approval.

(b) The Contractor shall, in preparing the instruction, consider the possible lack of experience and lack of familiarity of the operation and maintenance for the equipment supplied under this Contract and shall present the complete information clearly and precisely as much as possible.

(c) The erection procedures and instructions for equipment shall be provided in the form of documents and shall submit to the Department for approval before performing the erection works. If there is any modification, the Contractor shall submit the final erection documents (or) drawings after the erection works done and shall also be submitted as AS-BUILT Drawings to the Department.

(d) The content of the installation instructions shall be applicable and any typical installation instructions are not accepted.

(e) The Contractor shall dispatch his related equipment supervisor (s) to project site during installation period. Before the installation starts, the Contractor shall submit the detail qualifications of Supervisor for approval.

(f) All costs in connection with the Supervision shall be included in the equipment price in this Contract.

(2) Format and compilation

(a) The instructions shall be reproduced in ink by letter press or offset printing or in carbon by electrostatic printing. Reproductions obtained by using dyes, chemicals or photo-sensitive or heat-sensitive materials are not acceptable.

(b) All text shall be on size A4 paper.

(c) Diagrams and drawings for equipment and component assembly shall be with size A3 wherever the original is size A3 or larger. Insertion of loose drawings into cover pockets is not acceptable.

(d) Text, drawings, diagrams, and illustrations included in the instructions shall be easily readable by a person having normal eyesight.

(e) Each copy of the final instructions shall be bound into loose-leaf volumes in strong, durable, washable, vinyl plastic covers inscribed with bold letters upon the front and spine. A sample of the proposed inscribed covers and binding shall be submitted to the Engineer with the draft instructions for approval.

(3) Program for Delivery

The Contractor shall submit the schedule of design, engineering, manufacturing, and delivery of equipment together with main construction schedule.

S1.08 DRAWING

(a) General

All drawings produced by the Contractor or his sub-contractor for this Contract shall comply with the requirements of this Clause.

(b) Drawing Sizes and Standards

All drawings shall be drawn on the International Standards Organization (ISO) ‘A’ series of drawing sheets standardizing where possible on the A3 size. Information and details shall be written in English.

(c) Title Blocks

The Contractor or his subcontractor's title block shall show his name, the date, the title and number of the drawing and each new issue of the drawing shall be identified by a revision letter as part of the drawing number. A detailed description of the revision shall appear on the drawing. In addition, each drawing shall show the following details in the lower right-hand corner.

(d) Main Drawing List

The Contractor shall submit the main drawing list of equipment for the Project and this list shall be submitted to the Engineer for approval.

(e) Quality

a) Drawings to be approved by the Engineer (or) the Department shall be supplied as prints in the visible and readable font size with at least A3 size drawings and main equipment shall be with A2 or A0 size under black and white color print. and shall be the Contractor's original drawings in non-fading ink on durable print. Transparencies reproduced from the original will not be accepted as as-built drawings.

b) As-built drawings shall be of quality suitable for the reproduction of clear legible full-size print, and it shall be submitted along together with Operation and Maintenance Manual.

S1.09 PACKING

a) All Plant shall be effectively protected against damage and corrosion during transportation from the place of manufacture to the site and during storage.

b) Immediately upon arrival at Site, the Contractor shall arrange for all packages to be checked against the shipping list for loss and inspected for damage during transit.

c) The Department will not provide covered storage at the Site. The Contractor shall ensure that all packages are suitable for the storage conditions provided.

d) If machined surfaces show sign of damage on receipt of shipment, the corrosion protection shall be removed, the rust and moisture eliminated, the defects repaired by approved means and the protection re-applied.

e) Electrical insulation shall be protected against sweating and entry of dust during transportation and storage.

f) Flange faces and openings shall be covered by metal blanks and gaskets. Rubber parts shall be protected against light and air. An approved drying agent shall be included with all items enclosed in plastic or other impervious material.

g) All packing material, except that required for storage of spare parts, shall remain the property of the Contractor and shall be removed from the Site. Only parts for immediate use shall be delivered from the works storage area and their packing material shall be removed quickly from the installation site and disposed of to the satisfaction of the Engineer.

h) All packages shall be clearly and indelibly marked with the dimensions, weight, slinging, and load beating points. Any packages which are not symmetrically loaded shall be marked with the position of the center of gravity.

i) Each package shall contain a packing list in a waterproof envelope. Two copies of the packing list shall be sent to the Engineer prior to dispatch.

j) The Engineer shall reserve the right to inspect and approved the equipment and the packing before the items are dispatched. Such inspection will not relieve the Contractor from responsibility for any loss or damage occurring during transportation and storage.

S1.10 PHOTOGRAPHS

(a) The Contractor shall keep photographic records of the works during installation, factory acceptance test and equipment assembly, installation and commissioning and shall be submitted to the Department by the Engineer.

(b) The Contractor shall supply photographs which will:

a) Assist during training of Department personals, who may have no experience during installation and during equipment in operation, during trouble shooting and testing of the plant
b) Record parameter and information which it may not be possible to obtain at a later date during dry test and wet test

This will supplement the detailed instructions provided in the operation and maintenance instructions and reduce the need to rely on memory.

(c) A volume of photographs shall be included with the operation and maintenance instructions. They shall be adequately edited and provided with captions and descriptions to the satisfaction of the Engineer.

(d) All costs in this connection shall be included in the Contract Price.

S1.11 LABELS

(1) Labels

(a) The Contractor shall provide labels in sufficient numbers, size, and detail to permit rapid and positive identification to be made of all pieces of equipment whether enclosed in cubicles or separately mounted.

(b) Labels used indoors shall be engraved on double sided, engraving grade plastic laminate with black letters not less than 3.0mm high on a white background. Labels (used outdoors) shall be of matt stainless steel, with the letters filled with a suitable wax (Gravograph or equal). Pipe labels shall use adhesive markers. Labels and all labels fixed outdoors shall be fastened by nickel-plated brass screws. Indoor plastic laminate labels of length less than 100mm shall be fastened by means of an approved contact adhesive. Labels for cubicles and equipment mounted within 2.0m above floor level shall be positioned so that they can by read be a person of average height standing in front of the cubicles.

(c) Labels for devices mounted on or in enclosures shall be provided on the inside of the enclosure adjacent to the device as well as on the device. Device labels shall not be located on removable covers of the device.

(d) Warning labels shall be provided on or in all electrical equipment where terminals at 230V and above may be exposed during maintenance, indoor warning labels shall be of plastic laminate with white lettering on a red background. Outdoor warning labels shall be of vitreous enameled steel with white lettering on a red background.

(e) The text of each device label shall include the device number and a clear description of the function. Fuses, miniature circuit-breakers, and links shall be identified by their function, voltage, polarity, phase color and fuse link (or circuit-breaker) rating. The wording for labels shall be in the English language.

(2) Rating Plates

A rating plate complying with the requirements of the appropriate standard shall be provided on each item of plant. Where the rating plate is affixed to and item of plant of a mass in excess of 1 ton, it shall also specify the mass of the item.

(3) General

Failure to complete the supply and fixing of labels and rating plates shall be sufficient reason for the Engineer to withhold the issuing of the final Acceptance Certificate in accordance with the Conditions of Contract.

S1.12 PAINTING

Synthetic resin paint shall be used for the finish paint of all exposed portions of all the Equipment, except for the portion embedded in concrete, machined mating surfaces and galvanized surfaces.

The primary coat shall be of the kind matching the finish paint mentioned and shall be of rust preventive nature.

The exposed portions of all Equipment except those embedded in concrete shall receive shop finishes as detailed in this section.

Paints shall be applied only to surfaces which are free of moisture as determined by sight and touch. The ambient temperature shall be at least 5°C above the minimum temperature recommended by paint supplier for application on any coat.

The paint shall be applied using brush or spray techniques. When painting on any surface has commenced, the painting operation shall be completed as soon as practicable, without delays. The drying time between coats shall not be less than 12 hours.

The Contractor shall supply touchup paint to match all shop-painted items. This quantity shall be at least 15 percent of the paint used to the original shop painting, except for the control cubicles for which at least 30 percent of the original quantity of paint shall be supplied.

The color schedule for the Equipment will be decided by Munsell color notation.

The painting system referred to in these Specifications shall be as follows.

PAINT SYSTEM 1

Surfaces in Contract with Water

(a) General All surfaces shall be painted with an inorganic, epoxy zinc-rich primer and three coats of coal tar epoxy. Final shop painting shall not be applied within 100 mm of field welding. These areas will only receive one coat of inorganic, epoxy zinc - rich primer that can be removed prior to welding.

(b) Surface Preparation

Surfaces shall be blast-cleaned in accordance with SSPC-SP10.

(c) Paint Application

(i) Materials

The painting system shall consist of one coat of inorganic, epoxy zinc-rich primer and three coats of a compatible coal tar system.

All components shall be from the same supplier and the supplier's instructions shall be rigidly adhered to.

(ii) Film Thickness

The dry film thickness of the primer shall be between 0.05mm and 0.09mm. The dry film thickness of each of the coal tar epoxy coats shall be between 0.15mm. and 0.20mm.

(e) Final Film Thickness

The final thickness of the three coats shall be at least 0.45 mm. This shall be checked by a Type B film thickness gauge, supplied by the Contractor, calibrated on metal identical in composition, thickness and surface preparation and finish to that being painted. A sufficient number of measurements shall be made to establish the final thickness.

The entire painted surface shall be subject to electrical inspection by a holiday detector, furnished by the Contractor.

PAINT SYSTEM 2

Surfaces in Contact with oil

a) Surface Preparation

Surface shall be blast-cleaned in accordance with SSPC-SP10.

b) Paint Application

(i) Materials

The painting system shall consist of two coats of a high built epoxy paint suitable for this purpose.

c) Final Film Thickness

A sufficient number of readings with a gauge supplied by the Contractor shall be taken to ensure a minimum dry film thickness of 0.30mm is attained.

PAINT SYSTEM 3

Electrical Panels and Boards

a) Surface Preparation

Surfaces to be painted shall be blast-cleaned in accordance with SSPC-SP6.

b) Paint Application

a) Materials

The painting system shall comprise two coats of inorganic, zinc-chromate primer and two coats of epoxy enamel.

b) Film Thickness

The dry film thickness of the primer shall be not less than 0.80 mm. and the dry film thickness of the epoxy enamel shall be not less than 0.10 mm.

c) Final Film Thickness

A sufficient number of readings with a gauge supplied by the Contractor shall be taken to ensure that a minimum final film thickness of 0.25 mm. is attained.

PAINT SYSTEM 4 (FOR INDOOR STEEL WORK)

Mechanical Equipment, Prefabricated Piping

a) Surface Preparation

Surfaces to be painted shall be blast - cleaned in accordance with SSPC - SP10.

b) Paint Application

(i) Materials

The painting system shall comprise one coat of inorganic epoxy zinc-rich primer and two finish coats of acrylic latex, glossy finish paint.

(ii) Final Film Thickness

A sufficient number of readings with a gauge supplied by the Contractor shall be taken to ensure a minimum film total thickness of 0.30 mm. is attained.

METAL COATINGS

(a) Galvanizing shall be applied by the hot-dip process to ASTM A120, ASTM A123 and ASTM A153. Materials (such as welding slag, paint, and grease) likely to resist attack by the pickling liquid shall be removed prior to pickling. The surface after galvanizing shall carry an unbroken covering of zinc uniform in appearance and in thickness. The thickness shall be 0.09mm (0.6 kg/m^2)

(b) Electroplating shall be either nickel plus chromium plating, cadmium plating or zinc plating shall comply with the following:

(i) Nickel plus chromium plating shall be in accordance with ASTM B456. Nickel plating alone shall not be used.

(ii) Electroplating of zinc shall be in accordance with ASTM B633 and ASTM A164 (or) equal.

S1.13 LOCKING FACILITIES

(1) Where locking facilities are required to prevent unauthorized access to or operation of equipment, the facility shall be suitable of application of a padlock with 10mm shackle diameter and 35mm shackle opening.

(2) Integral locking facilities, e.g., of the key-in handle type will not be accepted and if normally fitted in proprietary equipment shall be removed or otherwise rendered inoperative.

S1.14 TROPICALIZATION

(1) General: All materials and equipment supplied under these Specifications shall be suitable for being delivered, stored, and operated under tropical conditions of elevated temperature, high humidity, heavy rainfall, mildew, and fungus conductive environment.

Process for tropicalization shall be in accordance with the best commercial and industrial practices.

(2) Metals: Iron and steel shall be painted of galvanized, or metal sprayed as appropriate. Indoor parts may alternatively have chromium or copper-nickel plantings, or other suitable protective finish. When it is necessary to use dissimilar metals in contacts, these shall so selected that the potential difference between them in the electrochemical series is not such as to cause galvanic corrosion. If this is not possible, the contact surface of one both of the metals shall be electro-plated or otherwise finished in such a manner that the potential difference is reduced within the required limits or, alternatively, the two metals shall be insulated from each other by a suitable insulating material or a coating of varnish compound.

(3) Bolts, Screws, Nuts, Washers: Steel bolts, screws, nuts, and washers when used, shall be zinc, cadmium or chromium plated or, where plating is not possible due to tolerance limitations, of corrosion-resisting steel. All wood screws shall be dull nickel-plated brass or of other suitable finish. Corrosion-resisting steel, copper-nickel alloy or bronze shall also be used for bolts and nuts when either or both are subject to frequent

adjustment or removal or are in contact with water and for bolts projecting from concrete with nuts to removal or vice versa.

(4) Fabrics, Cork, Paper, etc.: Fabrics, cork paper and similar materials, which are not subsequently protected by impregnation, shall be adequately treated with suitable fungicide. Sleeve and fabrics treated with linseed oil varnishes shall not be used.

(5) Adhesives: Adhesives shall be especially selected to ensure the use of types which are impervious to moisture, resistant to mold growth and not subject to the ravages of insects. Synthetic resin cement only shall be used for joining wood. Case in cement shall not be used.

(6) Electrical Material and Equipment: Materials and components which are inherently fungus resistant or are protected by hermetic sealing or oil immersion need not be treated. Other elements shall be protected by additional varnish for high humidity and given an antifungal treatment.

S1.15 MISCELLANEOUS METALWORK

The Contractor shall provide and install in respect of the Plant in his supply, the following miscellaneous metalwork.

(a) Soleplates, bedplates, foundation bolts and anchor bolts.

(b) floor plates and kerbing, including covers for pipe and cable trenches, required for completing the floors around and over the Plant.

(c) platforms, stairways, ladders, guards, handrails necessary for easy and safe access to the Plant requiring access for operation, maintenance, and testing.

(d) safety guards at each point where normal access would permit personnel to come within reach of any moving item of plant; and

(e) lifting lugs, eyebolts or other lifting attachment points on each item having a mass of more than 40 kg.

S1.16 EMBEDMENT, FOUNDATIONS AND PLINTHS

1) Except where otherwise stated,
   a) The Contractor shall provide the embedded supports and metalworks. They shall be consistent with dimensioned concrete outline and structural metalwork drawings. The Contractor shall ensure that adequate provision has been made in the civil drawings for the complete installation of his Plant and shall inform the contractor for the civil works of:

(i) Any required changes and the reasons.
(ii) Location and outlines of all metalwork to be embedded in the concrete.

b) Any equipment to be embedded shall be supplied to the civil works contractor not less than 3 months before construction work is programmed to commence in the area concerned.
c) Unless the Contractor informs the civil works contractor of his requirements not less than 3 months before work is programmed to commence in the area concerned, such additions or alternations to the civil works shall be made by the Contractor or, if the Engineer so requires, by the Department at the expense of the Contractor.
d) The Contractor shall be responsible for ensuring that any items which he requires to have embedded and any agreed alterations to the civil works, are conducted on site.

2) All scrabbling to a depth of 15 mm. grouting in of plant, grillages and steelwork, adjustment to foundation levels, grinding of foundations, bedding on foundations, and cementing into walls and floors, shall be carried out by the Contractor.

3) Equipment for mounting on floors shall be installed on concrete plinths to be constructed by the Contractor with the finished level up to 75mm above the floor level to cater for normal variations which will occur in foundations. With respect to his Plant, the Contractor shall supply all foundation bolts and packing plates between the concrete and the plant, equipment, and bases.

4) Plant which is mounted on the floor, and which does not require supporting steelwork grouted or embedded in the concrete foundation and plant which is surface mounted on concrete walls, or the lower face of concrete shall be fixed in position by approved masonry anchors. Masonry anchors shall be expansion type or resin adhesive type, shall be of adequate strength and corrosion-proof. The Contractor shall provide the fastenings and shall forward to the Engineer full details of the proposed masonry anchors including typical pull-out values and if requested shall submit samples for approval. Wooden, fiber of plastic plugs or similar type fixings will not be accepted.

5) Embedded parts installed by the Contractor shall be accurately placed and secured by the Contractor. The placing of the concrete around such items will be by others.

S1.17 POSITION OF INSTRUMENTS, CONTROLS AND HANDWHEELS

(1) Instruments shall be located conveniently for access and reading. Instruments which must be read frequently shall be located between 750mm and 1,800mm from the floor. Those which are read occasionally may be located between 500 mm and 2,000 mm from the floor.

(2) Controls and valve hand wheels shall be located conveniently for access and operation. In general controls should be within the range 750mm to 1,500mm and valve hand wheels 1,000mm to 1,500mm above floor level.

S1.18 FABRICATION AND WELDING

(1) General Requirements for Fabrication

The following requirements shall apply to all fabrication of components.

(a) Plates and sections shall be free of all surface marks or damage exceeding 1mm deep.

(b) Weld root gaps for partial penetration welds shall not exceed 1.5mm the dimensions of weld preparations, root gaps and plate alignment shall be to tolerances specified on the relevant drawings. All weld preparations shall be subject to examination for material flaws.

(c) Before welding, the weld preparation and plate surface for 15mm on either side of the preparation shall be completely cleaned to base metal including complete removal of any surface coating be abrasive blasting.

(d) Weld procedure and welder qualification tests shall be conducted in accordance with the approved standards. Where the standard does not specifically require weld procedure and/or welder qualification test, the Engineer may request the Contractor to submit details of the proposed weld procedures and of the qualifications of the proposed welder. The Engineer may at his discretion require that weld procedures and/or welder qualification tests be conducted in such cases. The Engineer reserves the right to call for further qualification tests and to withdrawn approval of any welder whose work is unseat is factory.

(e) Weld procedure and welder qualification tests shall reproduce the production conditions including preheat, electrode treatment, interpose temperature, degree of restraint and stress relief.

(f) Undercut not exceeding 1 mm. deep shall be removed by grinding; undercut exceeding 1 mm. deep shall be filled by welding.

(g) The surface of welds shall be smooth and free of sharp contour changes. The Contractor shall grind the surface of any weld as necessary in the opinion of the Engineer to avoid affecting the interpretation of non-destructive examination.

(h) Arc strikes on the place surface shall be avoided. Accidental are strikes shall be ground out and the area crack detected.

(i) Welded-on fabrication aids shall be kept to a minimum and shall be subject to the approval of the Engineer. They shall be attached only by approved welders using approved procedures and shall be removed by flame cutting not less than 1.5mm above the parent plate surface and then by subsequent grinding and crack-detecting of the weld area.

(j) Butt welds shall be free from under filling and from reinforcement greater than one-tenth the face width of the weld. All undercuts shall be filled by welding.

(k) Wherever practicable, welding shall be conducted in the down hand position.

(l) Weld spatter shall be completely removed. Machined surfaces and tapped holes shall be adequately protected from spatter during welding.

(m) Joints not completely protected from the weather or in a corrosive environment shall be seal welded. Unless otherwise approved, welds between dissimilar metals shall be performed at the Contractor's premises.

(n) Electrodes shall be stored and dried before use strictly in accordance with the electrode manufacturer's recommendation and welding code requirements.

(o) Preheat and interpose temperatures shall be applied in accordance with the electrode and steel manufacturer's recommendation and with the weld procedure tests. Measurements shall be by temper sticks or surface pyrometer on the opposite side of the plate surface pyrometer on the opposite side of the plate surface from that to which heating is being applied.

(2) Further Requirements for Important Stressed Components

The important stressed components shall mean those components whose failure would endanger the operation of plant or the safety of personnel. They shall include but shall not necessarily be confined to:

(a) components or parts there of including welds which are stressed to greater than 40 percent of yield stress in normal or abnormal service conditions.

(b) components which are stressed directly or indirectly be pressure conduit or tailwater pressure, operating oil pressure or air pressure.

(c) all rotating parts of main plant (generator and turbine but excluding auxiliaries)

(d) bearings and their support systems; and

(e) lifting equipment, crane girders and crabs.

The following further requirements shall apply to the important stressed components in addition to the requirements in sub-clause (1) of this Clause.

(i) All plate materials and sections shall be identified by heat number at all phases of fabrication and erection. They shall be checked ultrasonically for internal defects.
(ii) As far as practicable, all shop-welded fabrication shall be stress relieved.
(iii) As far as practicable, all welds shall be full penetration, back gouged and of a configuration which lends itself to radiographic or ultrasonic examination.

(3) Non-destructive Testing of Welds in Steel Components

(a) All full penetration welds in important stressed components shall be examined for their full length radiographically or ultrasonically. In general, this examination shall be by radiography for butt welds and by ultrasonic for tee-welds. The examination methods and the standard of acceptability shall be in accordance with Section V of the ASME Code.

(b) In addition, a percentage of all other welds shall be examined ultrasonically or radiographically. The examination methods, extent of examination and standard of acceptability shall be in accordance with Section V of the ASME Code or AWS Code.

(c) The toes of all fillet welds in important stressed components shall be subject to crack-detection.

(d) Radiography of welds shall be conducted in accordance with Section V of the ASME Code.

(e) The Contractor shall submit radiographs and reports to the Engineer within seven calendar days of the taking of radiographs. The reports shall contain complete identification of the component concerned, definition of the location of the radiographed areas, full description of the radiographic techniques and report on all indications of the film.

(f) Ultrasonic techniques and acceptability of defects found by ultrasonic examination shall be in accordance with ASTM A435.

(g) Welds in which unacceptable defects are found by radiography or ultrasonic examination shall be subject to re-examination by the same respective method after repair.

(4) Non-destructive Testing of Welds in Aluminum Components

Such welds shall be evaluated generally in accordance with Section V of the ASME Code. The actual scope of tests shall be to the approval of the Engineer, dependent on the design and function of the components concerned.

S1.19 PIPING, VALVES AND THREADED FASTENERS

(1) General: All piping, valves and threaded fasteners shall be designed according to ANSI Standards; the pipes shall be in accordance with ANSI B 31.1; all flanges shall be of raised face (RF) designed according to ANSI B 16.5.

Screwed joints may be used for pipes up to 50 mm. diameter at working pressures not exceeding 7kg/cm^2. Pipes of 25mm. diameter and less for working pressures exceeding 7 kg/cm^2 shall be joined by unions of approved type.

The working pressure of a system shall be taken as the maximum pressure it can attain including water hammer and/or relief valve blow-off pressure.

The pipe diameters shall be calculated considering the following maximum allowable speeds:

- Air 15m/s and 5 m/s in between compressors and receivers.
- Oil and water at the suction side m/s
- Oil and water at the pressure side 2.5 m/s

The thicknesses of the pipes shall be calculated following the ANSI requirements; at least 3 (three) millimeters for corrosion shall be considered for the water and air piping and 1 (one) millimeter for the oil piping.

All piping 100 mm nominal diameter and larger shall be completely prefabricated at Contractor's workshop with all fittings in place except that extra length for field cutting and welding shall be provided where required for field assembly.

Piping with flanged connections shall be furnished with gaskets, bolts, studs and nuts. All pipes up to 50 mm. nominal diameter shall be assembled by means of threaded or socket welded fittings. Threaded and socket welded pipe will be Site fabricated, as erection proceeds.

Piping systems shall be complete with fittings, valves, supports and all necessary accessories. Piping arrangement shall be neat in appearance and shall allow a convenient operation. Items requiring periodic attention shall be easily and readily accessible from floors or platforms. Pipes shall neither obstruct pass ways nor interfere with access to valves and equipment.

The piping buried in the concrete shall be sloped for drainage and provided with 25mm diameter drain valves at all low points in the system.

The supports, hangers, anchors and clamps necessary to support and restrain all pipes and valves shall be designed, selected and located in order to ensure uniform continuous slopes for draining and minimize stresses in the piping material, and to let

the piping system be safely supported, guided and anchored especially for the pipes to be laid in the pier trench.

All items to be site welded to the piping shall be of the same material as that of the relevant piping.

As far as practicable, the supports shall be grouped and of consistent design throughout.

The Contractor shall submit for approval drawings showing.

- the piping flow diagram
- the piping P and I diagram
- the piping layouts

The Contractor's calculations of the piping diameters and thickness shall be available for approval at the Engineer's request.

Asymmetric sketches shall be supplied for site erection.

(2) Pipes: Pipes shall be in accordance with the ASTM A 53 Grade B standard specification or approved equivalent for welded and seamless steel pipe. Type S, seamless pipes will be preferred. Longitudinal welded pipes type E, electric resistance welded pipes are subject to approval.

All pipes shall be shipped with the ends plugged by plastic covers.

The beveled ends to be welded at site shall be protected by a special paint compatible with the welding.

Elbows having radius at least 1.5 times of nominal diameter shall be used for changes in the direction of piping having 75mm nominal diameter and over. For piping having 50mm nominal diameter and below commercial fittings shall be used. Bends having radius not less than 5 nominal diameters instead of ells may be used.

Minimum wall thickness at any point of the elbows, bends and ells shall not be less than the minimum wall thickness allowed for pipes.

Shop prefabricated pieces may be employed for tee reducers, drain and other special pieces. Materials and thickness shall be the same as for the straight pipe. Branch connections shall be reinforced where necessary in accordance with the requirements of ANSI B 31.1 "Code for Pressure Piping"

For piping having 50 mm nominal diameter and over, seamless type fittings such as tee, reducers and cap shall be used for intersection of piping, piping branches, changes in size and end closure. Metered fittings and metered bends will not be accepted.

(3) Valves: All the valves shall be of the flanged type, made of carbon steel with stem and sealing rings of stainless steel, all valves shall be provided with back seated items.

Valves nominal diameter shall always be equal to the relevant pipe diameter.

Seals and seats shall be positively fixed so that they cannot become loose in service. The fixing of seals and seats by an interference fit only is not acceptable.

The operating mechanism shall have means of lubrication and position indicators and, in the case of isolating valves, the means of padlocking in the open and closed positions together with approved padlocks and keys.

All hand-operated valves shall close by clockwise rotation of the hand wheels which shall be marked to show the direction of closing. Valve hand wheels shall be located for safe and convenient operation with extended spindles where necessary to achieve this. All hand operated valves shall be capable of being opened and closed against their maximum working pressure fully unbalanced with a force at the hand wheel not exceeding 100N. If necessary to achieve this, reduction gearing, ball or roller bearings shall be provided.

As far as practicable, all valves for similar service shall be of the same make and type and be interchangeable.

All gate valves for water and air service shall be of a type in which the operating mechanism is not subject to the working fluid.

Valves other than needle type shall not be used permanently if the need for throttling is foreseen, such as to adjust flow subdivision in a system, orifice plates or needle valves with fixed stops shall be provided.

Valves for water and oil service may be gate, butterfly, ball, plug or needle type, whichever is most suitable to the particular service and operating pressure.

Valves for air service may be ball, plug or needle type whichever is most suited to the particular service.

Non-return valves shall be of a type specifically designed to avoid impact and water hammer on closure. The closing member shall be pivoted from the valve body, not from a lid cover.

Relief valves for pumps shall be of direct spring loaded, angle body type.

For identification, each valve of 150mm N.D. and over shall be provided with stainless steel identification disc on the hand wheel.

Valves below 150mm N.D. shall be identified with size and ANSI class and shall be written in English.

(4) Threaded Fasteners: The threaded fasteners shall comply with ISO metric system and with the following requirements:

- steel bolts shall be forged unless otherwise approved
- mild steel fasteners shall be zinc or cadmium plated
- all parts shall be spot-faced or machined for nuts or bolts except in the case of clearance bolts in structural steelwork
- tapped holes shall not be used in sheet metal less than 6mm thick
- fasteners of less than 6 mm. diameter shall not be used except in instruments and relays
- threaded fasteners of more than 8 mm diameter shall have hexagon or socket hexagon heads
- all threaded fasteners subject to vibrations and/or installed in a position which is unable to be inspected during operation shall be locked in an approved manner.

S1.20 CASTING AND PATTERNS

(1) All steel castings shall be annealed in accordance with the relevant standard. All iron castings shall be mild annealed in a suitable annealing furnace to relieve casting strain before being machined.

(2) The Contractor shall retain all patterns required for the production of the Plant at least until the end of the maintenance period.

S1.21 LUBRICATION

(1) The Contractor shall submit, for the approval of the Engineer, a complete list of the lubricants recommended for each part of the Plant; this list shall give the type and grade of each lubricant in sufficient detail to permit the correct lubricant to be supplied from normal commercial domestic sources. As far as possible the types of lubricant required for the plant shall be reduced to a minimum.

(2) All lubricants and flushing oils required for the plant up to the time of taking over shall be provided by the Contractor.

(3) The Contractor shall nominate a minimum number of standard size grease nipples which shall be used for all Plant.

(4) The filling points for lubricating oil systems shall be provided with fine gauze filters beneath the filling caps to prevent the entry of dust.

(5) Drip trays shall be provided beneath oil filling and drain points and any other locations subject to oil leakage or spillage.

(6) The filling and drainage points shall be located so that they are conveniently accessible. Adequate working space shall be provided for the positioning of buckets, hoses and other appliances used for filling and drainage.

S1.22 SELF-LUBRICATING BUSHES

(1) Where self-lubricating bushes are specified, they shall be as follows:

(a) For applications subject to immersion or to weather, - bronze with lubricating insert ('Lubrite' by Merriman, Hingham USA or equivalent). The lubricant shall have long-term resistance to deterioration when exposed to atmosphere and water in a tropical climate.

(b) For indoor, nominally dry application - as in paragraph (a) of this sub-clause or epoxy resin with glass mesh reinforcement and hard chromium plated and ground journals.

(2) The use of 'Teflon' or similar materials and the use of materials which promote electrochemical action, is not acceptable.

S1.23 TEST, GENERAL REQUIREMENTS

(1) Test During Manufacture - General:

a) All Plant materials and components shall be subject to type, sample and routine tests and inspection while in the process of and upon completion of manufacture at the Contractor's premises in accordance with this Specification and the Conditions of Contract. Tests listed in the Standards as optional tests (to be performed if specified at the time of ordering) are required to be performed unless otherwise stated.

b) The Department, its representative and/or the Engineer will visit the factory of the Contractor during manufacturing and factory tests. The attendance to the Contractor's factory for any purpose by The Department, its representative and/or the Engineer shall not in any way release the Contractor of any of his obligations under the Contract until the final acceptance certificate is issued. Some factory tests, if so, permitted by prior approval of the Engineer, may be performed without the presence of The Department, its representative and/or the Engineer.

c) The Contractor shall bear the costs for the following engineers from the Department factory acceptance test (FAT) at the factory which shall include round-trip economy class air fare from Bangkok to the factory, local

transportation cost, lodging and meals and other miscellaneous expenses necessary for the purpose of the trip as the witness acceptance test for only the equipment manufactured in abroad. The costs for this factory acceptance shall be included in the bid price.

(i)	for turbines	minimum two (2) engineers
(ii)	for generators	minimum two (2) engineers
(iii)	for associated equipment	minimum two (2) engineers

d) It is the intention of the Department. to acquire the services of a qualified inspection company to conduct expediting services, inspection company to conduct expediting services, inspection during manufacture and attendance at factory tests. The Contractor is required to provide all reasonable facilities including advance notice (at least thirty (30) days) of all testing dates in order that the said inspection company may fulfill all of its duties as required under the contract to be made between the Department and the inspection company. The attendance of the inspection company at the Contractor's factory during fabrication and at factory tests shall not relieve any of the obligations of the Contractor under this Contract.

e) Type, sample and routine tests shall be to the relevant American Standards or other approved standards for equipment where the test requirements are not specified in this Specification.

f) The Contractor may offer type test results for identical equipment in lieu of the type tests specified, in which case the specified type tests may be waived by the Engineer. If type test results for identical equipment are offered in lieu of the specified type tests, the Contractor shall also provide evidence as to the similarity of the equipment tested and the Contract Plant.

g) The Contractor shall submit evidence to the Engineer that the instruments used for the tests have been calibrated at an approved testing laboratory within a period of up to 3months for a portable instrument and 6 months for a fixed instrument.

h) The Contractor shall submit to the Engineer 4 certified copies of all results of all tests required under the Contract. The results of each test shall be recorded in the form of test certificates or test reports.

i) The results of tests shall be submitted to the Engineer within 1 month of the tests being conducted.

j) In the event of any test piece failing to comply with the requirements of the Contract, the Engineer may reject the whole of the material represented by the test piece.

(2) Tests at Site - General

a) Responsibility for Tests

(i) The Contractor shall conduct the Tests at Site

(ii) The Contractor shall provide everything required to conduct the tests, including the provision, installation, and removal of all test instruments, and obtaining of all records. The Contractor shall provide certified test certificates to prove that all instruments have been calibrated by an approved laboratory not more than 3 months prior to conducting the tests. The Contractor must specify items of testing equipment to be handed over to the Department.

(iii) The Contractor shall prepare and submit the program to the Engineer for approval, schedules for each test together with a program for the Tests on Completion.

(iv) The Contractor shall submit one copy of the results of each of the Tests at Site to the Resident Engineer at Site within one week of the tests being conducted. Four copies of the certified results of each of the Tests at Site in the form of test reports or test certificates shall be provided to the Engineer within one month of the tests being conducted.

(v) The Department's staff may observe or participate in the Tests on Completion.

b) Scope of Tests

The Tests at Site to be carried out and passed before taking over of the Works by the Administration shall be deemed to comprise two main stages of testing as follows:

i. Preliminary tests which are tests performed prior to rotation of, energizing at normal voltage or admission of normal water or air pressure to the main or ancillary Plant under test.
ii. The Tests on Completion which are tests to progressively prove the correct operation of complete ancillary systems and of the main Plant items.

The Tests on Completion shall include, immediately following all other tests, a test of service performance including 50 hours running. Where appropriate, the plant shall be connected to the PEA power system. The test shall include a total of 50 starting and stopping sequences. The service performance tests shall be completed without adjustment and without fault. This shall be a prerequisite for taking-over.

S1.24 ELECTRICAL EQUIPMENT

(1) Motors

All motors shall be totally enclosed, fan-cooled type with provision for lubrication, suitable for operation in high ambient temperatures and high humidity conditions. Motors up to and including 1/2 hp shall be 220V, single-phase. The exception to this will be motors on the emergency "essential services" but that must be 380V, 3phases. All motors above 1/2 hp shall be 380V, 3-phase.

Unless otherwise specified, induction motors shall be of the direct-line starting, drip-proof type, and when operated, shall not develop trouble under a voltage fluctuation of +10 percent. The induction motors shall not be affected by a rise of 30 or 40 percent in voltage and frequency due to a full load rejection of the unit.

Motors shall be
- normal starting torque
- low starting current
- squirrel-cage induction type
- designed for full voltage starting
- drip tight or weatherproof
- totally enclosed.

Would rotor motors will be acceptable only if a squirrel-cage type were not satisfactory for the duty. The motors shall have Class B, 80°C temperature rise and continuous rating at 40°C ambient temperature and class F insulation. Motor lead insulation shall be Class B and cable terminal boxes shall be provided preferable with stud type connectors.

(2) Magnetic Motor Starters

Magnetic motor starters shall have the following features and/or accessories:

(a) molded case circuit breaker disconnects with thermal time delay and instantaneous trips

(b) individual fused control transformer

(c) operating coil

(d) thermal overload protection in each phase temperature compensated with thermal elements correctly related to motor nameplate, current and type of enclosure

(e) auxiliary contacts for the control of related auxiliary devices such as motor heating, indicating lights, inter-locks, etc.

All starters shall be suitable for across-the-line starting of motors with manual resetting and under voltage release features.

All motors of 25hp and above shall be provided with ammeters with suppressed scale for starting current and have motor full-load current deflection at two-thirds of the scale.

All motors shall be provided with quick-break molded case circuit breakers with operating handle lockable in OFF position. They shall be rated to interrupt the full-load current of motor or other equipment in the circuit.

Magnetic contactors used in various switches shall be made of arc-resistant metal and have sufficient capacity against current onrush. The contacts shall be designed to obtain high contact pressure and positive seating to reduce contact bounce.

(3) Relays and Devices

Electric contacts of dial type thermometers, thermal relays, oil level relays, oil pressure relays, air pressure relays, limit switches, etc., shall be able to safely break a current of possible maximum inductive load (2A) and 48 or 110 or 125V dc.

The relays (control, protection, and auxiliary relays) and meters shall be air-sealed to prevent corrosion by hydrogen sulfide gas which will occur after water is impounded in the reservoir.

Mechanical targets (operated at 125V dc) shall be individually provided with any equipment that is annunciated as a group due to a faulty condition. In this manner the faulty equipment can be easily identified.

(4) Molded Case Circuit Breakers

All molded case circuit breakers shall have 2 or 3 poles as required, having thermal time delay and instantaneous trips with ON-TRIP-OFF indicating operating mechanisms. Circuit breakers used in conjunction with motor starters or contractors shall have the operating mechanisms interlocked with the starter or contractor cover, so that the cover cannot be opened unless the circuit breaker is open.

Circuit breakers shall be bolt-in type, interchangeable, temperature compensated, quick-make, quick-break type and shall comply with NEMA standards.

A group alarm contact shall annunciate an open breaker and each breaker shall have an individual light which shall come on when the breaker is open.

(5) Pilot Devices

Pilot devices such as selector switches, push-button stations, thermostats, etc., shall be of the heavy duty, oil tight type, housed in a dust-tight enclosure designed especially for the type of environmental. Local stop buttons neat the motors shall be lockable in pressed position for maintenance.

(6) Indicating Lights

All indicating lights shall be of LED type (E12) long life and service under conditions of shock, vibration and rough handling unless otherwise specified.

(7) Instruments and Meters

All instruments and meters shall have approximately 110mm dials, shall be of heavy-duty industrial type, suitable for withstanding extreme shock and severe vibration.

(8) Convenience Outlets

Convenience outlets in the control cabinets shall be duplex 3-pin type rated for 15 or 20A at 250V, suitable for Thailand pattern plug as approved by the Engineer.

(9) Pressure, Level and Flow Switches

The sensing switches shall have weather proofed or dustproof enclosures and shall be mounted for easy adjustment and for rigidly cocking in position after being adjusted. They shall be of heavy-duty rating and shall have stainless steel rotating parts and permanently lubricated bearings.

(10) Electrical Enclosures

As indicated in this Specification sections, electrical enclosures shall be complied as follows:

The construction of electrical enclosures located in areas subject to conditions classified in the National Electrical Code as hazardous shall be of a type designated by IEC or NEMA or equivalent as suitable for the environment in which they are located.

Electrical switchboards, panels, and cabinets, except those of cast metal, shall be constructed from steel plate reinforced as required to provide true surface and adequate support for devices mounted thereon. Thickness of the steel plate shall conform to the requirements of UL50. Switchboards, panels, and cabinets shall be of

adequate strength to support mounted components during shipment and to support a concentrated load of 91 kilograms on their top after erection.

Anti-condensation heaters of 220Vac complete with switch, shall be provided in enclosure containing control or relay equipment, except when the external surface area is less than 0.5m^2 (excluding the bottom).

The rating of the heaters shall be at least 20W for each compartment of the enclosure. Where the heat produced by the equipment during normal operation is equal to or greater than the output of the heater a thermostat shall be provided to control the heater.

All enclosures fitted with anti-condensation heaters shall have ventilation openings in the doors which shall be screened with vermin-proof and insect-proof fine brass gauze or a suitable filter and arranged to minimize entry of dust and prevent entry of water. Sealing of doors and covers shall be by closed cell neoprene foam sections on to surfaces at least as wide as the sealing section; water absorbent materials is not acceptable for seals.

Lighting shall be provided inside each enclosure large enough for a man to work inside. Luminaries shall be controlled by a fully enclosed door-actuated switch.

Where an enclosure contains fluids under pressure, compartments shall be provided to prevent damage to equipment by fluid leakage or discharges.

Finish painting inside enclosures shall be gloss white. The finished surfaces outside shall present a first-class appearance of uniform color to adjacent enclosures. Equipment contained in enclosures shall be finish painted as if it were exposed to view.

A label showing the cubicle abbreviation shall be provided on the outside rear or cabling side of each enclosure.

(11) Ground Buses

A 4mm by 25mm cross-section bars copper ground bus shall be provided at the bottom of each enclosure to which the metallic cases of meters, instruments, relays, and grounding circuits of all other equipment shall be connected. The ground buses shall be solidly bolted to the steel framework so as to make good electrical contact. Solderless lug or terminals shall be provided on the ground buses for terminating the copper ground cables from the grounding systems.

(12) Wiring

The wiring of the control cabinets, control boards, cubicles and control boxes for auxiliary equipment shall conform to the IEC or NEC or NEMA standards, shall be

stranded copper switchboard wire, PVC insulated. All wiring shall be 2.5mm^2 except for current transformer circuits which shall be 6mm^2. All hinged wiring shall be extra flexible. The small wiring used in the semiconductor circuit will be excluded. The wiring for all instruments, relays and auxiliary devices of equipment and accessories shall be connected by ring tongue, crimp style terminals (amp terminal). All wiring shall be neatly and carefully installed in suitable wiring ducts with removable covers and complete to conveniently located terminal blocks for connecting to incoming and outgoing leads.

The terminal arrangement shall group all leads to facilitate connections to the incoming cables. Not less than 20 percent spare terminals shall be provided on each group of terminal blocks for terminating spare conductors in control cables and for future use.

Both ends of all wires shall be provided with terminal number rings and the number shall be recorded in the wiring diagram.

The interior wiring shall be concentrated on terminal blocks installed at a convenient height in the equipment or control cabinets in order to facilitate external cable connections. Wire runs shall be neatly trunked inside the switchgear or in wiring troughs. Conductor connections shall not be soldered except for essential requirements.

The terminals of motors or other equipment shall have pressure compression type terminal lugs.

The following color identification shall be applied to the insulation of wires used for back wiring of control cabinets, control boards, cubicles, control boxes and auxiliary equipments.

- Secondary circuit of potential transformer - red
- Secondary circuit of current transformer - black
- dc circuit - blue
- ac circuit except power circuit - yellow
- Neutral - green

Three-phase outgoing cables shall be color coded as follows.
- Phase 1 - black
- Phase 2 - white
- Phase 3 - red
- Neutral - green

Direct current shall be color coded as follows.
- Positive - white
- Negative - black

(13) Terminal Blocks

Terminal blocks shall be of the 600V molded block type with insulating barrier between terminals. Terminal blocks for current transformer secondary circuit shall be of short-circuit type. Terminal blocks shall be attached with a cover and the terminal number. Each terminal block shall have marking strips and shall be equipped with crimp style terminals for 2.5 m^2. or more. Terminal blocks shall be provided with at least 25 percent surplus terminals as spares for each control board and cabinet. No more than two wires shall be connected to one terminal.

Terminal blocks shall be located in such a way that the incoming cables shall terminate neatly and conveniently. All numbered terminals on the schematic diagrams shall be brought out to the terminal block and labeled accordingly.

(14) Cables and Conduits

The Contractor shall furnish all control and power cables which will be used for controlling, operating, and supplying power for Equipment of the power plant. The Contractor shall supply all conduits, accessories and fittings which will be required for laying the cables.

The Contractor shall allow for the following minimum of spare cores in each multi-core control cable.

NUMBER OF CORES IN CABLE	MINIMUM NUMBER OF SPARE CORES
Up to 5	-
Up to 12	2
Up to 20	4
Over 20	6

S1.25 OPERATOR TRAINING

The Contractor shall instruct the Department's operation staffs for the operation and maintenance training of the plant equipment during commissioning heat run period after completion of all site tests. The Contractor shall satisfy himself and the Engineer that the Department's staff are fully capable of operating and maintaining the Plant before leaving the Site. The cost of these services shall be included in the Contract Price.

SECTION 2 - TURBINES AND GOVERNORS

S2.01 SCOPE OF WORK

The scope of work under this clause shall consist of design, manufacture, shop test, supply, delivery, and installation, field test, placing in successful operation, commissioning, and guarantee of the following turbines, governors, and auxiliary equipment.

(a) Two single-runner, horizontal, Pelton type turbines.
(b) Two electronic PID type governors complete with pressure oil system.
(c) The spare parts for turbine, governor, and auxiliary equipment.

The Contractor shall supply all the necessary switches, contactors, magnetic starters and relays with the turbine, governor, and electrical auxiliaries. All electric items supplied by the Contractor shall be standard manufactured items available from stock. The Contractor shall provide all terminal boxes required and shall provide all wiring and conduit from the electrical components to these terminal boxes.

Hill curve (or) Turbine Prototype Performance Curves indicating Allowable Operating Range, turbine prototype efficiency, needle valve opening, output and discharge against net head shall be submitted together with the Bid and the curves which consistent with the guarantees relating to efficiency and output shall also be submitted.

Oil Pressure Control System Diagram for Governor including Component Arrangement, P&I Diagram indicating Cooling Water System related with this specification shall also be submitted with the Bid.

Failure to submit the above information will subject to rejection of the Bid Proposal.

S2.02 TURBINE

(1) Type
Single runner, Pelton, Horizontal installation, mono-block in single piece type Turbine and the pelton runner shall be overhung and directly mounted on the generator shaft without any bearing housing attached to the turbine casing.

(2) Design Data
The main design data of the turbine shall be as follows:

(a) Net Head (m)
Design 179.48

(b) Discharge (m^3/sec)
Design (each) 2 x 0.517

1) Capacity (kW)

Guaranteed Values under net head:	
Design (each)	not less than 819.5 kW

(d) Efficiency (%)

Minimum guaranteed values under design net head and design kW:	90

(e) Frequency of Rotation (rpm)

Rated	To be proposed by the Bidder

(f) Elevation of Turbine Shaft (m MSL)

Centerline	+71.00 (approximate)

(g) Direction of Rotation

View from generator	Clockwise

(h) Couple to Generator	Runner directly mounted on generator shaft

(3) Requirements for Design and Characteristics

(a) General: The turbine shall operate at any gate opening, under any head and under tail water level as specified without unacceptable torque and/or pressure oscillations and without unacceptable cavitation.

The best turbine efficiency shall be obtained between 80 percent and 100 percent of full gate opening under 179.48 m design net head. The derivation of guaranteed efficiency shall be fully substantiated in the Bid preferably by certified results of tests on prototype and/or model turbine homologous with those offered, together with a full account and justification of the method used in translating these results to the efficiencies guaranteed for the turbines offered for this project.

The Contractor shall perform Computational Fluid Dynamics (CFD), the analytical and numerical calculations (or) mathematical model in manufacturer's laboratory to verify that the selected runner model and the designed hydraulic shape of manifold, distributors with injectors to reduce flow energy losses, to get the equal flow rate in distributors, the least pressure distribution in runner buckets and the best guaranteed output with highest efficiency values according to Schedule 8 Guarantee and Informative Data and the specifications stated in this section.

The Contractor shall also perform the Presentation of CFD (or) mathematical model at manufacturer's factory during DEDE visit for factory acceptance test (FAT) before delivery of equipment to verify the turbine output and efficiency.

The Bidder shall submit the procedures and methods of this verification for at least two (2) optimization points to calculate and verify turbine performance for similar turbine type performed (or) similar model report performed for prototype turbine to verify that the proposed manufacturer has enough capability to manufacture and guarantee the performance of the proposed turbine model in this contract.

(b) The total stored energy constant of the generator and turbine shall be not less than the minimum necessary for stable governing and the attainment of the specified and guaranteed pressure rise and speed rise.

The Bidder shall submit with the Bid for calculation of speed rise, pressure rise and GD^2 needed for operating with isolated Dummy Load Test and parallel operation together with flywheel weight and dimension installed at the generator verifying that the Bidder's proposed system can be connected and operated with the 22kV PEA Grid system without any problem to the supplied equipment during emergency shutdown as well as without any hunting when synchronizing and connecting to the existing grid system.

Failure to submit this will subject to rejection of Bid Proposal.

(c) Frequency Regulation

The Contractor shall guarantee the maximum transient frequency change which will result from an instantaneous change of 50 Hz in any initially steady isolated load having a self regulation coefficient of 1.0, being supplied by one turbine, or both with the permanent speed droop of 3 percent. The Bidder shall submit calculation to justify the regulation.

(d) Speed Regulation

The Contractor shall guarantee the maximum momentary speed rise which can occur when the generator output corresponding to 100 percent gate opening at maximum gross head is instantaneously rejected from both units with a permanent speed drop of 3 percent. The maximum runaway speed rise shall not exceed 2.0 time of the rated speed. The Bidder shall submit the speed rise values to justify the regulation with the Bid.

(e) Pressure Regulation

The Contractor shall guarantee that the maximum gauge pressure which can occur in the pressure conduit or turbine on instantaneous rejection of any load of which the units capable, shall not exceed 269.22 m of water measured at the penstock nearby turbine unit. This guarantee shall apply under all conditions of normal operation (i.e., all plant functions correctly). The Bidder shall submit the calculation to justify the regulation and submit with the Bid.

(f) Turbine Housing/ Casing

Turbine Housing and base frame shall be designed to support the base static loads and dynamic forces due to operation and installed independently on the powerhouse floor without embedded in the concrete not to occur any correction or modification works for civil work structures.

Turbine housing shall be made of welded steel structure with stiffener reinforcement. The turbine housing and the distributor pipe or nozzle pipes shall be fabricated with flange connection and shall be removable during transportation.

One (1) Inspection hole shall be included in the turbine casing for maintenance purposes, and which shall not be less than 500 mm in diameter.

(g) Operating Mechanism and Components

a) Operating Mechanism of the turbine shall be controlled only by needle valve operated by servomotor (or) hydraulic cylinder and deflector to be closed in normal stop and emergency stop condition after the closing needle valve (s).

b) Nozzle pipe injector, elbow and joints shall be fabricated with steel and shall be provided with flange connection to connect with turbine casing using gasket seal (or) O ring Seals.

(h) Nozzle Mouth, Needle and Needle Shaft

The nozzle mouthpiece, needle and needle shaft shall be made of high strength stainless steel and fixed in the maintenance free slide bearing bushes sealed with two sealing rings to prevent water leakage. The needle shall be equipped with thread, and it shall be easily replaceable.

The nozzle needle shall be operated and controlled by hydraulic cylinder (or) servomotor with micro pulse type linear transducer with rod for feedback

position control so that feedback signal (4-20mA) for each needle shall be sent to Governor PLC.

Mechanical position indicator in % (or) millimeter scale for needle opening indication and which shall also be calibrated at turbine factory before delivery of the Units.

(i) Jet Deflector

Jet deflector shall be made of a spherical hardened stainless steel to achieve maximum strength protection against wear and abrasion. It shall be operated and controlled by hydraulic cylinder (or) servomotor and guided with maintenance free slide bearing (made of bronze) with limit switches for its open/ close feedback positions to Digital Governor PLC.

Pivot joints of the deflector mechanism shall be provided with self-lubricating bushing and the pin, bolts and nuts shall also be stainless steel for easy replacement.

Counterweights are also allowed to be used for closing action in case of emergency stop condition.

(j) Servomotor/ Hydraulic Cylinder

The casing of cylinder shall be machined and polished over all internal surfaces. The piston shall be equipped guide ring with seal. The cylinder rod shall be made of stainless steel over full length.

(k) Turbine Shaft and bearing

The Pelton runner shall be directly mounted at generator shaft so that turbine shaft bearing is not applicable.

(4) Turbine Dismantling Arrangement

All major turbine parts shall be provided with eyebolts, lugs or lifting devices. Provision shall be made to support the turbine shaft and runner during erection and dismantling.

(5) Runner

(a) The runner shall be made of water resistance chrome nickel steel, forged mono-block in single piece casting, machine, fine ground and polished having wear and corrosion resistance Chrome-Nike-Steel (X3CrNiMo 13-4) or higher grade of material for strength shall be used

(b) The runner shall be manufactured by using a minimum of 5-axis CNC milling machine for highest precision profile with lowest manufacturing tolerances so that any welding or casting is not allowed for Runner. Furthermore, the final the proper polishing process shall also be applied to achieve smooth surface condition.

Evidence for proofing this shall be submitted with the Bid proposal.

(c) Each runner complete with runner seals shall be statically and dynamically balanced and the runner material verification and balancing report shall be submitted to DEDE during the manufacturing period and before delivery. The runner shall be dynamically balanced and mounted directly on the extended shaft of Generator by means of a shrinking connection device / key so that the generator shaft shall be designed precisely to be fitted together during engineering stage and delivered separately to project site.

(d) They shall be aligned and assembled at site during the installation period under manufacturer's supervision at the Contractor's premises.

(6) Turbine Setting

(a) Each runner complete with runner seals shall be statically and dynamically balanced and the runner material verification and balancing report shall be submitted to DEDE during the manufacturing period and before delivery. The runner and generator shaft shall be designed precisely to be fitted together during engineering stage and delivered separately to project site.

(b) They shall be aligned and assembled at site during the installation period under manufacturer's supervision at the Contractor's premises.

(7) Local Turbine Control Cubicle

1) Construction

The cubicle shall be made of steel plate not less than 2.0 mm in thickness. A hinged door shall be provided on one side of the cubicle, and, on the other side, the cubicle shall be installed nearby turbine unit at turbine floor. Front and rear hinged doors, all necessary wiring shall be provided. The Cubicle shall be installed nearby Turbine-Generator and shall be equipped with indicating lamps, instrumentation, and connecting terminals used for interconnection between field turbine instruments and Governor PLC input/ output modules.

(b) Instruments to be connected with the Cubicle

The following signals shall be connected to the cubicle and shall send their commands, signals, and data values to Governor PLC for control and monitoring purpose: -

1) Penstock pressure
2) Distributor pressure
3) Hydraulic pressure
4) Governor oil tank level
5) Oil filter signals
6) Oil flow switch
7) Oil pressures
8) Oil temperatures
9) Oil flow signals
10) Turbine signals
11) Inlet Valve signals
12) Bypass valve signals
13) Governor oil pump signals
14) Cooling water system signals
15) Lubrication oil temperature (if applicable)
16) Lubrication oil tank level (if applicable)
17) Lubrication system signals
18) Speed signals

The above signals from the field instruments can also be connected directly to Governor PLC Cubicle without using Turbine Control Instrument Cubicle and the details shall be submitted for DEDE approval during engineering design stage.

(8) Protection and Alarms

(a) The Contractor shall provide protection functions for Generating Unit as per the “Protection and Relaying Functions” specified under Control, Protection and Alarm Section as well as the applicable international standards.

2) In addition to the devices listed, the Bidder/ Contractor shall provide such other protection and alarm devices of all necessary for the safe unit operation of the turbine, governor, inlet valve and ancillaries shall be available in international market including all distributors or re-seller or aftersales service available to purchase in Thailand.

S2.03 GOVERNOR

(1) Type

(a) The turbine shall be provided with the digital type of automatic PLC controlled governing system with the oil pressure tank (or) oil pumping system. The system shall be independent, adjustable and control the Unit to operate with an adequate margin of stability under all steady state and transient load conditions without hunting and shall cause the Units to operate stably and satisfactorily in parallel with each other and/or the interconnected with Grid system.

(b) The governor shall be of the PLC controlled electro-hydraulic type with an established reputation of satisfactory and reliable service. Evidence of using PLC Controlled Governor with product catalog/ information and license software shall be provided with the Bid.

(c) The speed signal for the governor shall be derived from an approved source which shall not be used for other functions. The source for the speed signal shall be wired directly to the governor PLC panel without fuses or other electrical protection devices and it shall not be damaged by short circuits. The source for the speed signal shall be sufficiently free from interference or distortion to ensure stable speed control of the unit and it shall have sufficient resolution to ensure accuracy of speed control. The Contractor shall also provide suitable frequency and load reference sources for the governor.

(d) The proposed location for the major items of governing equipment in the station is shown on Drawing. The Bidder shall propose the locations the governing equipment offered so that the Layout and Dimensional Drawings for both electrical PLC controlled Panel and Hydraulic oil pumping system shall be indicated clearly inside powerhouse and shall be attached with the Bid.

(e) The governor shall be provided with all the speed switches required for its operation and control diagram for which Operation and Control Sequence Diagrams (Normal Start/ Normal Stop/ Emergency Stop) for Governor Control System shall also be submitted with the Bid.

(2) Governor capabilities

(a) The governing system shall be suited to and afford all facilities necessary to meet the monitoring and control system requirements as per Section 11.

(b) The Unit will be connected with PEA Grid at 22kV network so that governor shall be capable for operating responding to deviation in frequency of 0.05 Hz or greater. It shall be capable of responding to load changes greater than 5 percent of rated capacity of initiating servomotor movement within 0.2s and

load fluctuations of 5 to 10 percent rated capacity by damping the fluctuation to 10 percent of the initial fluctuation within 10s. However, during emergency shutdown conditions, the Unit shall be able to supply an isolated load with stable control of frequency.

(c) The governor shall include the facilities listed below:

(i) Means for adjusting and locking the damping time constant between zero and 4.0 s.
(ii) Means for adjusting the temporary speed droop from 10 to 60%.
(iii) Means for adjusting and locking the accelerometer time constant between zero and 3.0 sec.
(iv) Means for adjusting the governor speed setting over at least the range +5 percent to -10 percent of normal speed while operating or stationary.
(v) Means for adjusting the load set point from 0 to 110 percent of rated generator load for electro-hydraulic governor only
(vi) A needle valve and deflector stroke limiting device.
(vii) Means for adjusting permanent speed droop to any valve between 0 and 6%.
(viii) Provision for adjusting and locking the openings and closing times of the needle valve and deflector within a range incorporating a minimum time of 3.0 sec. If a stepped rate of needle valve and deflector closure is used there shall be provision for the independent adjustment of the position and timing of the step(s) and
(ix) A device for closing the needle valve and deflector as part of the stop and shutdown sequences.

(d) Governor Cubicles

For governor cubicle, the PLC and electronic equipment for governor control, protection and monitoring shall be installed inside the Control Room. The Governor Hydraulic Parts shall be separately installed close to turbine therefore the evidence for this such as Location Layout of Equipment with the detailed Component List descriptions shall be submitted with the Bid.

(3) Governor Oil Pumping System

(a) A complete governor pumping system shall be provided for each unit. Each system shall supply enough hydraulic oil for the opening, closing, and adjusting needle valve and deflector, and the inlet valve servomotor. The governor system shall be suitable for the same grade of oil as the bearings.

(b) A separate oil and accumulator tank shall be designed and included in Governor Oil Pumping System as per ASME Boiler and Pressure Vessel Code, Section III to maintain the allowable operating pressure including pressure

switches, level control devices, pilot control valves, oil pressure adjustable valves, oil strainers at suction line of each pump, safety relief valves, check valves, temperature relay and hand operated valve for the complete operation for both governor oil pumping system and inlet valve opening hydraulic unit.

The hydraulic P&I diagram showing the above components shall be submitted in the Bid indicating oil cooling equipment.

(c) Duplicate AC motor-driven vertical pumps with motor suitable for operation at 380Vac, 50Hz shall be provided for normal and standby duty respectively complying with IEC standards IP 54 Class F Insulation. The duties shall be interchangeable while in service setting Lead/ Lag selector switch at any MCC panel. The rated capacity of each pump shall be not less than 1.5 times of the total oil volume of servomotors sufficient for all requirements of the system. Each pump shall be complete with at least its own components as per item (b) so that either pump may be withdrawn for maintenance without affecting the operation of the other. The strainer shall be fitted with a differential pressure indicator to give indication of the need for cleaning.

The preliminary equipment layout arrangement and component drawings shall be submitted in the Bid to verify that Bidder complies with the above requirements.

(d) The governor hydraulic pressure unit shall be designed with an opened vessel type with sufficient capacity in the sump tank to prevent pollution in case oil leakage on the hydraulic pressure unit. Oil sump tank shall be provided with oil level gauges, oil temperature gauges, service manholes and drain valves. The bladder type nitrogen accumulator tank shall be provided with enough volume to maintain pressure for needle valve, deflector and inlet valve servomotor cylinders having sufficient capacity to the turbine start and brought to full speed at any time within 8 hours after the loss of AC and DC power supply to the hydraulic pressure unit and with the normal pump not commencing to rotate until the unit reaches normal speed and in addition to one complete closing stroke from low oil level or low pressure shutdown in case of oil pump not operating.

(e) The governor and inlet valve oil pipework shall be arranged so that oil cannot drain from the servomotor cylinders, control valves or pipework when the oil pressure supply is off. Air release points shall be provided on the servomotors and where necessary, on the pipework. The oil pressure supply shall be automatically isolated from the governing and inlet valve systems when the unit is stopped.

(f) The oil sump shall be fitted with a suction and return connection for oil centrifuge equipment.

(g) Twin cartridge type filters (or) 'auto-clean' type filters shall be fitted in the main oil pressure supply from the receiver. Each filter shall be fitted with a differential pressure signal to send to Governor PLC and give an indication of the need for cleaning. They shall be of sufficiently fine filtering capacity to prevent damage to any portion of the governing system by foreign matter, cartridge type filter shall be capable of being individually removed for cleaning without shutting down the governor.

(h) A float valve (or) similar shall be fitted to the oil pressure supply connection in the pressure receiver to prevent release of air in the event of abnormally low oil level in the receiver. The float valve shall be arranged to permit oil to be delivered into the receiver when the oil is at any level.

(i) Portable Oil Centrifuge Unit (not applicable)

One portable oil centrifugal unit of 400 L/h capacity shall be supplied to use in the station. The oil centrifuge unit shall be suitable for removing water, metal particles and other foreign matter from all lubricating and regulating oil systems. The unit shall be mounted on a rubber tire trolley, shall be suitable for unattended operation and shall be supplied complete with:

- Motorized centrifuge unit, with all wet parts of corrosion resistant material. All wearing parts shall be renewable.
- Motorized pumps feed dirty oil and discharge treated oil from the centrifuge.
- Electrical heaters with thermostatic control to bring the oil to the correct temperature for centrifuging.
- Regenerative heat exchanger to heat incoming oil and cool outgoing oil.
- Control panel with all necessary starter and heater controls.
- All necessary thermometers, pressure gauges, sight glasses and flow indicators.
- All necessary piping, valves, flexible suction and delivery hoses and tools.

The operation of the centrifuge unit shall be such as to minimize aeration, frothing and foaming of the oil.

S2.04 SPECIFIED SPAREPARTS

The Contractor shall supply all the specified spare parts and components including special tools for assembly and disassembly of the turbine and governors as stated as below: -

1) Turbine Spare Parts
   - Needle Valve Position Feedback Transducer 1 Set
   - Actuator Arm Bushes (or) bearing bush 1 Set
   - Packing seals and gaskets for the turbines 1 Lot
   - Deflector with bush (complete set) 1 Set

2) Governor Spare Parts
   - Solenoid for Needle Control 1 Set
   - Solenoid Control Module for Needle Control 1 Set
   - Oil filter 2 Sets
   - Accumulator Gas Filling Kit 1 Set

SECTION 3 - INLET VALVES

S3.01 TYPE AND CONSTRUCTION

(1) The turbine shall be provided with an inlet valve of the butterfly type designed for minimum head loss and disturbance and having the diameter which shall not be less than of the inlet pipe.

(2) The main elements of the valve shall be of cast, forged or fabricated steel and shall also be manufactured according to ASTM, ASME, BS, EN, AWWA and ISO Standards. If fabricated construction is used, all welds stressed directly or indirectly by pipeline pressure shall, to the maximum extent practicable, be full penetration butt or tee-butt welds. All wearing parts shall be renewable and all such parts in contact with water shall be of corrosion resistant material or sleeved with corrosion resistant material.

(3) The sealing shall be by solid, rubber to metal (or) metal to metal, contact between the rotor seals and the body seats and shall not involve inflation or other similar forms of relative movement of elements in the seals or seats. If metal to metal contact between seal and seat is used the material shall be such that galling, or pick-up cannot occur on contact. To this end the hardness of any parts between which contact or sliding occur shall differ by at least 50 Brinell hardness.

(4) The trunnion and servomotor connecting rod bushes shall be of greaseless, self-lubricating type. Should weight closed valves be offered, provision shall be made to prevent dirt and foreign matter from entering the top of the servomotor.

(5) The seal leakage during both shop and site tests shall not leak under a head of 179.48 m of water column.

(6) The seals, seats, trunnion bushes and trunnion glands shall be so arranged that they can be removed or installed without dismantling the valve bodies or removing the valve from the pipeline.

(7) The Contractor shall provide steel pedestals to support the valve and transmit all loads from the valve to the floor slab.

(8) The Bidder shall submit the layout dimensional arrangement of Inlet Valve and bypass valve together with dismantling pipes and drainpipe with the Bid.

S3.02 OPERATION

(1) The valve shall be capable of opening by governor pressure oil system and closing against any flow up to and including that due to free discharge at the outlet of the valve with maximum water level in the upper reservoir.

(2) The valves shall be operated by oil pressure supplied by the governor pressure oil system. Operation in close direction shall be by counterweight.

(3) The hydraulic piston and its mounting, pressure piping and control valves shall be adequate for the pressure operated by pressure unit with the most adverse conditions of unbalanced closure against free discharge.

(4) A manually operated mechanical lock for securing the inlet valve rotor in the closed and open position shall be provided and shall be of adequate strength to resist the thrust of the servomotor in both the opening and closing directions. The locks shall embody provision for padlocking in the inserted and withdrawn positions.

(5) A system shall be provided for automatically checking, collecting, and returning oil to the governor oil sump tank any oil leakage of the servomotor.

(6) The initiation of opening of the inlet valve shall be interlocked with the establishment of a pressure in the nozzle substantially equal to pipeline pressure.

(7) The inlet valve opening and closing times shall be independently adjustable, but the adjustments shall be of a form that cannot be readily or inadvertently altered. In the interest of minimizing the times necessary to start up and to shut down in an emergency, the opening and closing times shall be the minimum consistent with safe operation.

S3.03 CONTROL AND INDICATION

(1) The control gear shall be such that the inlet valve may be opened and closed by local manual mechanical control and remote control as part of the starting and stopping sequence. The valve controls shall be kept as simple as possible consistent with their function.

(2) Position indicators visible from the floor of the Machine Bay shall be provided for the bypass valve, inlet valve rotor and mechanical lock.

S3.04 BYPASS VALVE

(1) The inlet valve shall be provided with a bypass valve, pipes, and fittings, preferably around 100 mm diameter. The purpose of by-pass valve is to fill water into the casing and to balance the pressure between upstream and downstream side across the inlet valve, and the bypass valve shall be operated by DC motor (110Vdc) (or) hydraulic operated when the needle valve, deflector and inlet valve are closed before starting the turbine-generator. A manually operated gate valve (normally open) shall also be provided together with a bypass valve.

(2) The bypass valve shall be mounted directly on the connecting pipe (or) valve body and shall be complete with a pipe connection to the isolating valve which shall be mounted directly onto the penstock. The bypass valves shall be operated automatically operate from PLC Control Command at Unit start and also manually operated by hand wheel of gate valve. Means shall be provided to ensure positive segregation of oil and water circuits.

(3) All wearing parts of the bypass valves including those susceptible to erosion or cavitation shall be renewable and those in contact with water shall be of stainless steel or bronze.

S3.05 DISMANTLING JOINT AND SHORT PIPES

(1) A flanged stub pipe and a welded short pipe shall be provided to connect the inlet valve to the end point of the penstock. The short pipe shall be compatible for welding to the penstock and shall be designed in accordance with the minimum criteria used for penstock pipe. For maintenance of the inlet valve, the penstock shall be supplied with a blind flange with the separate bolts and nuts and the operation of the other unit can be done without interruption during maintenance.

(2) The short pipes shall supply at least 800mm in length and include 150-200mm trimming allowance and shall incorporate connections for all equipment required to be connected to the penstock. The Contractor shall be responsible for trimming and fitting the closing piece and also for the making of the welded joints between the pipeline and the closing piece. These welds shall be subject to a 100 percent radiographic inspection.

(3) A flanged dismantling joint shall be provided between the turbine casing and inlet valve to adjust and to dismantle during maintenance. The dismantling joint shall be complete with nuts, bolts and jointing suitable for attaching to the turbine casing, the dismantling joint shall permit installation and removal of the inlet valve. The design shall be such that no forces are transmitted via the pipe to the turbine.

S3.06 PRESSURE CONDUIT AND TURBINE DRAIN SYSTEMS

(1) A minimum 100 mm diameter manually operated gate valve with connecting pipes shall be provided with each turbine for draining water from penstock upstream to the tail water. The conduit connection to penstock tappings shall be located upstream of the inlet valve in the stub pipe or closing piece. The embedded pipework provided by the civil works contractor shall be as shown on the Drawing.

(2) A minimum 75 mm diameter valve and pipes shall be provided to drain water from the turbine casing to the tailrace. The valve, piping and supports shall be suitable for operation under maximum unbalanced head and free discharge without appreciable vibration.

(3) The Bidder shall submit the layout arrangement of Turbine, Inlet Valve, bypass valve and pipe arrangement shall be submitted with the Bid.

S3.07 SHOP TEST

(1) Physical Inspection

Contractor shall perform the factory test for the valve under the witness of Client personals measuring the size and the dimensions indicated in the submitted shop drawings. The inspection form and format shall be submitted for approval before the witness acceptance test.

(2) Assembly at the factory

The valve shall be preassembled at manufacturer's factory before witness acceptance test together with counterweight to perform operation test to record opening and closing time of the valve with counterweight assembly.

(3) Hydraulic Pressure Withstand Test

Hydraulic Pressure Withstand Test shall be performed for valve body with seals and seat assembly. Both sides shall be tested and record the values together during the witness acceptance test.

The test parameter shall be as follows:

- 1.5 times the maximum design pressure for 10 minutes.
- 1.5 times the maximum design pressure with an additional pressure of 0.3 Mpa for 1 minute.

SECTION 4 - TESTS FOR TURBINE, GOVERNOR INLET VALVE AND AUXILIARIES, TURBINE MODEL TEST, TURBINE FIELD EFFICIENCY TEST

S4.01 TESTS FOR TURBINE, GOVERNOR, INLET VALVE AND AUXILIARIES

(1) Tests During Manufacture

Turbines, governors, inlet valves and auxiliaries shall be subject to the following tests at the Contractor's premises and according to manufacturer's standards and the international standard regulations.

Contractor shall provide manufacturer's internal QC test reports such as balancing reports, material test reports (or) material certificates during manufacturing and shall submit before the factory acceptance test so that Witness Test Attendees shall verify comparing with shop drawings approved during engineering stage.

Calibration Certificates of testing instruments shall be provided together with Witness Test Reports.

The Contractor shall bare all travelling expenses (air tickets, accommodation, meal, allowance, etc.) for at least two (2) DEDE Engineers (as Witness) for turbine, mechanical parts to attend the test at factory and sign for approval of test results before delivery to site.

(a) Material Tests
- (i) Material tests on all important stressed components as defined in Clause S1.17 (2).
- (ii) Radiographic examination or ultrasonic examination of all major castings and forgings. The areas proposed for such an examination shall be nominated by the Contractor when he submits drawings of the components concerned in accordance with Clause 4.06 of Volume 1 and shall be subject to the approval of the Engineer. The decision as to whether further examination is required shall be determined on the incidence of defective materials disclosed by the initial examination. The acceptability of the material shall be judged in accordance with American Society for Testing Materials, cracks and hot tears being 'unacceptable', severity level 2 for all other forms of defect being 'borderline', as defined in those Standards. Any areas found by these examinations to contain unacceptable defects shall be subject to re-examination after repair.
- (iii) Radiographic, ultrasonic examination and crack detection of welded components in accordance with Clause S1.17
- (iv) Crack detection of all castings and forgings.

(b) Hydrostatic Tests

(i) On all equipment subjected to water, oil, or air pressure during normal or abnormal working conditions, in accordance with the relevant American Standards, subject to the test pressure being not less than 1.5 times the maximum working pressure but the testing pressure shall not be less than the rated pressure occurred at penstock pipes during emergency trip.

(ii) Leakage and deflection tests on all equipment stressed by pipeline pressure.

(iii) Leakage tests with kerosene under gravity for all sump tanks.

(c) Tests on Unit Auxiliaries

(i) Motors for unit auxiliaries shall be subjected to type and routine tests.

(ii) All motor-driven auxiliary machines shall be run as complete units and tested for starting current, running current, power factor, bearing performance, gland tightness, noise, and vibration.

(iii) One auxiliary machine of each type for connection to the unit auxiliary system shall be tested to demonstrate satisfactory operation over the range of voltage and frequency which many occur in service including full-load rejection of the generator.

(d) Tests on Governors

The governor shall be tested as per IEC publication 308 for the governor. And test items to be submitted for approval by DEDE.

(2) Tests at Site

(a) Preliminary Tests

The preliminary tests for the turbines, governors, inlet valves and ancillaries shall include the following:

(i) Radiographic (or) ultrasonic examination of all site welding parts as defined in Clause S1.17.

(ii) Hydrostatic pressure tests on all pressure pipe systems. (The test pressures shall be respectively the same as specified in Clause S4.01 (1) (b) for the tests during manufacture).

(iii) Insulation and continuity tests on wiring including tests for correctness of connection.

(iv) Checking for correct operation of each control, protection, and indication device.

(b) Tests on Completion

For the turbines, governors, inlet valves and ancillaries, the Tests on Completion shall include the following:

Tests for correct operation, control, indication and protection of all ancillary systems required to be in service for the operation of the turbine/generator units including:

- Oil Pumping System (Governor)

- PLC Controlled Governor system
- Unit PLC Control
- Inlet valve and bypass valve operation
- Cooling water supply system
- Drainage System
- Brake System
- Final alignment checks for rotation parts
- All instruments feedback signals from field to Control Systems

When water from penstock available for test, Contractor shall start drain for penstock to assure that there are no external pieces inside penstock which may be harmful and cause damage to Turbine parts and Inlet Valve so that Civil and Electromechanical Scopes shall perform inspection together with DEDE representatives and shall make witness before Commissioning Wet Test.

No Load Bearing Heat Run Test, Load Heat Run Tests with Load rejection for different load % for 25, 50, 75 and 100% respectively and 48 Hours PEA Grid Connected Heat Run Test shall be performed for completion of Contract.

Contractor shall perform the followings during Commissioning Wet Test: -

(i) Speed, pressure and frequency regulation tests.
(ii) Check pressure and output fluctuations.
(iii) Tests of correct functioning of controls, protection and indicating equipment.
(iv) Test to prove that the delivered turbine and related equipment are complying with the guaranteed efficiency and output as specified in the Contract.
(v) The relevant sections of the 'International Code for the Field Acceptance Tests of Hydraulic Turbines' IEC Publication 41 in so far as this code is consistent with this Specification and the conditions at Site, except that the tolerance shall be as stated in subparagraph (ii) of this paragraph.
(vi) Tolerances allowing for inaccuracies of measurement, the following tolerances shall be applied to performance figures ascertained from Tests on Completion.

- Momentary speed rise - N $\pm$ 2.0 percent absolute.
- Maximum pipeline pressure - N $\pm$ 2.0 percent of the ascertained figure.
- Power output - N $\pm$0.5 percent of the ascertained figure.
- Inaccuracy of efficiency for field test of turbines shall not exceed $\pm$ 1.5 percent.

Tolerance according to IEC standards shall also be considered.

Furthermore, for the completion of Testing and Commissioning, The Contractor shall perform the following tests for the generating units by connecting to the PEA power grid system:

- Dummy Load Test

- Dummy Load Operation Test of complete excitation system including automatic voltage regulating equipment at various loads and including load acceptance and rejection test at 25, 50, 75, 100% of load.
- Continues Load Test for 48 hours to the PEA Grid

S4.02 TURBINE FIELD EFFICIENCY TEST

Field testing to verify the turbine efficiency and outputs shall be done by the Contractor after completion of all installation works and dry test. The test procedures, instrument used and date for the test shall be submitted to DEDE for approval.

Tests shall be carried out in accordance with the provisions set forth in "International Code for the field Acceptance Test of Hydraulic Turbines" (IEC Publication 41) and the method, diagram and the instruments used for the test shall be submitted with the Bid.

The Bidder shall indicate in his Bid at least two methods for measuring flow and shall submit drawings with located indication including necessary provisions for the penstock.

Failure to provide information may lead to the rejection of Bidder's Proposal.

All instrument and cost required for performing the test shall be at the Contractor's expenses. Testing instruments shall be calibrated by an independent institute/organization, and it shall be submitted to DEDE for approval.

Should the result of the test show that the efficiency or the output is lower than the corresponding guaranteed value, all the liquidated damage costs relevant to the test shall be deducted from the Total Contract Price.

SECTION 5 - MECHANICAL AUXILIARY EQUIPMENT

S.5.01 UNIT COOLING WATER SYSTEM

(1) General Description

(a) The Contractor shall provide one unit a separate cooling water system for supply to, and where necessary, the generating equipment of this plant during the unit is operating. The cooling water shall be taken from penstock which is upstream of the inlet valve. The location of tapping point shall be subject to the DEDE approval. The envisaged schematic arrangement of the unit cooling water system is shown on the Drawing. The details shown on the Drawing shall be taken as the minimum requirement. The items of Plant to be supplied by the unit cooling water system shall be for:
  (i) bearing lubricating oil system (if required)
  (ii) turbine shaft sealing (if required) and
  (iii) Any other unit auxiliary requires a supply of cooling water while that unit is operating

(b) The Contractor shall design and specify the flow requirements, size of piping required and the operating head of the system.

(c) The Contractor shall submit the cooling water system diagram showing valves, strainers, and instrument and pipe sizes together with the Bid.

(2) Arrangement of Equipment

(a) The system shall include duplicate automatic and manually operated self-cleaning type filter (or) strainers drawing water from the penstock and supplied for the Unit and other services as required.

(b) A stainless-steel orifice for flow distribution adjustment, and a flow relay for flow indication and flow failure alarm, shall be provided. The system shall be complete with automatic motor driven back-washing strainers (or) filters, all pipes, valves, pressure gauges, flow control valves, air releases and drains.

(3) Type and Construction of Equipment

(a) A.C. Motor Driven
A.C. motor driven isolating valve shall be controlled during turbine start and stop sequences.

(b) Strainers (or) Filters
  (i) The strainers (or) filters shall be of the automatic and manually operated self-cleaning type, with mesh openings not more than 50 microns and in

any case small enough to exclude any foreign matter large enough to cause damage (or) blocking in any part of the system.

(ii) Any discharge from the strainers (or) Filters resulting from a backwash of flushing cycle shall be piped to drain. The mesh shall be of corrosion resistant material and the strainer bodies and covers shall be galvanized internally and externally.

(iii) The strainers (or) Filters shall each have an automatic air release valve with discharge piped to drain. The head across the strainer when 30 percent blocked shall not exceed 1.5 m of water.

(c) Portable Chemical Feeder (Not applicable)

(i) Cooling water conditions may produce bacterial growth in the water passages of the various heat exchange systems.

(ii) A portable chemical feeder shall be provided to enable periodic injection of suitable concentration of hydro-chloric acid or sodium hypochlorite into each unit cooling water system in order to control the bacterial growth. It is expected that approximately ten parts per million residual chlorines will be required in the cooling water systems, however the chemical feeder shall provide for a range of feed rates which shall be fully adjustable.

(iii) The chemical feeder shall consist of a tank, pump, filter, check valve, pipes, swivel type injection connections for pipe coupling and other necessary instruments and shall be provided with a control panel, electrical cord, and plug. The pump shall be of the positive displacement type driven by an electric motor. Two (2) flexible tubes shall be provided to connect the chemical feeder to the injection point in the cooling water system. The chemical feed unit and tank shall be mounted on a four-wheel hand truck with pull bar and lifting eyes at each corner. The equipment shall be neatly arranged, and provision shall be made for storing flexible tubes and electrical cord.

(iv) The chemical injection points for each unit cooling water system shall be located upstream of the Unit cooling water system and accessible from the machine hall floor level.

(d) All piping for unit cooling water systems shall be of seamless steel pipes with bolted flange connection.

S5.02 COMPRESSED AIR SYSTEM (NOT APPLICABLE)

(1) General Description

(a) The common compressed air system will be used to supply operation air to the following equipment:

(i) Turbine governor pumping set oil/air pressure receivers

(ii) Maintenance service points at erection bay and machine bay and generator brakes.

(b) The Contractor shall determine the capacity of compressor, primary chamber and air receiver, the normal operating pressure and pipe size so that the charging of a governor pressure receiver from atmospheric to working pressure can be achieved in 0.5 hours.

(2) Arrangement of Equipment

The system shall comprise two motorized air-cooled compressors for normal and standby duty respectively. The duties shall be interchangeable while in service. Each compressor shall include a silencer, intake, filter, governor type drainage valve, primary chamber, after-cooler, non-return valve and isolating valve delivering into the air receiver. The compressor shall be controlled by air pressure in the high-pressure air receiver, connection of high- and low-pressure air receiver shall be made by pressure reducing valve and solenoid valve which shall be controlled by the air pressure of low-pressure air receiver.

The compressors shall be arranged to operate by automatic and manual control. The system shall be complete with all pipes, fittings and connections, manual valves, temperature, and pressure gauges.

(3) Compressors

(a) The compressors shall be continuously rated and of a reciprocating, air cooled pattern.
(b) All working parts shall be replaceable.
(c) The compressors shall be provided with after cooler and, where necessary, inter-coolers. They shall be air cooled, and the tube nests shall be replaceable. The tubes shall be of corrosion resistant material. Each cooler shall be complete with moisture separator and automatic trap fitted with sight glass assembly.
(d) Main bearings, and for reciprocating compressors, connecting rod and crosshead bearings shall be oil pressure lubricated by a pump mechanically driven from the compressor. Where separate cylinder or rotor lubrication is provided, the oil pump shall be mechanically driven from the compressor.
(e) The pressure oil system shall include a suction strainer, sump level indicator and full flow strainer of either the replaceable cartridge or cleanable edge filtration type.
(f) Crankcases shall be enclosed when the compressor is operating. Cooling jackets, air cowlings and crankcases shall have adequate access for cleaning and inspection.
(g) Intake shall be provided with suction silences and an air cleaner of either the oil bath or replaceable cartridge type.

(h) Compressors shall be fitted with protective devices to stop the compressor in the event of low oil pressure or high air delivery temperature.
(i) Compressors shall be fitted with starting unloaders such that the unit reaches full speed before air delivery commences.
(j) Motors and compressors shall be rigidly mounted on a common base plate to maintain correct alignment. All moving parts shall be enclosed. The base plate shall minimize the transmission of vibration to the foundation.

(4) Air Receivers and Air/Oil Receivers

(a) Compressed air receivers and air/oil receivers shall be designed and constructed in accordance with ASME Standard.
(b) The receivers shall be fitted with safety valves, pressure gauges and automatic and manual condensate drains.
(c) The Contractor shall provide detailed shop drawings and calculations for the design of the receivers sufficient for the DEDE Engineer to check compliance with ASME requirements.

S5.03 VENTILATION AND AIR-CONDITIONING SYSTEMS

(1) General

(a) The Contractor shall design, supply, and install the ventilation and air-conditioning systems in the power station. The system shall comprise:
  (i) Three (3) air conditioning split type ceiling mounting, each for the Control Room, 24,000 BTU-HR Sealed Energy Save No. 5.
  (ii) Three (3) air conditioning, spit type for office 24,000 BTU-HR Sealed Energy Saving No. 5
  (iii) Individual ventilation systems for the following rooms:
    - Toilets - window mounted exhaust fan
    - Diesel Room - exhaust fan
    - Battery Room - exhaust fans
    - Control Room - supply/exhaust fans
    - Office Room - supply/exhaust fans
    - Switchgear Room - exhaust fan
(b) Each system shall include control and indicating instruments and all electrical wiring.

S5.04 POWERHOUSE WATER DRAINAGE SYSTEM

(1) General Description

(a) The station drainage pumping system shall consist of two sump pumps and motors each of 4 L/s capacity when operating in the drainage pit. Schematic arrangement of pumps and pipework shall be submitted for approval.

(b) The drainage pumps will be used to remove normal seepage, drainage water, and casing drainage water which will be directed by gravity drains into the drainage pit. The pumps shall be supplied with quick release couplings such that a pump can be removed and used as a portable pump for drainage of a draft tube. The pumps will also be used to drain the inlet valve pits under emergency conditions such as a burst connection from a pressure conduit. The Contractor shall determine the size of piping required and the head against which the pump must operate to enable complete drainage of a turbine draft tube.

(c) The drainage water may vary from the normal site 'clean' condition to a condition where it contains silt, small, suspended material, and contaminants such as lubricating oil, kerosene, and grease in concentrations up to approximate 150 ppm.

(2) Arrangement of Equipment: The system shall comprise two drainage pumps each with its own discharge piping, pressure gauge, check valve, and gate valve. The pumps shall operate under both manual and float switch control. The float switches shall be arranged to operate in accordance with levels. The duties of the two normal drainage pumps shall be interchangeable by manual controls.

(3) Type and Construction

(a) The pumps shall be submersible, bottom suction, vertical shaft units with quick release coupling suitable for operating while submerged for indefinite periods and after being stationary for long periods. The design and construction of the motors shall prevent the entry of external water, foreign material or contaminants into the motors or their cooling systems under all conditions.

(b) The pumps shall be held with guide rail in the pit and can be removed by sliding up along the guide rail.

(c) The pumps shall be driven by 230Vac, single-phase motors. Provision shall be made for replenishing the cooling lubricant if required.

(d) The float switches shall be suitable for submerged operation. They shall be mounted in a vertical steel pipe which shall be located in the drainage pit. Off takes from the sump to the float switch pipe shall be equipped with mesh strainers. The float switch pipe complete with float switches shall be arranged so that it may be easily removed from the drainage pit.

(4) Piping and Fittings: The Contractor shall supply duplicate galvanized piping together with all steelwork and fittings for locating the pumps and float switch pipe within the drainage pit.

S5.05 PORTABLE FIRE EXTINGUISHERS

(1) The Contractor shall supply portable fire extinguishers complying with accepted standards. Each extinguisher shall be mounted on a suitable bracket on the wall at a location to be advised by the DEDE Engineer.
(2) Extinguishers shall be red with a glossy baked enamel finish, chrome-plated trim, and safety pin.
(3) The following table lists the quantities of portable fire extinguishers required. For those type of extinguishers where it is possible to supply either a model which can be refilled on site or a model which must be returned to a factory for refilling, the model which can be refilled on site shall be supplied, fully charged on complete with one (1) spare refill for each extinguisher.

TABLE S5.05-1
FIRE EXTINGUISHERS

Location	Minimum Capacity	CO_2	Dry Chemical
Erection bay	6 kg	1	1
Control room	6 kg	2	1
Office area	6 kg	1	-
Diesel room	6 kg	1	1
Machine bay	6 kg	2	1
Battery room	6 kg	1	-
Storeroom	6 kg	1	1
Switchgear room	6 kg	1	1

S5.06 OVERHEAD TRAVELING CRANE

(1) Type and Rating

(a) The Contractor shall provide an electrically driven, pendant controlled, overhead traveling, and top running bridge type crane for the Powerhouse, together with a set of crane rails, longitudinal travel collector wires and associated equipment, four end buffers for the longitudinal travel and permanently fixed ladder and platform for routine maintenance.

(b) The capacity of the crane shall not be less than 5 tons however the Contactor shall design and supply depending on the heaviest part of equipment to be lifted during erection and maintenance of the equipment inside this station.
(c) The crane shall be designed, constructed, erected, and commissioned in accordance with CMAA or equivalent standards.
(d) The height of lift of the crane and the limits of traverse and travel of the crane hook shall be determined by the Contractor and shall be sufficient for all erection and maintenance operations on the Plant in the Powerhouse Machine Bay.
(e) The limits of lifting traverse and travel of the crane hook shall give the maximum possible coverage within the Powerhouse.
(f) The crane will constitute a prominent feature of the Powerhouse and shall be designed to present an appearance aesthetically in keeping with this role and with the interior architecture of the Powerhouse.

(2) Operating Requirements

(a) The crane shall have electrically driven hoisting (two speeds), traversing and traveling motions controlled by a low voltage push-button pendant. The pendant shall be movable horizontally along the crane bridge and located vertically for operation from the machine bay floor.
(b) The operating speeds of the crane shall be within the following ranges:

Hoist	Normal	0.050	m/s
	Creep	0.005	m/s
Traverse	Normal	0.33	m/s
	Creep	0.08	m/s
Travel	Normal	0.60	m/s
	Creep	0.16	m/s

Minimum Height of Lift	10	m (approx.)

However, Contractor shall submit the details for approval during the engineering stage.

(3) Crane Runway

(a) General
The Contractor shall supply and install all sole plates and anchor bolts for the crane rails, longitudinal travel buffers and limit switch strikers.
(b) Span
The span of the crane runway rails measured centre to centre shall be 9.0 m ± 2 mm.
(c) Rails The crane runway shall consist of jointed flat bottom rail and shall be installed to within ±2 mm of level for its full length. Each section of each

crane runway rail shall be interconnected, and the rails shall be connected by grounding conductors to the Powerhouse grounding system.

(d) Longitudinal Travel Buffers
Four longitudinal travel buffers complete with soleplates and holding down bolts shall be supplied and installed by the Contractor, one set for each end of the runway.

(e) Longitudinal Travel Limit Switch Strikers
Two longitudinal travel limit switch strikers shall be supplied and installed by the Contractor. These shall be positioned to provide a possible overrun of 150 mm when the limit switched trip.

(4) Construction Requirements

(a) Crane Structure

(i) The crane shall be of fabricated steel construction. The bridge shall consist of one main girder connected together at each end by means of a substantial cross beam. The vertical deflection caused by the rated load plus the trolley shall not exceed length/ 1,000 of span. Floor plate walkways and steel handrails shall be provided and shall be suitable for routine maintenance of crane parts. The securing of the main girders to end carriages shall be by high tensile bolts and nuts to assure correct alignment and easy erection.

(ii) The complete bridge structure shall be mounted on end carriages. Each end carriage shall contain wheels which rotate on antifriction bearings mounted on simply supported axles. The design of each end carriage shall be such that easy inspection and wheel removal is possible. In the event of a wheel shaft breaking, it shall not be possible for the crane and carriage to drop more than 33 mm.

(iii) Four travel buffers shall be attached to the outer bogies; one for each can stop at the end of each crane runway.

(b) Longitudinal Travel Mechanism
The longitudinal travel drive units shall be identical motorized geared units ensuring smooth operation of the longitudinal travel. The high precision gears of these units are run in the oil bath. Each drive unit shall be equipped with electromechanical brake operators according to the sliding rotor principle which shall be capable of being replaced without removing other components. The brakes shall be capable of being applied gradually to minimize swaying of the load and shall operate automatically when the supply to the motor is interrupted. The travel motor is designed as a drive unit for acceleration and safe deceleration of high-inertia load.

(c) Low Headroom Monorail Hoist

(i) The hoist motor shall drive the hoist drum by central drive. The hoist drive shall be fitted with an automatic, spring applied, energized to release, brake. The hoisting drum shall be steel or cast iron and shall have accurately machined grooving to accommodate the hoisting rope in single layers. The hoisting rope shall be performed, non-rotating construction.

(ii) The hook of the crane fall block shall be of swiveling type, supported on a ball or roller thrust bearing. The fall block shall be provided with shrouded sheaves. The fall block sheaves, compensating sheaves, and reeling return sheaves shall have machined grooves and shall be mounted on ball or roller bearings.

(iii) The motor torque is transmitted to the reduction gear through a flexible coupling to cushioning high starting torque peaks.

The minimum breaking strength of the rope shall be not less than five (5) times the hoist's rated load.

(d) General

(i) All gearing other than final drives shall be enclosed in gear cases. The gearboxes shall be fitted throughout with ball or roller bearings. Gearing shall be designed in accordance with the AGMA Class II with a minimum service factor of 1.25.

(ii) All shafting to which gears, pinions and other similar parts are fitted, shall preferably be provided with a raised portion and/or shoulder where such parts are carried. Any change of section of shaft shall be affected with fillets of ample radius.

(iii) All bearings and other wearing surfaces shall be provided with means for lubrication, preferably by automatic circulation. Points for lubrication by grease gun shall be suitable for the same make and grade of grease and shall each be provided with a separate grease nipple of the all steel, one piece button-head type. All grease nipples shall be readily accessible and grouped wherever possible. Removable; sheet steel guards shall be provided for open gearing.

(iv) All gear boxes, motors, bearings, etc. shall be positively located after alignment, other than by their holding down bolts.

(v) All platforms shall have 75 mm high kick strips at their edges.

(e) Electrical Equipment

1) All electrical equipment shall be suitable for operation from the 400V, 50Hz three-phase four-wire supply from the AC Station Service Distribution Board. The Contractor shall provide, on the crane, adequately rated single phase transformers, suitable for continuous operation for the

supply of power to the control circuits, lighting and power outlet circuits and 'POWER ON' indicator light circuits.

2) The electrical power supply to the crane shall be by means of three shrouded hard drawn copper collector wires supported by brackets, attached to the building above crane runway level. Red indicator lights shall be installed between phases at the end of the collector wires to show that collector wires are energized. The Contractor shall supply and install the collector wires, three collectors or renewable carbon head type, and all necessary and strainers, brackets, insulators, collector wire guards, and other fittings, together with a 'lock-off' type isolating switch and all wiring and conduit from this switch to the point of connection to the three longitudinal collection wires. The isolating switch shall be labeled 'CRANE ON/OFF'.

3) All motors shall be half-hour rated for the required duty cycle.

4) A control and protection panel enclosed in a cabinet, of dustproof, sheet metal construction, incorporating a hinged door and hinged panel, shall be mounted on the crane bridge. The equipment shall include an externally operated triple-pole main isolating switch, triple-pole main contractor, triple-pole ganged magnetic overload relays for each motor and all necessary fuses, control switches and wiring for the motors, control circuits, and one single-phase switched socket outlet. A 'POWER ON' indicating light shall be fitted to the cabinet.

5) A fall block operated; whole current over hoisting limit switch shall be provided for the hoist. In addition, a shunt type limit switch shall be fitted to the hoist to limit the travel in the 'raise' and 'lower' directions. Shunt type limit switches shall be provided also for the cross-traverse and longitudinal travel motions. All limit switches shall be self-resetting and shall be electrically connected in a manner permitting 'backing out' after tripping.

6) The traverse power take off shall consist of an approved trailing cable system. An isolating switch shall be provided at the point of entry to the crab platform. This switch shall isolate the cross-traverse motion and shall be labeled "CROSS TRAVERSE-ON/OFF".

7) All crane wiring shall be installed in screwed conduit.

8) The control pendant shall preferably operate at 24V but not more than 50V. The push buttons shall return to the off position when pressure is

released. The pendant shall include a power on/off switch. The buttons for each motion shall be grouped together and shall be logically identified. The electrical conductors to the pendant shall not be used to support its weight. The pendant shall incorporate a 'power on' indicating light.

S5.07 DIESEL-DRIVEN STANDBY ELECTRIC POWER SYSTEM

(1) Scope

The work to be done under this section includes the design, manufacture, supply, shop testing, delivery, and the installation, testing, initial operation and complete with auxiliaries, capable of fully automatic black start and loading.

The work to be finished by the Contractor shall include the following.

(a) Diesel Engine
- Diesel engine
- Governor
- Fuel oil system
- Lubricating oil system
- Cooling system
- Air intake system
- Exhaust system
- Engine starting system, including battery and automatic charger
- Engine protective devices and instruments and control panel

(b) Generator
- Generator
- Excitation system
- Generator protective devices
- Generator instruments, and control panel

(c) Steel Base for Unit Mounting
- Steel base
- Vibration dampeners
- Oil drip pan covering full length of base

(2) Application

In the event of a failure of the incoming power, the diesel engine driven generator set will automatically start and be used to provide standby electric power to assist in starting

hydro-generating unit. The ambient air has H_2S present, and equipment shall be designed accordingly.

a. Requirements for Design

The rating of the generator, and thus the diesel, shall be suitable for the following duties.

1) The base continuous load that the diesel shall carry at all times will be the essential and emergency lighting, communication equipment, 2 battery chargers, cooling water system supply, 1 control building air conditioner and condenser unit, the town site water pump, guardhouse power supply and 1 station air compressor.
2) The diesel generator must be capable of starting the largest motor on the essential services distribution panel board with a base continuous load as specified in (a).

Preliminary sizing of the diesel generator indicates that 125kVA at 0.8PF is required. Final rating selection shall be made by the Contractor based on detailed load calculations.

The unit shall be capable of starting and loading automatically, as required, and of supplying an isolated load. Final design and rating shall be approved by DEDE.

b. Diesel Engine and Auxiliaries

1) Diesel Engine
The diesel engine shall be capable of operating on normal diesel fuel and shall not require premium diesel fuel for satisfactory performance. The engine shall be rated to produce the required output at 45°C ambient temperature and 99 percent relative humidity.

The diesel engine may be either normally aspirated or supercharged.

The engine and generator shall be supplied complete with a common bedplate suitable for mounting on a concrete foundation. Adjustable steel spring type vibration isolators with sound pads shall be provided for mounting between the unit base and concrete foundation. A suitable oil drip pan shall be provided under the full length of the diesel and generator to catch oil leakage.

2) Governor
The engine shall be equipped with a suitable governor for 50 Hz operation. The engine shall have a separate overspeed trip device to stop the engine in the event of the engine exceeding its safe speed.

3) Fuel Oil System
This system shall include for minimum one 100L, standard indoor fuel tank complete with fill-connecting piping, vent pipe, level indicator, low-level alarm, cradles and supporting structure, mounted for gravity feed to the engine pump. The system shall be complete with all interconnecting fuel oil piping and flexible connections. One hand-operated fuel pump shall be provided for pumping fuel from barrels to the fuel tank.

4) Cooling System
The cooling system shall be air-cooled, or oil cooled with shaft driven air fan.

5) Air Intake System
This system shall include an engine air cleaner, complete with support structure, intake piping, flexible connections and piping supports as required. The filter elements of the air cleaner shall be of a washable type. A differential pressure indicator shall be provided across the filter to indicate when the filter elements require cleaning.

6) Exhaust System
This system shall include a muffler, complete with support structure, exhaust piping, flexible connections, pipe supports, and insulation for exhaust from building. The muffler is to be located inside the building. The exhaust system inside the building shall be suitably insulated over its entire length. Noise is a critical factor, and the Contractor shall include the best muffler system available.

7) Starting System
This system shall include a heavy-duty starting motor, regulator, batteries of ample capacity, battery rack, jumpers, cables, and 2-rate automatic battery charger.

8) Protective Devices
The engine shall be provided with all necessary protective devices, safety features and controls which shall include, but not be limited to:
- Low oil pressure cutout
- Automatic over speed shutdown
- Over crank shutdown

9) Control Panel
The engine control panel shall be mounted on the unit and shall include, but not be limited to, the following instruments and controls.
- Complete engine automatic starting controls, including a test switch
- Safety devices
- lubricating oil pressure gauge

- lubricating oil temperature gauge
- Tachometer/hour-meter
- Start-stop automatic switch
- Automatic-manual control selector switch
- Cranking limiter
- Individual signal lights, manual resets, and common alarm terminal.

A remote alarm annunciator shall be provided in the control room.

10) Special Tools

The Contractor shall supply one set of any special tools necessary for the complete servicing and maintenance of the engine and all auxiliaries. The Contractor shall provide one barrel hand pump with all hoses, connectors, and fittings to fill the storage tank from standard fuel oil barrels.

c. Generator and Exciter

1) Generator and Exciter

The generator shall have a continuous rating of 125 kVA, 0.8 PF, 400/230V, 3-phase, 4-wire, 50Hz, and shall be capable of operating at 110 percent load at rated power factor and frequency for a minimum of 1 hour.

The unit shall be suitable for operation in a tropical climate, as stated in previous sections of the Specifications.

The generator shall be equipped with a direct coupled, brushless, or static exciter, designed and rated to match the generator's characteristics.

2) Construction

The generator and exciter shall be air-cooled, self-fan, ventilated type, in a drip-proof enclosure and winding insulation shall be Class F with a full amortisseur winding.

3) Voltage Regulator

A solid-state voltage regulator shall be supplied, capable of maintaining the output voltage within 1 percent of the rated voltage over the full operating range of the generator. Provision shall be made for manual adjustment of the regulated output voltage from 10 percent below to 10 percent above the nominal rated voltage.

d. Generator Control Panel

A totally enclosed sheet steel control panel with front hinged access door shall be supplied to house the following generator control equipment:

- AC voltmeter and ammeter with selector switch

- Automatic voltage regulator
- Frequency meter (48 to 52 Hz)
- Protection relays
- Battery, Charger with charging ammeter and voltmeter
- Automatic control and timing relays as required performing the functions of start/ stop diesel generator, closing generator breaker (located in AC station switchgear) when generator is up to normal frequency and voltage

The starting and stopping functions shall be controlled through separate timing relays to permit adjustable delay in starting and stopping over a range of 0.1 seconds to 10 minutes by both Locally.

e. Equipment Bases

The Contractor shall supply and install all equipment concrete bases. The final setting on bases shall be cement grout. The Contractor shall provide connecting bolts, gaskets, leveling shims, and washers, and shall supply the anti-vibration mounts for the diesel-generator unit and auxiliaries.

Each piece of equipment shall be installed strictly in accordance with the manufacturer's instructions. The complete initial lubrication of all equipment, including all gear cases, sump, and other oils shall be provided by the Contractor.

All equipment shall be factory painted in keeping with the requirement of Clause S1.11.

SECTION 6 - TESTS FOR MECHANICAL AUXILIARY EQUIPMENT

S6.01 TEST DURING MANUFACTURE

(Except powerhouse crane)

The mechanical auxiliary equipment shall be subject to the following tests at the Contractor's premises.

(1) Material Tests
Material tests shall conform to the requirements of Clause S4.01 (1) (a).

(2) Hydrostatic Tests
Hydrostatic tests shall conform to the requirements of Clause S4.01 (1) (b).

(3) Performance Tests

(a) Operating tests on all electric motors under conditions simulating the actual service for output, efficiency, power factor, temperature rise including oscillograms of starting and running current voltage.

(b) Hydraulic, pneumatic, and electric tests on all pumps, compressors, air-conditioning units, and fans under conditions simulating the actual service to demonstrate that the performance complies with the Contract and to establish complete operating characteristics. Particular attention shall be paid to limiting noise and vibration levels.

(c) Performance tests on the air-conditioning units.

S6.02 TESTS AT SITE

(Except powerhouse crane)

(1) Preliminary Test

The preliminary tests for the mechanical auxiliary equipment shall include the followings:

(a) Hydrostatic pressure tests on all piping systems. The test pressures shall be respectively the same as specified in Clause S4.01 (1) (b).

(b) Insulation and continuity tests on wiring including tests for correctness of connection.

(c) Checking pipework for freedom from obstructions.

(d) Checking for correct operation of each control, protection, and indication device.

(e) Checking the operation of all pump and compressor assemblies for vibration, overheating, leakage from joints, seals, glands, etc.

(2) Tests on Completion

For the mechanical auxiliary equipment, the Tests on completion shall include the followings:

(a) Tests of the correct functioning of automatic and manual control and protection equipment. These shall include a demonstration of correct repetition of twenty consecutive operating cycles.

(b) Tests to verify that the operation and system performance of all pumps and compressors are in accordance with the Contract.

(c) Tests to verify the performance of the ventilation and air-conditioning plant shall include:

- Continuous operation of all equipment for at least 50 hours to demonstrate that it will operate without overheating.
- The measurement of air quantities flowing in each ventilated or air-conditioned room.
- The measurement of temperatures and humidity in each air-conditioned room at regular intervals during a test period of 50 hours. These tests shall if practicable be carried out on days when outside air conditions are close to design extremes. The outside air conditioning shall be measured during the tests.

(d) The measurement of noise levels during the running of the plant at maximum load.

(e) Tests to verify that the operation and performance of other mechanical auxiliary equipment is in accordance with the Contract.

S6.03 TESTS DURING MANUFACTURE FOR POWERHOUSE CRANE

The power station crane shall be subject to the following tests at the Contractor's premises.

(1) Material Tests
Material Tests shall be as specified in Clause S4.01 (1) (a).

(2) Tests on Assembled Crane

All parts of the crane shall be fully assembled, wired, and tested for correct operation at the Contractor's premises. For these tests the hoist ropes need not be fitted to the drums.

S6.04 TESTS AT SITE FOR POWERHOUSE CRANE

(1) Preliminary Tests

The preliminary tests on the powerhouse crane shall be carried out as soon as erection is complete and shall include the checking of connections and testing for correct operation of all equipment.

(2) Tests on Completion

The following tests shall be carried out regardless of any tests which may have been carried out at the Contractor's premises

(a) Tests of the response to all controls, without load.

(b) Tests of the operation of the hoist, travel, and traverse limits, without load.

(c) Tests of operation of the brakes on the hoist when loaded to 25 percent in excess of the rated load.

(d) Measurement of the maximum deflections of the main beams of the crane under rated load and the overload conditions specified above.

(e) Recording the travel and traverse speeds under the overload conditions specified above.

(f) Measurement of the hook height from the assembly bay floor and total height of lift without load.

(g) Measurement of the hook approaches to the walls without load, and the overrun remaining when the limits have tripped, and the brake has applied.

(h) Measurement of the hoisting and lowering speeds without load and with rated load.

(i) Measurement of longitudinal travel and traverse speeds without load and with rated load.

SECTION 7 - GENERATOR AND AUXILIARIES

S7.01 GENERATORS

(1) Scope of Work

The work to be done under this section consists of the design, manufacture, supply, delivery to site, installation, commissioning and guarantee of synchronous generator Two (2) Complete Sets, unit capacity not less than 1,000kVA for 50 Hz operation, as specified herein.

(2) Purpose and Function

The generator supplied in this contract shall have a single driven shaft and have enough extended length to mount Pelton turbine runner. The unit shall be used to generate 3-phase, 3,300 (or) 690V, 50 Hz electric power at generator terminal, which will be stepped up to 22 kV, for incorporation into existing 22kV high voltage systems.

(3) Responsibility of the Bidder

The Bidder shall guarantee and be responsible for the hydroelectric generator supplied under this project.

- The output and efficiency of the generator and temperature rises of the various parts as specified under this section.
- Generator bearing housings for both DE and NDE sides shall be fixed at the generator casing with its own external lubricating oil system so that separate bearing housing design is not acceptable due to limited dimensions inside powerhouse.
- The Bidder shall submit with the Bid for the equipment layout drawings of synchronous generator, turbine runner with casing, inlet valve, draft tube, lubricating oil system and hydraulic oil pressure unit showing the actual dimensions of equipment to be located in turbine floor as preliminary design information to evaluate that the proposed equipment shall be installed inside the given dimensions.
- Flywheel dimensions and GD^2 value shall be provided in the bid to absorb momentary shock load at min 100kW within allowable frequency variation of 5% due to sudden changes of transient load during connecting with PEA grid without tripping generator circuit breaker.
- Furthermore, minimum dynamic forces such as axial, radial, and thrust forces which are necessary for Civil Work Contractor to design the foundation of major equipment.
- To indicate the strength and forces of all extended parts to withstand all mechanical and electrical forces and other related forces which may be

experienced in normal operation and emergency shutdown conditions as well as those caused by terminal and field short circuits, over speed conditions and any fault conditions.

(4) Standards and Codes

The work covered by these Specifications shall be designed, manufactured, and tested generally in accordance with the following standards and codes or approved equivalent.

- National Electrical Code	ANSI C2
- Rotating Electrical Machines	IEC 60034-1
- AC generators	ANSI C50.10, C50.12
- Standard Criteria and Definitions of Excitation Systems for Synchronous Machines	IEEE STD 421
- Shaft	ANSI B49.1
- Motors	MEMA MG 1
- Control Cubicles	MEMA SG 5
- Instrument Transformers	ANSI C57.13, NEMA EI 2
- Relays	ANSI C37.90
- Indicating instruments	ANSI C39.1
- Wire	Metric standard
- Screw threads	Metric standard
- Transformers	ANSI C57
- Definition of electrical items	ANSI C42
- Test Code for Synchronous Machines	IEEE No. 115
- Standard methods for determining losses and efficiency from tests	IEC 60034
- Electrical Insulation	IEC 60085, IEEE43

Where reference is made to any of the above standards and codes, the issue current at the time of design shall apply.

(5) Description

The units shall be of the horizontal-shaft, revolving field, synchronous brushless type and shall conform to the latest standards of ANSI or IEC or EN or IEEE Standards unless otherwise specified herein.

The Pelton runner shall be equipped and mounted at the extended synchronous brushless generator shaft with digital AVR excitation system of adequate capacity to meet all AC generation requirements under all possible service conditions.

(6) Capacity and Efficiency

The unit shall have a continuous rated output of not less than 1,000 kVA at 0.8 percent power factor (overexcited). The maximum temperature rise of both stator and rotor windings at rated output and normal conditions shall be 80˚C based on ambient air temperature not exceeding 40˚C in accordance with ANSI or IEC standards.

The units shall be capable of operation over the following conditions: -

- Generator output up to rated kVA continuously at voltages 5 percent above or below voltage for a range of power factors from 100 percent to 80 percent (overexcited) at 50 Hz system operation with a 40˚C ambient temperature.
- Guaranteed efficiency shall not be less than 95.5% at 0.8P.F. running at rated output not less than 1,000kVA.
- Short Circuit Ratio should be not less than 0.8p.u.

(7) Speed, Direction of Rotation and Frequency

The Speed of unit shall be designed and selected based on turbine design for 50Hz operation and shall be capable of operating continuously at a runaway speed to be determined by the turbine characteristics and shall be provided in the Bid.

The direction of rotation shall be counterclockwise when viewed from turbine side.

(8) Voltage and Phases

The unit shall be designed to deliver its rated capacity at a balanced 3-phase potential 3300 (or) 690 V between phases. The tests and guarantees shall be based on this voltage and 50 Hz operation. The unit shall operate successfully at rated capacity at 5 percent above or below rated voltage.

(9) Insulation and Noise Level

The generator stator windings and all connections, main and neutral leads, etc., shall be insulated in accordance with ANSI C50.10 and IEC 60085 and the Coil shall be treated with VPI (Vacuum Pressure impregnation) and have Class B temperature rise and Class H insulation for both stator and rotor.

The noise level should not be more than 85 dBA measured from 1 meter distance around the generator.

Failure to comply with this information will subject to rejection of the Bid.

(10) Harmonic Distortion, Wave Form and Telephone Interference Factor

The total harmonic distortion shall be not more than 5% according to IEEE standards or IEC 61000.

The potential wave form of the generator open-circuit terminal voltage shall not deviate from a sine wave more than 10 percent in accordance with ANSI standards.

The telephone interference factor shall be within the limits specified in ANSI standards.

(11) Flywheel Effect

The flywheel effect (WR^2) of the rotating parts of the combined turbine runner and generator shall be calculated as per the given information in the Bid so that the Bidder shall submit flywheel dimensions and GD^2 value together with the Bid Documents.

Failure to submit this information will subject to rejection of the Bid.

(12) Soleplates

The Contractor shall provide a baseplate for mounting the generator and shall be complete with anchor bolts and soleplates with anchors for grouting as required. The Contractor shall be responsible for ensuring that the soleplates are placed at the correct position and approval by DEDE Engineer. Means for adjustment shall be above the concrete surface.

(13) Stator

The Stator winding shall be insulated with Class H insulation as defined in ANSI or IEC standards.

(a) Stator Frame and Iron: The design of the stator frame, the soleplates, and the means of attachment of the soleplates to the frame shall be suitable to withstand all stresses to which they may be subjected in service as a result of all types of short circuits or faults.

Cast finger supports for the laminations will not be accepted.

To minimize the effects of end-iron heating during operation, adequate ventilation shall be provided, and nonmagnetic materials shall be employed where necessary.

The stator core assembly shall be constructed from low-loss cold-rolled silicon steel sheets. These shall be varnished to limit losses by Foucault current, cut into full sheets or sections, and stacked around a central mandrel. Radial ventilation ducts obtained by the welded air vents shall be provided to distribute air along the stator core.

(b) Stator Winding: The stator winding shall be made of copper conductors and the conductor strands shall be transposed to minimize stray losses. Facilities shall be provided for terminating the cable on the unit housing. Final details of the main lead termination at the unit shall be subject to approval by the DEDE Engineer. All bolted main current-carrying terminals shall be silver or tin plated.

The generator star neutral point shall be brought out and connected to the generator neutral resistance cubicle via Power cables. The location of the neutral resistor cubicle shall be installed nearby synchronous generator.

The stator winding shall be capable of successfully withstanding dielectric test in accordance with ANSI and IEC standards.

Adequate means shall be taken in the design and assembly of the stator winding to ensure the followings:

- The stator coils shall be adequately supported and braced to prevent dropping in the slots and to withstand the full stresses developed due to electrical fault conditions. Adjacent coil ends shall be held apart by spacers and bound to each other. Cording used to hold coils in position shall not be continuous (i.e. each coil shall be tied separately). The support rings to which the coils are lashed and supported shall be made of nonmagnetic material.
- The stator coils, when installed, shall fit firmly in the slots. A coil rejected because of slot fit shall not be used unless rebuilt.
- The stator coils shall be tightly wedged in the slots with wedges that will not buckle or shrink.
- The wedge in each slot shall be prevented from dropping out should it become loose in service.
- The stator coils, including spares, shall be manufactured to fit the stator core and end deformation will be the minimum necessary during installation.
- The insulation of the stator coils shall be sufficiently durable that, should it be necessary at any time to remove the coils, their removal and replacement may be carried out without damage to the insulation of any of the other coils. The quality and life of the insulation shall be impaired in attaining the above requirements.

- The stator coil insulation, wedging, packing, bracing, and typing shall be such as to minimize the effect of thermal shock and of additional differential expansion which may occur as a result of the overload conditions.
- All possible measures shall be taken to maintain the tight fit of coils in the slots to prevent vibration, loose wedges, and consequent high intensity discharge in the slots.

(c) Resistance Temperature Detectors: The Contractor shall supply 2 resistance temperature detectors per phase, embedded in the various parts of the stator winding in accordance with ANSI C50.10 or IEC standards.

The resistance temperature detectors shall be embedded in a suitable location, one at each end of the stator core for temperature measurement for the detection of end-iron heating.

The exact location of the resistance temperature detectors in the stator winding and core shall be subject to the approval of the DEDE Engineer. All resistor temperature detectors in and around the generator shall be wired to a terminal box mounted on the outside of the generator air housing. This terminal box shall be separated from other terminal boxes.

All connections from the resistance temperature detectors to the terminal boards shall consist of twisted leads in shielded instrument cables.

The resistance temperature detectors shall have a resistance of 100 Ohms at 0˚C over a temperature range of 0˚C to 120˚C.

All of the resistance temperature detectors shall be connected to AVR Module (or) the Unit PLC Control Panel for monitoring and protection of the Units.

(14) Rotor

The rotor shall consist of shaft, polar wheel, fan, balancing disc, excitation armature and rotating bridge rectifiers.

The rotor winding shall be insulated with Class H insulation as defined in ANSI or IEC standards and shall be designed to withstand 10 times rated field voltage or standard voltage dielectric test to ground for 1 minute.

Each field coil shall be fabricated so that the space between adjacent turns is completely and solidly filled with insulating material to ensure uniform insulation thickness between conductors throughout the coil. Every effort shall be made to avoid excessive deformation or burring of the conductor during the forming of the coil.

The design of the rotor shall be such as to permit the easy removal and replacement of the field poles. If tapered keys are used to secure the field poles to the rotor rim, the drive key shall project above the rotor rim a sufficient distance to facilitate removal of this key by means of a key puller and to permit checking for tightness after overspeed tests have been performed.

The polar wheel, referred to as salient pole rotor, shall consist of a laminated assembly.

(15) Reactance

The reactance values shall be provided in the Bid as manufacturer's preliminary design values such as the values for synchronous, transient, sub-transient and negative sequence reactance under unsaturated and saturated conditions with short circuit ratio values, armature time constants and armature resistance. The generator manufacturer's design curves such as Capability Curve, Short Circuit Curve, Efficiency Curve, and Transient Voltage Curve during load rejection, Stator Earth Fault Curve, shall also be submitted together with manufacturer's Drawings from factory having complete dimensions verifying such manufacturer is well proven and qualified manufacturer to produce the synchronous generator under European and American standards.

Failure to submit this information will subject to rejection of the Bid.

(16) Generator Enclosure

The generator enclosure shall provide an open-circuit ventilation system. The enclosure shall be arranged to permit easy removal for the purpose of inspection and maintenance.

No materials capable of supporting combustion shall be used within or in the construction of the generator enclosure. Anti-condensation space heaters, automatically controlled by thermostat shall be provided and the analog signal shall be sent to PLC for monitoring and protection.

(17) Cooling System

The generator shall be self-ventilating with its own fan cooling action being utilized the force air through the windings, ducts, etc. Fan blades on the rotor shall be given special care in their design and in securing them to the rotor so that they will be held rigidly in position at any speed which the rotor may attain.

The generator shall be of an open-cooled design. The generator cooling air, after passing over the field, stator iron and windings, shall be diverted through the generator housing and exhausted outside the powerhouse.

(18) Braking System

(a) The braking system shall be of the hydraulic oil pressure operated friction brake type and it is to be supplied from governor oil pressure unit.
(b) The brakes shall be interlocked with digital input contact via limited switch to Governor PLC so that the brake unit will not be applied at speeds more than 30% (or) when the turbine needle valve and deflectors are in opened position.
(c) Brake cylinder shall be provided with a limit switch, to provide status contact to Governor PLC for Brake Applied (or) Not Applied status. Governor PLC will apply brake during the unit stop (or) shutdown sequence at that time of unit speed is less than 30% of rate. Unit shutdown shall occur when the status of brakes is applied during unit speed more than 30%.
(d) To minimize scoring of brake tracks, ample area of brake lining shall be provided, and the type of lining supplied shall be matched to the hardness of the brake track surface (which shall be checked by measurement) according to the followings: -

Brake Track Hardness (Brinnel)	Brake Lining (Ferodo type, or Equivalent)
Less than 150	CR
150 to 200	MR, MZ or L
Greater than 200	BA

The brakes shall be located and arranged to minimize the entry of brake dust into the generator.

The evidence of Main Dimensional Layout of synchronous generator from Manufacturer's factory shall be submitted together with specific speed, rotational direction, material descriptions, GD^2 values, anchor bolts, etc. shall be submitted with the Bid to verify that the proposed manufacturer's design is complying with DEDE's specification and layout drawings attached in the Bid.

Failure to submit this information will subject to rejection of the Bid.

S7.02 SHAFT AND BEARINGS

(1) General

(a) The arrangement of shaft and bearings shall be of the form specified as above in Clause S7.01 with heavy duty roller ball bearing type.

(b) Bearing housing shall be directly fixed at Generator housing so that longer generator shaft and bearing operating life shall be properly designed to bear the weight of turbine runner and reliability of generating units.

The Bidder shall attach the generator layout drawings showing the above requirements with the Bid.

Failure to comply with this requirement will be subject to rejection of the Bid.

(c) The separate bearing housing from generator housing is not acceptable and it will be subject to the rejection of the proposed Bid.

(d) The Contractor shall carry out a detailed mathematical analysis of the rotating parts of the turbine generator and their support systems to ensure stability, considering amplitudes and frequencies of transient axial and lateral thrusts and tensional vibrations together with steady-state loads emanating from the turbine and generator. The calculations shall be submitted to the DEDE Engineer for approval.

(e) The Contractor shall be responsible for determining and applying the method of shaft and bearing alignment and for determining alignment tolerances.

(f) The Contractor shall provide a bending diagram for the turbine and generator shafts and the relevant information shall be incorporated in the Operation and Maintenance Instruction.

(g) The shafts, couplings and all rotating parts shall be designed to withstand any torque which the associated turbine can produce under any possible combinations of head, gate opening and speed.

(2) Shaft and Couplings

(a) The shaft shall be of forged steel machined all over. A secure means shall be provided to prevent water from entering into the shaft from the turbine end.

(b) Shaft couplings shall be made by flanges integral with the shafts. The couplings shall be provided with locating spigots and fitted bolts or shear bushes.

(c) The generator shaft and turbine couplings shall be coupled together and fully checked at the dimensions before delivery at the manufacturer’s factory.

(3) Bearings

(a) The generator bearings shall be heavy duty roller ball bearing type for both DE and NDE suitable for all operating conditions for starting and stopping, normal and emergency stop operation at rated generator output, and operation at up to the maximum runaway speed.

(b) Provision shall be made to prevent the flow of electric currents through the bearings. The bearing insulation shall be arranged by the use of an insulation/ metal/ insulation sandwich or similar method, so as to permit the insulation to be tested without dismantling any part of the unit.

(c) Bearing lubrication shall be used external lubrication grease or oil and the grade of oil which shall be readily available commercially in Thailand.

(d) The bearings housing shall be connected with external lubrication oil circulation for circulating hot oil in case of external oil lubrication system is used.

(e) An oil level indicator and sight glass with alarm contact shall be provided at bearing housing to give an alarm and interrupt the starting sequences in the event of low or high oil level in any bearing oil sump. No water-cooling pipes at bearing oil cooling are allowed so that precautions shall be taken to prevent water oil from coming into contact with the circulating air system of the generator.

(f) In case of external oil lubrication system is used, bearing oil shall be cooled by using external cooler with radiator (or) heat exchanger and shall meet the following requirements:

(i) The use of water-cooled bearings will not be accepted.
(ii) Fouling of cooler tubes by algae and/or bacterial growth is expected.
(iii) The coolers shall be made of suitable material to permit periodic, low concentration acid injection (ten parts per million residual chlorine) into the cooling water system for algae and bacterial growth control purposes.
(iv) Coolers shall preferably be so arranged that the water side of each section of a cooler can be safely drained, opened, and cleaned in turn while the generator is in operation.
(v) Pipe work shall be arranged to prevent emptying the cooling system when cooling water flow is stopped.
(vi) Cooling water source shall be taken from penstock pipe and supplied to the lubricating oil system and the Contractor shall provide the whole cooling system diagram of each turbine and generator unit shall be submitted for approval.

(g) The design of the bearings shall preferably be such that neither high pressure oil injection nor low pressure oil overflow during starting and stopping sequence is required.

The bearings shall not be damaged if the unit is stopped without the stopping and starting lubrication oil (or) grease oil supply being available.

(h) In case of lubricating oil pumping system is provided, it shall be supplied with enough capacity to circulate hydraulic oil having filters of sufficiently fine filtering capacity to prevent damage to any part of the bearing/ oil system by foreign matter.

(i) The oil temperature analog signals, starting and stopping digital signals of oil pump shall directly sent to Governor PLC for Unit protection purpose to be included in Sequence of Unit Start and Unit trip.

(j) The filters shall be fitted with differential pressure indicators to give an indication of the need for cleaning. Filters shall be capable of being individually cleaned without shutting down or reducing the output of the generator.

(k) All generator bearings shall be provided with a resistance temperature detector specified and the value shall be sent to AVR or Governor PLC control system for protection and monitoring purposes. They shall be located at the parts most sensitive to the maximum temperature in the bearing housing.

The preliminary lubrication oil (or) greasing system diagram shall be submitted along with the Bid indicating all components and instruments for bearing protection.

S7.03 SIGNAL GENERATOR

(1) General

The Contractor shall provide all devices necessary for the PLC control system as specified in these Specifications and for the proper operation, maintenance, and commissioning of the units.

(2) Speed Detector

(a) The Contractor shall supply one speed detecting device for each generator which shall be sent speed analog signal directly to Governor PLC Controller as speed detector. The detector shall be the speed measuring (or) sensing equipment which shall be a part of the unit control and indication system as specified in this Specification.

(b) The output of the speed detector shall be wired to shrouded terminals in a junction box on the generator from which the Contractor shall connect instrument cables to the speed measuring equipment at Governor PLC Panel.

(c) Rotating Speed of generator and turbine shall be derived from the two (2) inductive (or) NAMUR type sensors located at Non-Driven End of Generator using tooth wheel and the speed signals from two sensors shall deliver to Speed Monitoring Relay to indicate and divert 4-20mA to Governor PLC for speed sensing function. The independent speed sensing method shall be provided and mounted on the generator shaft without passing any fuse.

S7.04 EXCITATION SYSTEM

(1) Type and Performance

(a) A complete brushless digital excitation system with floor mounted cubicle, including automatic voltage regulating components and excitation transformer shall be supplied for each generator.

(b) Auxiliary Winding at Generator shall be provided with complete wiring and components for this system to provide the continuous power supply to digital AVR in case of not using excitation transformer with excitation control panel.

(c) The excitation system shall comply with the following performance:
   (i) The system shall maintain the generator voltage stable and equal to the value determined by the voltage setting device when the generator is operating connecting with the system (or) separated from the system.
   (ii) The maximum variation in generator terminal voltage when the operating conditions change from no load to rated generator output shall not exceed 1 percent.
   (iii) In the event of an increase in generator frequency up to that corresponding to the maximum rise resulting from the loss of the generator load, the excitation system shall remain stable, and it shall rapidly restore the voltage back to normal.
   (iv) During transient disturbances such as load variation (or) short-circuits in the system, the excitation system shall be capable of functioning correctly and, in addition, providing increased excitation as required.
   (v) Damping of oscillations between the generator and the power system shall be positive at all times and for all operating conditions within the capability of the generators.

(2) Exciter

(a) All equipment required for the excitation system offered shall be provided with ringless and brushless and PMI (permanent magnet insert type) and permanent magnets shall be mounted on the exciter armature poles to provide sufficient voltage. The voltage priming shall be performed in all circumstances, even after a long shut-down period.

(b) Static electronic equipment shall be constructed, to the maximum possible degree, as plug-in withdrawable modules.

(c) The semi-conductor equipment shall contain a number of devices connected in parallel, so rated that continuous operation of the generator at rated load will be maintained despite failure of any one paralleled semi-conductor circuit. Protective devices shall be provided in the control and in the semi-conductor circuits to isolate a faulty device without interruption of the generator excitation. The Bid shall provide details of the measures taken to ensure the reliability of the excitation equipment.

(d) The excitation equipment shall be protected from or shall otherwise withstand the maximum voltages and currents arising from short-circuits, out-of-synchronism operation of the generators, or failure of supply to the excitation system.

(3) Voltage Regulators

(a) A digital type of automatic voltage regulator (AVR) shall be provided for the generator excitation system. The excitation current capacity for the AVR shall be limited until up to 7A where the other parts of the exciter system design shall be able to work with this arrangement.

(b) A manual control facility shall also be provided for the generator excitation system. Facilities shall be provided at the excitation equipment, to enable changeover from AVR to manual control of the excitation level.

(c) Besides Manual Control, the AVR unit shall have Open Loop Control mode where there is no feedback loop on the Generator Voltage (Auto Mode) or Excitation Current (Manual Mode). Selector Switches shall be provided in front of cubicle.

(d) AVR control loop feedback algorithm shall be PID (Proportional, Integral and Differential) type only. Filter type algorithm, or any other algorithm besides the PID type is not acceptable.

Evidence for providing PID Controlled AVR shall be attached with the Bid.

(e) The AVR unit shall have build in soft start function under Auto Mode; where the Start Frequency (Hz), Start Level (% of Rated Voltage), and Ramp Time (Seconds), shall be provided under this function. External switches, Timer relay, separated PLC to achieve this function is not acceptable.

(f) Exciter Rotating Diode monitoring function shall be built into the AVR unit, where two dedicated switch outputs shall be provided in the event of Alarm and Trip, this is on top of the other AVR Alarm/ Trip outputs to main PLC.

(g) The AVR shall be supplied power from generator auxiliary winding source (or) excitation transformer from Excitation Transformer Panel.

(h) The AVR shall be responsive to the positive phase-sequence component of the generator voltage and shall be independent of frequency.

(i) The voltage setting device for the AVR shall be suitable for operation by hand at control cubicle and by remote control. The device shall provide a settable range of ±10% (with adjustable) of nominal generator voltage.

(j) Communication ports shall be available at AVR module to configure without power supply such as Ethernet Modbus port, USB port, Serial ports, CAN BUS, etc.

The Bidder shall submit the manufacturer's catalogues and layout cubicle drawings for excitation system with component list with the Bid.

Failure to submit this information will subject to rejection of the Bid.

(4) Field Circuit Breaker and Switches

(a) Field Circuit Breaker and switches required for the excitation system shall be mounted in the excitation cubicles (or) other control cubicles.

(b) Field switches shall be generally in accordance with IEC, EN (or) ANSI and shall be fitted with all necessary devices for control and indication.

(5) Excitation Transformer (if applicable)

Excitation transformer shall be provided (if necessary) as per design criteria and excitation DC current, so that excitation transformer shall be 3 phase, indoor housing, epoxy cast resin, cast coil, copper conductor, dry type with class F insulation, self-cooled 80º Celsius temperature rise at 40º Celsius ambient

temperature connected to generator terminal of 3300 (or) 690Vac. Busbar support with insulator, power cables and fuses for each phase shall be used if necessary. Ventilation fans and filters for the excitation transformer panel shall be provided with thermostat control.

The Bidder shall submit the manufacturer's catalogues for AVR, excitation transformer in the proposed excitation system with drawings and component list with the Bid.

Failure to submit this information will subject to rejection of the Bid.

S7.05 INSPECTION AND TESTS

(1) Factory Test

Generators shall be tested at factory in front of DEDE Engineers and the test program with procedures shall be submitted to DEDE for approval.

The Bidder shall submit the list of Factory Witness Test items according to IEC and IEEE standards so that the evidence shall be submitted with the Bid.

The Bidder (or) Contractor shall perform the test for Generator, excitation system, lubrication oil (or) grease supply system at manufacturer's factory to verify that these are able used together without any trouble. Contractor shall bear all travelling expenses (air tickets, accommodation, meal, allowance, etc.) for two (2) DEDE Electrical Engineers (as Witness) to attend the test at factory and sign for approval of test results before delivery to site. If there is any defect (or) rejection of manufactured equipment, the Contractor shall perform the same test at factory again after correction with his own cost.

(2) Individual Parts

All stator and rotor coils for the generator shall be tested in the factory for grounds and short circuit between turns. In testing the generator field coils for shorted turns, readings shall be taken of ac amperes, volts, and watts, preferably using the same value of current to test all coils. Certified test reports for generator current transformers, as specified elsewhere, shall be submitted to the DEDE for approval before Witness Test.

(3) Generator

Test for Generator Unit shall be done determine the performance to determine the guaranteed efficiency as per Contract. The tests shall be done at the manufacturer's factory together with the excitation system and lubrication system.

All tests shall be performed in accordance with IEEE Test Procedures for Synchronous Machines No.115 (or) IEC Test Procedures for Synchronous Machine so Contractor shall submit the test items, procedures to submit DEDE Engineer's Approval.

(4) Excitation System

Tests on the excitation system, including tests on the components shall be proposed by the Contractor, incorporating reputable international standards, for the approval of the DEDE Engineer.

Functional tests shall be done combined with Generator so that the other internal test shall be done at excitation system factory and test reports shall be submitted to DEDE for approval.

(6) Performance of Tests after Installation

All tests made at the Site shall be performed by the Contractor. The Contractor shall submit to the DEDE Engineer for the method of performing tests. The Contractor shall ensure that all necessary precautions are taken to guard against accident or damage to persons or property in performing the tests and shall arrange for the supply and erection of all necessary barriers, guards, and danger signs for safety purpose.

The Bidder shall submit the Field Test and Dummy Load Test Procedures of Turbine and Generator Performance according to the applicable IEC Standards showing the diagrams, measuring methods with instruments and calculation criteria of efficiency together with Bid.

Failure to provide information will be subject to rejection of the Bid.

Furthermore, for the completion of Testing and Commissioning, The Contractor shall perform the following tests for the generating units by connecting to the PEA power grid system:

- Dummy Load Test
- Dummy Load Test Operation of complete excitation system including automatic voltage regulating equipment at various loads and including load acceptance and rejection test at 25, 50, 75, 100% of load.
- Continues Load Test for 48 hours to the PEA Grid

SECTION 8 - AC STATION SERVICE TRANSFORMER AND AC SWITCH BOARD

S8.01 SCOPE OF WORK

The work to be done under this clause consists of the design, manufacture, supply, delivery site, installation and guarantee of the following equipment: -

- One (1) set of 160kVA, 50Hz, Dry type epoxy cast resin with metal-enclosed indoor, station service transformer
- One (1) set of 600Vac, AC Distribution Board, metal-enclosed, indoor station service LV switchgear

S8.02 PURPOSE AND FUNCTION

Station service transformer (SST) shall be provided and to be used for stepping down the system voltage from 3.3 (or) 0.69kV to 400/230V to use for Station Service AC Power Supply through AC distribution board. The transformer shall supply power to the units and powerhouse auxiliary services.

In case of the loss of generating power (or) in case of Unit Black start, the standby diesel generator shall be started automatically to supply AC power to the plant auxiliary equipment.

S8.03 STATION SERVICE TRANSFORMER

The transformer shall comply with TIS 384 (or) Provincial Electricity Authority's standard (or) other reputable international standards. The continuous rating of the transformer shall be 160 kVA based on an average copper temperature rise of 80˚Cover the ambient of 40˚C. No-load losses and load losses shall not be more 860 and 2,600 watt respectively

The main characteristics of the transformer shall be as follows: -

Type	-	Indoor metal-enclosed
Class	-	Dry type, epoxy cast resin encapsulated,
Rating	-	160 kVA, 3-phase, 50 Hz
Primary voltage	-	3.3 (or) 0.69kV, delta-connected
Tap range	-	4 Full-capacity, off-load, High Voltage taps at ± 2 ½ % and ± 5 %
Secondary voltage	-	400/230 V, wye-connected, grounded neutral
Cooling	-	Self-Cooled (AA)

Basic insulation level of HV/LV Windings (minimum dry 1 min)

Power Frequency Test (1 min)	-	19 kV (Primary), 4KV (Secondary)
Basic Impulse Level Test (BIL)	-	40 kV (Primary), 10 KV (Secondary)

The high voltage bushings shall be connected from the Load Break Switch feeder and Lightning arresters as shown in Single Line Diagram. The connection cable to the low voltage bushing terminals of the transformer shall be with power cable. The Contractor shall supply the required current-carrying capacity and brace for the required fault levels for all phases and neutrals.

Ground Connections

The transformer shall have clamp type terminals for connection to the powerhouse ground system. Clamps and bolts, to accommodate a 95 mm^2 stranded cable, shall be provided for ground connections to the transformer core and to 2 points on the transformer enclosure.

Tap Changer

The transformer shall be equipped with a selector for off-circuit changing of the taps. This device shall have a lockable handle and position indicator external to the transformer enclosure.

High Temperature Detection

The transformer shall be equipped with the oil temperature-sensing element with alarm contacts, and it shall be sending status to HMI PLC Monitor for alarm and trip.

Auxiliary Power

Power from the station battery at 125 V dc (nominal) will be available for the instruments for transformer auxiliary circuits.

Details of the tests to be performed by the Contractor on the various components of the equipment shall be stated in the Bid and, in general, shall be as follows.

Factory Tests

Complete tests on the equipment shall be made at the factory by the manufacturer in accordance with ANSI (or) IEC standards for indoor dry type transformer, to determine the performance and operating characteristics and to confirm that the equipment functions properly. In addition to these tests, the following test shall be performed.

Standard insulation withstands tests on all small wiring and on all auxiliary devices at 1,500 V to ground, 50 Hz, for 1 minute.

Site Tests

The Contractor shall check the operation of all auxiliary circuits such as gauges, etc.

The Contractor shall carry out any other tests recommended to prove that the transformer is properly installed and adjusted to operate correctly and safely.

Tests shall be in accordance with Provincial Electricity Authority (PEA)'s regulation (or) IEC and ANSI Standards.

S8.04 HIGH VOLTAGE LOAD INTERRUPTING SWITCH (Not applicable)

The high voltage fuse load interrupting switch (3P-PF) shall be 3-pole group operate for the voltage and basic impulse level specified and shall be rated for 100-A continuous and 16,000 A interrupting current (momentary). The switches shall be mounted on NEMA rated porcelain insulators for the voltage and basic impulse level specified. The operating mechanism shall include porcelain linkage connections to switch blades with porcelain having a basic impulse level rating at least equivalent to the switch insulators. Switch mechanisms shall be operable externally from the front of cubicle and be equipped with a quick make-and-break device to open and close the switch independently of the speed with which the operating handle is moved. The load break switches shall be capable of closing in on at least 40,000 A asymmetrical fault current without impairing the ability of the switch to carry its full rated continuous current.

Six-pole, auxiliary switch shall be provided for alarm and interlocks.

Switch Ratings

SST Interrupting - 100 A, 3-pole, 40 kV basic impulse level (minimum) with current limiting fuses

Tests

Tests shall be in accordance with IEC (or) ANSI. The following tests shall be made on each load interrupter switch:

- dielectric
- short-time current
- interrupting
- Corona.

S8.05 AUTOMATIC TRANSFER

All necessary sensors, relays, and controls, etc., shall be provided to automatically transfer the load to the alternative source upon failure of the normal AC source. It shall also be possible to connect a diesel generator unit to the LV switchgear.

The preferred source for station service requirement will be the supply from station service transformer (SST) which is fed from the low voltage side of main transformers.

The automatic transfer and sequence of operation shall be as follows. Refer to Drawing for the station service, single-line diagram.

When transformer SST is de-energized and SST will open, then the diesel generator set will start. When diesel is up to full speed and voltage required, DG breaker will close to energize.

When normal power is restored from SST breakers, DG breaker will open first, and breaker SST will close to re-energize. The diesel generator will shut down after DG breaker is opened.

The Contractor shall supply all the controls, relays and equipment required to carry out automatic transfer of power sources as described.

Power	SST	MCCB (DG)
Source	E	E
SST	X	O
Diesel gen.	O	X

Operating Sequence

X = closed
O = open
E = electrically operated

Annunciation

The following operation shall be announced.

- Transfer from SST to diesel generator
- Return to SST from diesel generator
- Blocked auto transfer caused by selector switch in manual or withdrawal of supply or tie bus breakers.

The annunciation of all the above conditions is primarily to notify the operator of the status of the breakers and should be alarmed by the control room annunciator.

Test Switch

A test switch which is located on the main control board shall allow the testing of the Automatic transfer scheme by simulating an undervoltage condition of the preferred and alternative power source and causing an actual transfer of power sources.

Selection of Manual Control

Placing the selector switch in the manual position shall make the automatic transfer scheme inoperative and will allow each individual breaker to be operated by its own control switch.

S8.06 NO-FUSE BREAKER

No-fuse breakers shall be molded case, manually operated, quick make, quick break with both thermal and magnetic trip elements on each pole. All breakers shall be rated for 600V and shall have an interrupting rating not less than 30,000 rms A asymmetrical at 400V.

S8.07 SECONDARY WIRING AND TERMINALS

The switchboards shall be complete with all accessory secondary wiring. All wiring shall be stranded copper conductors. Conductor insulation shall be flame-retardant, heat-and moisture-resistant and shall be of the thermoplastic or thermosetting type. The insulation shall be rated at 600 V with a temperature rating of 90˚C.

Wire sizes shall not be less than 4 mm^2 for current transformer wiring and 1.5 mm^2 for control, metering, annunciation, and potential circuits.

The secondary leads of instrument transformers shall be brought out through test blocks with molded phenolic covers which have internal plug contacts and make a through connection when the cover is in place. The test block contacts shall be of the live pressure type to provide positive contact with minimum contact resistance and make a through connection when the cover is in place.

The test blocks of current transformers shall be provided with auxiliary contacts which automatically short circuit the current transformers when the cover or plug is removed. The test block contacts shall be minimum rated 600 V, 10A continuous.

All wiring shall be run in plastic wiring duct or shall be formed into compact flat groups suitably bound together and properly supported. The group shall be run straight, horizontally, or vertically, with short-radius right-angle bends. There shall be no splices in the wiring and all connections shall be made at 600V, 25A terminals. Suitable provision shall be made for training and supporting incoming cables from the point of entrance to the termination on the terminal blocks.

All wiring shall be identified at both ends with PVC cable markers which resist grease, oil, acids, and abrasion.

The arrangements and locations of all terminal blocks shall be subject to the approval of the DEDE Engineer. Circuits on the terminal blocks shall be marked with permanent marking fluid and shall be subject to the approval of the Engineer. A minimum of 20 percent spare terminal blocks shall be furnished.

S8.08 CONTROL SWITCHES AND INDICATION

One (1) selector switch for selecting Remote and Local Control for the breakers mentioned above.

Indicating Lamps for all phases, annunciator window for Fault and Trip of Breakers showing clear wording shall be installed in front of Annunciator Window.

Mimic Indication in Single Line Diagram in front of AC Distribution Front Door and the mimic graphic shall be submitted to DEDE for approval.

S8.09 INTERLOCKING

All circuit breakers controlling supply points shall be electrically interlocked to prevent the interconnection of supplies. Breaker auxiliary contacts and auxiliary relays shall be used in the interlocking circuit.

Lockout devices shall be provided if applicable so that if a breaker is tripped by its own under current protection scheme, other breakers feeding into the same bus cannot be closed.

Remote Indication

The LV switchgear shall have incorporated in the metering and control circuitry, provision for remote indication of the followings: -

"Open"
"Close"

Circuit	Indication	Ammeter	Voltmeter
Voltmeter			
Breaker SST	X	X	X
Breaker DG	X		

S8.10 CURRENT TRANSFORMERS

Current transformers shall be supplied in each of the transformer secondary breaker sections of the station service switchboard. The current transformers shall be of the 55˚C rise dry type, used for metering and protective relaying, and shall be supplied as follows in accordance with the latest edition of ANSI C57.13 for instrument transformers, or DEDE approved equivalents.

(a)	Purpose	-	Metering
	Quantity	-	3
	Ratio	-	250/5A
	Frequency	-	50 Hz

	Accuracy	-	0.5
(b)	Purpose	-	Protection
	Quantity	-	3
	Ratio	-	250/5A (or) 1000/5A
	Frequency	-	50 Hz
	Accuracy	-	5P20

S8.11 VOLTAGE TRANSFORMERS (If required)

Voltage transformers shall be indoor dry type, single-phase with both windings connected in open delta. The voltage transformers shall be rated as follows.

Three voltage transformers shall be provided for metering and undervoltage relaying on each incoming bus section.

Voltage	-	600V
Capacity	-	min. 10VA
Accuracy	-	metering 0.5, protection 3P
Quantity	-	6

S8.12 INSTRUMENT SECTIONS

The station service switchboard shall be provided with instrument sections. The instrument sections shall house the instruments, protective relays and voltage transformers as specified.

AC Ammeters

Ammeters shall be flush-mounted, taut-band suspension type, not less than 110 mm square with circular scale not less than 180 mm in length for 250-deg rotation, black figures on white background, 1 percent accuracy class, 0 to 200A scale for 5A, 50Hz circuit.

AC Voltmeters

Voltmeters shall be taut-band suspension type, flush-mounted, not less than 110 mm square with circular scale not less than 180 mm in length for 250 deg rotation, black figures on white background, 1 percent (%) accuracy class, 0 to 600 V for 110V, 50-Hz circuit.

Watt Hour Meters or Power Meter

Polyphase watt hour meters, for a 3-phase, 4-wire circuit, current transformer rating 900-5 A, voltage transformer rating 400-110 V, 50 Hz, to read and indicate kilowatt hour and kilowatt demand, complete with mechanical demand register, 5 dials, with anti-reverse device for unidirectional operation.

AC Voltmeter Switches

Voltmeter switches shall be rotary, panel-mounted type, enclosed contact mechanisms with removable cover, renewable, self-cleaning, maintained 6 normally open and 6 normally closed contacts, rated 600V, 20A continuous, 50A make and 30A break at 120V, 50Hz inductive load, pistol-grip handle, 4 positions with escutcheon plate engraved "OFF", 1-2, 2-3, 3-1", and wired for 3-phase, 4-wire circuit.

Relays

- 51, inverse time over current phase consisting of 3 single-phase relays, semi flush mounting in draw out case
- 51N, inverse time over current, semi flush mounting in draw out case.

It is intended that this relay, upon sensing a ground fault, shall trip the incoming breaker. If the fault persists it shall then trip 52G. This same sequence of operation shall apply to the new Unit.

- 27S/59, Under and Overvoltage relay for use with automatic transfer scheme, semi flush mounting in draw out case.

- Auxiliary relays as required for automatic transfer scheme.

The number of instruments and relays which shall be provided for the AC station switchboard shall be as follows.

Frequency meter	1
Wattmeter	2
Ammeters	2
Voltmeters	2
Kilowatt hour meters (or power meter)	1
Voltmeter switches, Ammeter Switch	2
All meters can be used with two sets of power meter	
51 relays	3
51 N relays	1
27/59 relays	1

All meters can also be integrated in Digital Multimeter and provide two sets of power meters.

All protection relays shall also be combined and in Multifunction Relay and comply relaying functions as per the single line diagram.

S8.13 GROUNDING

A grounding copper bus bar not less than 5mm by 50mm shall be provided along the front and rear of the switchgear. The ground bus shall be solidly bolted to the steel framework so as to make good electrical contact. Provisions shall be made at both ends of the switchgear for connection of the ground bus to cables from the station ground mat. Two clamp type terminals suitable for 95-mm^2 stranded bare copper conductor shall be provided. All non-current carrying parts shall be connected to the ground bus.

S8.14 NAMEPLATES

Nameplates of black background with white lettering and shall be provided for all LV. Switchgear identifications. Transformer nameplates shall be 22 cm wide by 4 cm high, with letters 19 mm high, centered on the plate.

All nameplates shall be attached to the switchgear with rust-resistant steel, self-tapping screws. The transformer, switchgear and all switchgear appurtenances shall be identified, and all nameplates shall be subject to the DEDE Engineer's approval.

S8.15 CHANNEL BASES AND BOLTS

The Contractor shall provide the foundation bolts and channels necessary for holding down of fixing the equipment to the concrete foundations. Where the design of the equipment requires special clamps to be used with the foundation bolts, these clamps shall be provided by the Contractor.

S8.16 TESTS

The assemblies and their individual components shall be factory and field tested by the Contractor in accordance with the test specifications outlined herein.

Factory Tests

The following tests shall be made according to the appropriate standards to ensure compliance with specifications.

Switchgear Assemblies

- Standard production tests as specified in NEMA SG 5 and ANSI C37.20 or approved equivalent
- Impulse and thermal tests as specified in NEMA SG 5 and ANSI C37.20 or approved equivalent.

Operational Checks

- Continuity and polarity tests on all coils and circuits
- Functional tests on the automatic under-voltage transfer scheme, and on overcurrent protection.

Field Tests

Such tests shall be carried out in the field, as are necessary in the opinion of the Engineer, for the satisfactory start-up and operation of the apparatus. These will normally comprise of:

- Control and secondary wiring check of complete installation
- Dielectric tests on control and secondary wiring using 1,000V megger
- Functional tests of the breaker operation, metering, relaying and the automatic transfer scheme.

SECTION 9 – GENERATOR TERMINAL CUBICLES, TRANFORMER TERMINAL CUBICLES, BUS DUCTS AND NEUTRAL CUBICLES

S9.01 SCOPE OF WORK

The work of be done under this section consists of the design, manufacture, testing, delivery to site, installation, placing in successful service, and guarantee of:

- 2 generator circuit breaker cubicles (Gen Switchgear)
- 2 generator excitation transformer cubicles (if applicable)
- 1 station load break switch cubicle (or) station service DS cubicle
- 2 generator neutral cubicles (NGR)

S9.02 PURPOSE AND FUNCTION

Generator Circuit Breaker Cubicles (Gen Switchgear)

The generator terminal cubicles shall contain generator circuit breakers, surge arresters, dry type single phase current and voltage transformers for metering, protection, and synchronization.

Generator Excitation Transformer Cubicles (if applicable)

The Generator Excitation transformer cubicles shall contain excitation transformers to supply the generator excitation systems.

Generator Neutral Cubicles

The neutral grounding equipment is to be used for grounding the stator winding neutrals of the generators. The stator winding neutral grounding equipment shall be suitable for limiting damage and detection of stator ground faults. The resistance capacity and the rating shall be calculated and selected to suit the generator rating.

S9.03 STANDARDS

The equipment and accessories shall be designed, manufactured, and tested where applicable, in accordance with the IEC (or) EN (or) ANSI standards.

9.04 GENERATOR CIRCUIT BREAKER CUBICLES AND BUS DUCTS RATINGS

The generator circuit breaker cubicles shall be of metal-enclosed construction in accordance with the requirements of IEC (or) ANSI standards unless otherwise stated herein. Circuit Breaker Type test report and selection of the proposed switchboard/ cubicles and generator circuit breaker shall be submitted together with the Bid.

S9.05 EQUIPMENT DETAILS

Generator Circuit breaker Cubicles (Gen Switchgear)

The Contractor shall supply two (2) generator circuit breaker cubicles, and each cubicle shall consist of the following.

Quantity	Descriptions
2	A metal-clad compartment design (Circuit breaker compartment, busbar compartment, cable compartment and low voltage compartment) shall be supplied to house the generator circuit breaker, current transformer, and voltage transformer. The three (3) poles circuit breakers shall be supplied and single throw having the following minimum ratings.

The rating of the generator circuit breaker cubicles and accessories shall be as follows:

- Voltage	3.3 (or) 0.69 kV (nominal)
- Frequency	50 Hz
- Phases	3
- System	3-wire delta
- Continuous current (minimum)	800 (or) 2000 A (minimum)
- Short-time (3 seconds) current	25 (or) 50kA
- Momentary (1 second) current	25 (or) 50kA
- Temperature rise (above 40˚C ambient outside of the enclosure for the generator terminal cubicles)	70˚C indoor

Generator Circuit Breaker

Quantity	Descriptions
2	Indoor, fixed type, three (3) pole, air insulated circuit breaker with auxiliary contacts for receiving and tripping command from protection and control system and shall have the following ratings:

Type	Indoor and mounted in Switchboard
Rated Operating Voltage	3.3 (or) 0.69kV
Rated Insulation Voltage	3.6 (or) 1.0kV (or) higher
Frequency	50 Hz
Continuous current	600 (or) 1600 A (minimum)
Short Circuit Breaking capacity	25 (or) 42kA (minimum)
Short time withstand (3s)	25 (or) 42kA (minimum)
Rated short circuit making capacity (peak)	88 kA (minimum)
Control Supply Voltage	125 V DC

12	Current transformer single phase, ring type for relaying, dry type:	
	- Ratio	400 (or) 1600/5A
	- Accuracy	5P20 for protection and 0.5 for metering
	- Insulation Class	Class B
6	Voltage transformers, single-phase, dry type, indoor	
	- Ratio	3300 (or) 690/110V
	- Capacity	15VA minimum
	- Accuracy	0.5 for metering and 3P for protection
	- Insulation Class	Class B
6	Lightning arrester, gapless type	

Station Service DS (or) Station Load Break Switch Cubicle

The Contractor shall supply One (1) Station Service DS (or) Station Load Break Switch Cubicle and each cubicle shall consist of the following.

Quantity	Descriptions
1	A metal-clad compartment design (DS compartment, busbar compartment, cable compartment and low voltage control compartment) shall be supplied to house the three (3) pole disconnector/ breaker shall be supplied with the following minimum ratings.

Disconnector/ Load Break Switch

Quantity	Descriptions	
1	Indoor, fixed type, three (3) pole, air insulated circuit breaker with auxiliary contacts for receiving and tripping command from protection and control system and shall have the following ratings:	
	Type	Indoor and mounted in Switchboard
	Rated Operating Voltage	3.3 (or) 0.69kV
	Rated Insulation Voltage	3.6 (or) 1.0kV min.
	Rated Impulse Withstand Voltage	12kV
	Frequency	50 Hz
	Rated uninterrupted current	600 A (minimum)
	Short time withstand (3s)	25 (or) 36kA (minimum)
	Short circuit making capacity (peak)	75.6 kA (minimum)
	Control Supply Voltage	125 V DC

Generator Neutral Cubicles (NGR)

The Contractor shall supply two (2) generator neutral grounding (NGR) cubicle and shall consist of the followings: -

Quantity	Descriptions
1	Current transformer, dry type, for protection shall be rated as follows: - - Ratio 400/5A (or) 1600/5A - Accuracy class 5P20 - Insulation Class Class B minimum
1	Single Phase Neutral Grounding Resistor, dry type, with the rated voltage of 3300 (or) 690V and the resistor shall be designed by Generator supplier for such that maximum line to ground fault current for 10 seconds and in accordance with IEC (or) EN (or) ANSI standards so that calculation sheet shall be submitted to DEDE for approval.

S9.06 DESIGN AND CONSTRUCTION OF GENERATOR TERMINAL CUBICLES

The Generator terminal cubicle shall be indoor, air-insulated, metal-enclosed, switchboards and it shall be complete, ready for installation at site, with all components furnished unless specifically excluded herein.

The switchboard shall be designed and tested as per the latest updated IEC standards.

The housing, partitions, etc., shall be fabricated from sheet steel panels having a minimum thickness of 2mm, structural shapes and nonmagnetic materials where required, in such a manner that the complete structure shall be rigid, self-supporting, and free from magnetic vibration, twist and weave.

The switchboard shall have the compartments that are busbar compartments, circuit breaker compartment, and low voltage compartments. There shall be a partition to separate each bus bar between the adjacent one.

The partition between the circuit breaker and busbar compartment shall be made of metal or bakelite plate (thickness minimum 4mm). All plates inside the panels used for construction of the walls, partitions, hinged doors, and removable panels, shall be adequately supported, and stiffened to prevent flexing and excessive vibration.

Each cubicle shall be provided with a steel channel base frame with provision for bolting it to the concrete floor and placed adjacent to the panel of the station service transformer cubicle. The switchboards shall be of the same type and model for generator circuit breaker cubicles (Gen Switchgear), generator excitation transformer cubicles (if applicable), station load break switch cubicle (or) station service DS cubicle inside the control room (or) electrical room at powerhouse.

The openings shall be provided in the bottom of each panel housing to permit the entrance of instrument transformers, power cables and control cables which will be terminated in the auxiliary compartment.

An electric heater 220Vac to prevent condensation shall be provided for each panel.

The Contractor shall be responsible for the coordination, proper physical fit, and other interfacing functions, including the location and phasing of bus terminations. The surge protectors, voltage transformers, buses and bus connections in each cubicle shall be installed in cable compartment of the same panel and the auxiliary compartment shall be provided

containing the voltage test devices, voltage transformer secondary fuses, current test link blocks and termination boards.

A hinged door shall be provided on the front of the auxiliary compartment. All hinged doors shall be equipped with semi-concealed highs and suitable locks. Similar locks shall also be provided on the voltage transformer drawers.

All compartment doors shall be constructed so that they will not seize in the event of a fire within the cubicle.

Ventilating louvers shall be provided in the hinged doors, and in other locations where required, to prevent undue temperature rise. The ventilating louvers in the hinged doors and in other locations of the housing shall have openings small enough to prevent the entrance of rodents and insects. Openings between adjacent compartments for ventilation purposes will not be permitted.

Entrance bushings shall be used for insulating and supporting the buses and bus connections that pass from 1 compartment into another. Where the use of bushings is not practical due to space limitations, panels of approved insulating materials may be used instead for this purpose. The arrangement chosen shall ensure a reasonably tight seal between compartments.

All materials used in the cubicles, such as bus insulation, bus supports, etc., shall independently support combustion.

Equipment and connections within each compartment shall have their mounting bolts arranged so that it will be possible to replace them without removing from service equipment in adjacent compartments.

The voltage transformers shall be single-phase, and each voltage transformer circuit shall be furnished with the current-limiting fuse.

The voltage transformers and fuses shall be completely disconnected and visibly grounded when in position to permit inspection or to permit access for removal or replacement of fuses.

The voltage transformer core shall not saturate at voltages lower than 110 percent of system voltage. The voltage transformer assembly shall have provision for padlocking in the disconnected position, and it shall be possible to close the outer door with the voltage transformers left in the disconnected position.-

The buses and bus connections shall be of copper bar and supported on suitable insulators and properly braced to withstand the short-circuit forces. The bus bars shall be fully insulated throughout and also at tap-off points using flame-retardant, track-resistant, non-hygroscopic materials.

Joints between bus sections, etc. shall have their contact surfaces, and shall be fastened with stainless steel bolts, nuts and locking devices.

Bus bar supports between panels shall be tightly sealed between compartments. means of linear expansion shall be provided.

Means shall be provided for permanent grounding of all exposed non-current-carrying metal parts of the generator terminal cubicle and secondary neutrals of the instrument transformers as required by the specified standards. All parts of the framework shall be in good electrical connection with one another for grounding purposes.

A continuous ground bus, extending the full length of each cubicle, shall be provided. A non-solder lug, suitable for connection of the stranded copper conductor, shall be provided at each end of the ground bus.

S9.07 DESIGN AND CONSTRUTION OF GENERATOR NEUTRAL CUBICLES

Each cubicle shall be fabricated from sheet steel, floor standing cubicles and shall install nearby generators at turbine floor.

The incoming cables from the generator terminals shall enter through the bottom of the cubicle via cable trench, tray, and conduits.

Each cubicle shall be provided with hinged door (s) at the front of the cubicle, each door completes with latching device and lock. A wire-glass window shall be inserted in the front door, located so that the position of the isolating switch may be observed without opening the door.

An electric heater to prevent condensation shall be provided. Means shall be provided for permanent grounding of all exposed non-current-carrying metal parts of the generator neutral grounding cubicle.

S9.08 WIRING AND WIRING TROUGHS

Care shall be exercised in routing and clamping the switchboard wiring to prevent damage to the cotton-braid covering and thermoplastic insulation.

Circuits of different voltages shall not be run in the same wiring trough. Separable wiring troughs or ones with barriers shall be used for this purpose.

Connections for termination boards shall be readily removable for test purposes.

Secondary devices shall be adequately protected from possible faults on the power circuits.

S9.09 TESTS

Complete tests shall be made at the factory by the Contractor on the various components of the equipment, in accordance with the IEC (or) EN (or) ANSI standards, to determine the performance and operating characteristics, and to determine whether or not the guarantees have been met. The following tests shall be included for each of the components as outlined below.

Qualification and factory tests on voltage transformers shall be in accordance with IEC Standards.

The factory tests shall be made on each instrument transformers including type test and routine test reports shall be submitted to DEDE for approval before delivery.

SECTION 10 - DC STATION SERVICES

S10.01 SCOPE OF WORK

The work to be done under this section consists of the design, manufacture, testing, delivery to site, installation placing in successful service and guarantee of: -

- 1 (one) 125-V battery with racks and fuses, 400AH minimum
- 1 (one) Battery Charger
- 1 (one) DC distribution panel board with instruments and circuit breakers

S10.02 PURPOSE AND FUNCTION

The DC station service system, comprising of Gel type battery, battery charging equipment and dc distribution panel board, shall be used for instruments and component power supply at PLC Controlled Automation System, Protection Relay, Metering and Alarm System, Instruments in Governor System, Lubricating Oil System, AC Switchboard, Motor Control Centers, and LV Switchboards, 22kV Vacuum Circuit Breaker, Annunciator System, emergency lighting and other essential DC loads which are to be used during shutdown and start-up of the generating unit.

S10.03 BATTERY

The batteries shall be 125-V, Gel type in shock-absorbing, translucent polypropylene plastic containers, in order to check the electrolyte level and manufacturer shall be certified according to ISO 9001 series quality standard complete with intercell connectors and standard accessories.

Battery shall consist of battery cells for minimum capacity 400AH, 10hrs rated with the following sequence of operation during trip, shutdown, and start-up of the generating unit as minimum: -

- Both generator breakers and 22kV breakers (total 3) trip simultaneously.
- Generator and line breakers reclosing sequentially.
- Both reclosed breakers trip simultaneously.
- No generation (or) other AC Supply is not available for 5 hours.
- Emergency Lamp for 5 hours.
- Indicating lamps, annunciation inside Control Room
- Continuous DC Supply for PLCs, protection relay, meters, HMI PC, Touch Screens, etc.

This duty cycle, together with an allowance of 10 percent for design margin, shall be used as a minimum to determine the battery capacity.

Bidder shall submit the Battery and Battery Charger Sizing according to IEEE 485 “Recommended Practices for Sizing Gel Batteries for Stationary Applications” and the Design Load Profile and Calculated Battery and Charger Sizing shall be submitted with the Bid verifying the proposed capacity is enough for equipment supplied under this contract.

The battery (Gel) shall have a capacity to supply the duty cycle given above, without

assistance from the charging source and without the battery dropping below 1.8Volts/cell. The battery (Gel) shall be constructed using the best industry practice. It shall have the polarity permanently and legibly marked on each terminal or on the cover adjacent to the terminal.

The battery shall be supplied complete with covered copper intercell, and connector ratings shall suit the maximum discharge current of the battery.

Cells shall have sufficient sediment space so that cleaning during the normal life of the battery may be avoided.

S10.04 BATTERY RACKS

Freestanding steel battery racks with lead-liner trays shall be provided for supporting the complete battery. The racks shall have a maximum of 2-3 tiers. They shall be sized and arranged to allow sufficient clearance for battery maintenance inside the battery room.

The battery racks shall be constructed from angle steel. The trays shall be fabricated from sheet steel and lined with sheet lead.

All surfaces shall be free from sharp edges and burrs, and the trays free from dents and bulges.

The lining of each tray shall be so fabricated that it overlaps the edges of the tray, and the only joints shall be at the corners. These joints shall be watertight.

S10.05 INSTRUMENTS ON DC DISTRIBUTION BOARD

The DC station service installation shall include a panel for the followings:

- DC ammeters complete with shunt and fuses (to measure total DC load and battery current)
- Non-automatic circuit breaker to disconnect battery from load
- Voltmeter and fuses to measure battery voltage
- Undervoltage relay to detect loss of dc with an ac alarm contact
- Ground detective relay with an alarm contact.

In the case of DC Distribution Panel is integrated in Battery Charger, all instruments shall be installed at Charger Panel.

S10.06 BATTERY CHARGER

The battery charger shall be fully automatic, rectifier-controlled design for automatic float and boost charging of batteries, to be enclosed inside a metal cabinet suitable for floor mounting. The charger is to supply DC at constant voltage for the average dc powerhouse load and for maintaining the battery, connected in parallel with the load, in a fully charged floating state. The ac supply source will be three-phase, 400V nominal rating, 50Hz.

Voltage regulation shall be ± 1 percent, with ac supply voltage variation of 10 percent and frequency variation of 5 percent from 0 to full load of the charger.

The nominal output of the charger shall be 125V dc, with the battery voltage range of 105V to 140V dc.

The equipment shall be of the static type, with no moving parts. It should be equipped with an automatic float-equalizer, 28d timer and with protection against sudden line voltage variations. Protection shall also be provided against damage due to overload.

The charger shall be connected with PLC Controller by using LAN (or) RS 232 (or) RS 485 cable to send the real time status of information about the battery, charger, and load information.

The charger shall have manual switching to the high-rate charge mode. Switching from high rate to float charge mode shall be automatic.

- The charger shall be equipped with the following protective devices.
- Circuit breaker with thermal magnetic trip unit for dc output. Its current rating shall be 1.5 to 2.0 times the charger rated current.
- A reverse current limiting device to protect the battery in the event of ac failure.
- Annunciator Lamps shall show indication under the following conditions: -
  a) Opening of the DC output breaker
  b) Failure of the AC supply
  c) Loss of charger control voltage
  d) Battery charger failure
  e) DC output under voltage

- Each of the annunciator circuits shall be wired to terminal blocks for connection to a remotely located annunciator. Alarms at the charger are not required.

The charger shall automatically return to service on restoration of ac supply after an interruption. Indicating lamps equipment status indications shall be provided.

The battery charger and auxiliary equipment shall be contained in a single, general purpose, ventilated enclosure, suitable for floor mounting indoors. The enclosure shall be fabricated from sheet steel panels. It shall be rigid, self-supporting, and free from magnetic vibration, twist, and weave. All panels used in the construction of the enclosure, including partitions and doors, shall be adequately supported, and stiffened where necessary to prevent flexing.

Components shall be arranged within the enclosure, with access via a hinged front door, for convenient inspection and maintenance and for making external connections.

Meters, indicating lamps and other externally accessible devices shall be located for convenient viewing or operation.

A copper clamp type connector having a conductor range of 25mm^2 shall be bolted to the enclosure for connection to the station ground system.

The enclosure shall have a nameplate giving charger input and output ratings and other pertinent information.

Identification tapes, Dymo embossing type, 13 mm wide or equivalent, shall be used for identifying fuses.

S10.07 DISTRIBUTION PANEL BOARD

The distribution panel board shall be suitable for floor mounting. The panel board shall have sufficient capacity for containing a main circuit breaker and branch circuit breakers. The panel board shall have a voltage rating of 250V dc and a short circuit capacity of 10,000ADC. Its current-carrying capacity shall be sized for the maximum discharge capacity of the battery and shall be a minimum of 400AH.The main breaker shall be a molded case type, 2-pole having voltage rating of 250V dc and an interrupting capacity of 10,000A DC. This breaker shall have a thermal magnetic trip unit.

The panel board shall have minimum 15 branch circuit breakers, molded case type, 2-pole, each with a thermal magnetic trip unit. Each breaker shall have a voltage rating of 250V DC, an interrupting capacity of 10,000A DC and a frame size of 100A DC.

The breaker trip ratings are provisional. The Contractor shall determine final ratings according to design requirements.

The main and branch breaker auxiliary switches shall be wired to separate terminal blocks. The normally closed auxiliary contacts of the branch breakers shall be connected in parallel and wired to 1 pair of terminal blocks. The contacts of each spare breaker shall be wired to 1 set of terminals.

S10.08 CABLE INTERCONNECTION

The Contractor shall supply properly sized cables between the battery, the instrument panel, and the battery charger. The Contractor shall also supply and coordinate cable size between the battery circuit breaker and the distribution panel.

S10.09 TESTS

Complete tests on the equipment shall be done at the factory by the Contractor to determine the performance and operating characteristics and to confirm that the equipment functions properly. Details of the tests to be performed on the various components of the equipment shall be submitted, and the following tests shall be done as follows: -

Battery Charger

- Mechanical operation of the components to ensure that all parts operate properly.
- Standard insulation withstands tests on all circuit breakers, relays, switches, and other devices and on all wiring at 1,500V to ground, 50Hz for 1 minute.
- Continuity and polarity test on all circuits.
- Functional and operational checks of all equipment and all control, metering, and protection circuits.
- Load simulation under various input voltages.

Distribution Panel board

- Mechanical operation of all circuit breakers to ensure that they operate properly.
- Standard insulation withstands tests on all circuit breakers and on all wiring at 1,500V to ground, 50Hz for 1 minute.

SECTION 11 - CONTROL, PROTECTION AND ALARM SYSTEM

S11.01 GENERAL

(1) Responsibilities

a) The Contractor shall design, supply, procure, delivery to site, installation, testing and commissioning the control, protection and alarm system for the turbine, generator, governor, lubrication system, generator control and protection panels, AC switchboards, DC service, 22kV Switchyard Equipment, Drainage System, other station auxiliaries including all interfaces and associated equipment.

b) For Protection, Metering, and Alarm System, the Bidder shall provide overall electrical single line diagram complete with ANSI protection relay numbers, ratings of all transformers, digital meters, excitation system, AC/DC Station Service System, standby diesel generator according to ANSI, IEC and IEEE standard codes and the description details for the Bidder's proposed system to be submitted together with Bid.

For this System, the Bidder shall submit together with the Bid for SCADA Control and Monitoring System method and Control Configuration Diagrams including Unit Normal Start, Stop and Emergency Stop procedures as well as control logic diagram (or) flow chart diagram for Pelton Turbine and Generator in Operation.

Failure to submit this information will subject to rejection of the Bid.

c) Equipment and Components, which are to be used in SCADA Automation Control System, shall be submitted in the Bid together with manufacturer's product catalog such as PLC CPU modules, Controller Chassis, I/O modules, Power Supply Modules, Ethernet Modules, HMI Touch Screen, Workstation PC, Notebook together with Licensed Software.

d) The protection system of the station of based on the principle of local back up. In other terms, any fault occurring anywhere at generator feeders, 22kV outgoing line, power transformers, governor, AC/DC system, standby diesel generator, generator terminal cubicles, load break switch, NGR cubicles, generator control and protection cubicles, AVR, 22kV switchyard equipment, etc. shall be monitored, and controlled. In the event of failure of battery, instruments or relays, the system should detect and enable to clear all failures of equipment.

(2) Requirements for Systems

a) Each system shall be designed to have high reliability and availability and however it shall be simple to operate and monitor by DEDE operator. The failure of any equipment or the loss of power supply to equipment shall not jeopardize the plant and shall initiate an alarm in SCADA (or) Annunciator Windows.

b) The normal control shall be operated at operator control station from the control room and for the purpose of system maintenance, commissioning (or) testing, it shall be done by via both engineering PLC (or) local control graphical HMI Touch Screen at Governor PLC control panel.

c) The control system shall comprise the programmable logic controllers (PLC) for SCADA and governing control system, the excitation system with digital automatic voltage regulator (AVR), the digital protective relays, the digital meters and synchronizing system. This PLC shall be connected to the human-machine interface (HMI) via of data communication cable. The metering and instrumentation of equipment and the related system shall be provided information for operator including annunciation system.

d) The operation for Generating Sets shall be by both automatic mode, and manual mode for load control, power factor control and frequency control mode. It can be selectable at SCADA HMI PC. In the typical automatic mode, the Unit shall operate until the rated speed and excite automatically until reaching at the rated generator voltage and it can be indicated READY lamp to start synchronizing with grid. The control functions shall be included supervising, controlling and monitoring to the unit conditions, recording the sequence of events, periodically fault and alarm events, providing integration of historical trending display, bar chart display and guidance messages.

The Bidder shall submit PLC Manufacturer's Letter of Confirmation for PLC Control System stating that the manufacturer will design, supply and supervise during installation and commissioning start-up together with guarantee performance for their Supplied Products with licensed software complying with the Specifications specified under this section.

e) The scope of supply for the control system of this power station shall be supplied to control to control and monitoring of generating units and 22kV switchyard equipment with station auxiliaries and shall be comprised of the following equipment.

i. Generator Metering, Control and Protection Panels (2 sets) with generator multifunction relay, contactors, lock-out relays, indicating lamps, annunciators unit, emergency push button switch, digital power multi meters
ii. 22kV Line Metering, Control and Protection Panel (1 Set) with feeder protection relays, auxiliary relays, contactors, VCB Control Switch, indicating lamps, digital power multi meters
iii. SCADA control panel with HMI touch screen, synchronizing relay, indicating lamps and control switches with related accessories

(3) Requirements for Devices

(a) Protective Relaying System

The protective relaying system shall be an integrated system of IEDs consisting of multi-functional digital relays, high-speed lockout relays, shutdown relays, blocking and test switches and auxiliary relays mounted in one or more cubicles.

Protective Relays

The Protective Relays for the Generator and 22kV line feeder shall be provided with reliable and longer life protection relay with minimum 2 years warranty directly from the manufacturer to ensure that the quality and reliability of the generating unit are assured.

The protective relays shall be microprocessor-based using digital signal processing technology and software to provide the protection functions, alarms and trip command, fault recording and communication to turbine control board via MODBUS protocol or CAN bus with TCP/IP (for Generator Protection). Each digital relay shall be provided with a port for communication with a laptop computer. The contractor shall design the protection system for generating unit, 22kV feeder protection as per PEA Grid Code, station service transformer, generator feeders, LV Switchboards and others related equipment.

Major protective relays for the generating set such as Generator and Line Protective relay shall be well proven by the reputable international certification such as: -

- 10 CFR 50 Appendix B Nuclear Quality Program
- ABS Marine Type Approval
- CE (Europe)
- CSA (Canada)
- ENA (UK)
- IEC, including IEC 61850-10 Conformance
- IEEE, including IEEE 1613 Reliability
- ISO 9001:2008
- ISO/IEC 17025
- KEMA
- RUS (for rural electric cooperatives)
- UL
- VPP Star Safety

Each relay system shall be provided with test facilities for secondary injection testing and current circuits, potential circuits, tripping circuits' and all other output contacts. All test switches shall be arranges so that the current transformer secondary circuit cannot be opened circuit in any position while the test plugs or cover plugs are being inserted or removed. Test plugs shall be furnished with each type of test switches. All digital relays shall be adequately protected against damage from incoming surges and shall meet ANSI (or) IEC test standards.

Each relay shall utilize a DC-to-DC converter type regulated power supply to provide high voltage and transient surge isolation between the station battery and the electronic components of the relay system. And each DC-to-DC converter shall be provided two electrically separate contacts for remote annunciation of output voltage failure. Each power supply shall be designed for continuous operation at any voltage from +/- of rated DC voltage and at range of ambient temperature of 10°C to 85°C and 0% to 95% humidity.

All modules of digital type protective relays consist of highly reliable logic circuits and circuit components. All modules shall be mounted on plug-in circuit cards. Wiring boards shall be epoxy-fiberglass construction. Printed circuit wiring shall be employed with soldered or weld connection to circuit components. Wiring board shall be provided with heavy-duty circuit connectors with gold-plated contacts.

The instruction manuals shall be prepared with the object of providing sufficient detailed technical information of each type of protective relay to enable DEDE to efficiently carry out commissioning and routine testing, to

provide guidance in the tracing of faults and to permit order of replacement parts. In this regard, each instruction manual shall give full details of circuit operation, circuitry and components. All technical data, operating time curves, sample calculations and other characteristics shall be based upon 50 Hz. Operation.

The settings for the relay functions shall be programmed by via laptop computer using Original Software from manufacturer. And the method of uploading and correction shall be trained to DEDE operator before commercial operation of the plant.

Lock-out and Non-lockout Relays

Lock-out relays shall be high speed half-cycle type, solenoid operated, mechanically latched, with manual reset handle. Non-lockout relays shall be similar but without the latch and reset features. Output contacts shall be rated for 2A at 125Vdc so sufficient contacts shall be supplied for all stated functions.

Auxiliary Relays

Auxiliary relays shall be rail-mounted socket type with sealed case and coils and contacts rated for 125VDC.

Protection Circuits

Relays and protection circuits for shall be rated for 125VDC and shall be supplied from separate dedicated fused DC circuits. Loss of supply relays shall monitor the supply and shall alarm the control system upon loss of DC. All VTs and CTs circuits shall be supplied with test switches for isolation and tests. In case of the maintenance, cut-off switch shall be provided for circuit protection to ensure that the breaker failure relay (50BF) will not be operated.

Metering

Active and reactive energy metering shall be provided for revenue, statistical and efficiency measurement. High accuracy metering of kWhr and kVARhr are required at control room. Metering shall comply with IEC 60687. Metering test block shall be provided in the CT and VT circuit to provide isolation and testing connection facilities for the meter.

All metering shall be a digital type meter with ethernet communication and can be recording information and shall be shown on operator control station and shall be print out the information through SCADA when required Meters shall have backlit LCD screen for display of quantities and phase vectors, and controls for selection of measured and calculated quantities. Meters used for monitoring distribution line electrical quantities shall be of revenue metering accuracy class.

Unit Synchronization

A digital synchronizer shall be supplied to permit automatic synchronizing of the unit(s). The system shall design to synchronize one by one unit and shall include the interfaces with the voltage matching.

The synchronization system shall include the followings:

- Synchronization ON/OFF Switch
- Gen. Selection Switch (Unit 1 or 2)
- Voltage Raise/ Low Selector Switch (Sprin Return)
- Sync. allowed indicating lights
- Guide Vane Open/ Close Switch (Spring Return)

(b) All electrical devices shall comply with the Standard International Technical Specifications such as IEC or NEMA or JIS standards.

(c) The Contractor shall use devices whose ratings exceed the rating required by the function and duty of the device in order to increase the reliability of the plant.

(d) Control, Monitoring & Protection Panel Construction

The system shall include Two or more cabinets each shall include:

- Generator Metering, Control and Protection Panels (2 sets) with generator multifunction relay, contactors, lock-out relays, indicating lamps, annunciators unit (min. 16 windows), emergency push button switch, digital power multi meters (Class 0.5 minimum)
- 22kV Line Metering, Control and Protection Panel (1 Set) with feeder protection relays, auxiliary relays, contactors, VCB Control Switch, indicating lamps, digital power multi meters (Class 1.0 minimum), annunciators unit (min. 16 windows)
- SCADA PLC Control Panel (1 Set) with HMI Touch Screen, PLC CPU modules, Power Supply and Communication Modules, Auxiliary Relays, I/O modules, Chassis, Speed Sensing Modules, Push Buttons, Selector Switches, Indicating Lamps, etc.

(e) Devices shall have adequate range of setting to allow for possible changes during commissioning. The setting shall be readily adjustable and lockable.

(4) Solid State Systems

(a) All solid-state equipment shall be built up from proven modules and components. Unproven equipment will not be accepted and bidders shall include with their bids details of the history of any solid-state equipment

offered. Modules performing identical functions shall be designed to be interchangeable. Each module shall have sufficient test points to fault finding and calibration.

(b) The electronic components used in the modules shall be of the highest quality, having a design in-service life of at least 20 years; this requirement applies particularly to capacitors.

(c) Indication by means of light emitting diodes or other methods shall be provided on the digital inputs and outputs of solid-state equipment to indicate the logic state. Outputs shall be protected against short-circuits.

(d) Programmable Solid State System
Control systems employing microprocessors shall have their programs stored in non-volatile and reprogrammable memory. The Contractor shall supply all information and equipment necessary to enable the Department to re-program the control systems.

Following successful commissioning the Contractor shall supply to the Department a complete set of flowchart and program listing plus, if applicable a duplicate set of pre-programmed EPROM's.

The controller shall be equipped with all facilities necessary for the maintenance, operation and fault clearance by technicians with limited knowledge of electronics.

S11.02 CONTROL SYSTEM REQUIREMENTS

(1) SCADA Control Panel

The Contractor shall provide the SCADA Control Panel with the following:-

- HMI Operator Control Station 1 Set (PC set including licensed operating software to control operate the TG unit)
- Laptop/ Notebook computer for engineering work station 1 set (including software tools for engineering work station notebook to adjust or modified system configuration, changing parameters and to perform commissioning and testing for the unit)
- Programmable logical controller (PLC) with software in unit control PLC cubicle for each unit and shall be comprised of Central processing units (CPU), I/O modules I/O modules to interface with same brand with CPU, Power supply modules, Communication Modules (same brand with PLC), Governor I/O modules (same brand), HMI touch screen for each unit (same brand) and Licensed Software for SCADA

- Digital Excitation System for each unit
- Synchronization system including synchronizing relay, synchroscope completed with Selector Switches, Sync. ON/OFF Switch, Sync. Lamp, Raise Low Switch, etc.
- Local Area Network (LAN) System including switching hubs (Including interfacing port) and Modbus communication ports (or) communication modules
- All design documents and drawings including equipment sizing, calculations, relay coordination study, relay settings, system block diagrams, layout; schematics; and wiring diagrams.
- Logic flow charts or descriptions for control sequences.
- Control system input and output and alarm list
- Format of predefined reports
- Branch circuits for each function shall be individually protected. Provision shall be made to enable isolation of each circuit separately.
- Control, annunciation, alarm and protection circuits shall operate at 125VDC and the consumable capacity for Battery and charger sizing calculation shall be submitted with the Bid (Section 10–DC Station Service).
- All indicating and pilot lamps shall be of the low power, cool operating with DC, switchboard type, with color caps and mounted resistors integrally. All indicating lights shall be suitable for operating at 24V (or) 125V DC.

(a) HMI Operator Control Station

Operator control station shall be minimum 64-bit multiprocessor CPU minimum 2.5GHz and providing ethernet communication ports to connect SCADA system via Ethernet switching hub so that it shall be equipped with minimum 16B of RAM, minimum 256GB SSD for operating system, 2x1TB HDD (hard disk drive), 3D graphic VGA card at least 2GB and sound cards including speaker, and internal latest version of Modem, minimum 24 inches LCD color monitor with adjustable stand, Back-Up Power Supply, A3 Color Laser Printer with Ethernet Port, DP interface and Ethernet interface cards and other periphery for complete installation to operate generating units and satisfactorily operation according to the specifications in this section. Communication to PLC shall be Peer-to-Peer architectures.

(b) Laptop/ Notebook computer for engineering work station

The laptop computer shall be supplied as the engineering work station at least 64-bit multiprocessor, min. 8GB RAM, min. 256GB SDD (or) 1TB HDD, and minimum 14” color LCD display, communication ports to connect and access existing Operator PC, other control modules and equipment with IEEE outlets to suit with the communication to all field equipment supplied for this contract.

(c) Programmable Logic Controller (PLC)

A programmable logical controller shall be a well-proven 32-bit processor design with wide range of I/O modules accepting discrete, analog and RTD inputs and shall have flash card for data and parameter storage. The PLC shall provide on-board self-diagnostics, with on-board LED indicators defining processor controller status. As a minimum, the process controller shall support the following attributes:

- Built-in minimum RAM 32MByte and Flash 32Mbyte in minimum
- Processor speed minimum 1GHz
- Built-in One RS-485 port and one RS-232 port
- Analog loop shall be processed at operator tunable rate down to 10 times per second
- Binary loop shall be processed at operator tunable rate down to 10 times per second
- A full range of preconfigured algorithms that can be used to implement control strategies
- Capable of being configured in ladder logic or capable of executing higher level programming languages such as BASIC, C or capable of executing operator-defined functions not included in the standard function
- Capable of executing any combination of the above functions, i.e., Standard algorithms, ladder, higher level programming languages, etc.
- Capable of peer-to-peer communication with any of additional Operator Control Stations and every other module in the system
- Support Ethernet TCP/IP communication to Remote I/O unit
- Storing control configurations (software) on-board in non-volatile memory and capable of retaining configuration information for at least 1 year. The system shall alarm when the battery reach a low-voltage condition before failure.

Maximum Processing Time: The processing time of the particular controllers shall be dedicated to the requirement of the controlled technological process and shall be in accordance with the following three categories, with maximum processing time not exceeding the specified limits:

- 50ms for quick-acting process, e.g. Electrical processing system
- 150ms for normal sequential controls, e.g. Pump control or valve actuator control
- 250ms for modulating control

  The above processing times included input operation, logic or function processing' and output operation.

(d) Governor I/O Modules.

The I/O modules shall be able to support process signals from various types of sensors and contact devices without requiring external or auxiliary signal conditioning devices. The modules shall be installed inside steel cabinet nearby turbine floor (or) inside SCADA control panel.

The Digital modules shall include the following features:
- Binary input: capable of receiving 24V dc
- Binary output: Isolated contact rated at least 0.75A, 24Vdc and user selectable as normally open or normally closed
- Support minimum 8 points/ module
- Signal isolation and Operate either signals are Positive or Negative logic
- Output provided with Electronic Short Circuit Protection (ESCP)
- Detection of the quality and presence of input signals (e.g. open thermocouple detection).
- Detection of the quality and presence of input signals (e.g. open thermocouple detection). The quality of each input point shall be determined and classified as either goods, questionable, substituted or bad. When bad, the value shall have bad quality indication
- Surge, over current and reverse polarity protection
- Individual input shall be fused or feature current limiting. If fuses are provided, a common alarm contact for the fuse failure shall be provided.

Analog input and output signals shall include the following:
- Signal conditioning including linearization, scaling to engineering units, a minimum of 16 bits analog to digital (A/D), and a minimum of 15 bits digital to analog (D/A) conversion
- Analog input channels can be configured for the ranges: 4 to 20mA, +/ 10V, +/ 5V, 0-5V (or) PT 100 with individual A/D conversion
- Analog output channels can be configured for these ranges Analog output: 4 to 20 mA, +/-10V. Capable of driving 1350 ohms of current and 2K ohms of voltage
- RTD input: Capable of receiving 100 ohms platinum (if necessary)

(e) Turbine Control Unit (HMI Touch Screen)

The turbine control unit (HMI touch screen) shall be by PLC based having functions to control turbine, generator, governor, digital AVR, inlet valve, bypass valve, hydraulic pressure unit, lubrication oil unit, cooling water unit and the related auxiliary equipment and it shall be included functions of synchronizing, electrical protection, control sequence, needle valve and deflector control, load set point (MW and MVAR), frequency set points,

emergency shutdown functions, etc. and it shall be located in front of SCADA Control Panel inside the Control Room.

In order to monitor and control the units, the Contractor shall provide a real time data to display on both HMI touch screen and operator station PC as a minimum of the items as follows:-

- Turbine Head, Speed, HPU pressure, temperatures, etc.
- Penstock Head, inlet valve and bypass valve statuses
- Generator Voltages, Current, PF, Frequency, kW, kVAR, kWh
- Generator Temperatures such as windings and bearings
- Hydraulic Governor pressures, oil temperatures
- Lubrication Unit temperature, pressure
- Cooling water temperature, pressure and flow status
- 22kV Line Voltage, Voltage, Current and Frequency, Circuit Breaker and DS Status
- Power Transformer winding and oil temperature, status alarms
- AC and DC power status
- Standby diesel generator status
- All switching device positions and statuses

Database (History) type shall be Industrial Database (non RDB) 64 bits architecture and shall support OPC A&E Collector and OPC DA collector.

All displays shall be updated at least once every 5 seconds. Response time to an operator command to completely generate or cancel displays shall not be exceeding 1 second. It shall be possible to access any displays by entering a tag name or tag index number. Manual substitutions for input data shall be possible on a point-by-point basis through the operator station.

Group/Faceplate Displays (on LCD monitor) shall be detailed control display for a related group of binary signals, process variables, set point and output indicated by tag name and point text description. The operator shall be able to select point for control action, change the mode of control or set point.

(f) Synchronization System

The Contractor shall supply both automatic and manual synchronizing facilities to allow the generators to be connected to the power system. The manual equipment shall include digital synchroscopes, synchronizing check relay, synchronizing indication lamps, a synchroscope selector switch, running and incoming voltmeters, running and incoming frequency meter, synchronizing sockets for each circuit.

The instruments shall be mounted on the synchronizing panel (or) SCADA PLC Panel in such a position that one operator alone may synchronize effectively.

A synchronizing check relay shall be provided to supervise the closing of the generator circuit breaker. This relay shall be put in circuit via the synchronizing selection plug.

A control signal and indication shall be provided at the end of the starting synchronizing. This signal shall permit the automatic synchronizer to synchronize the unit to the system. The automatic synchronizer shall be put into circuit via the synchronizing selection plug.

(g) Local Area Network (LAN) and Interfaces

The Local Area Network (LAN) and Interfaces shall be a based T Ethernet TCP/IP system and switching hub linking the Operator control station PC and Engineering Laptop.

The communication between Operator control station PC and SCADA PLC shall be through local area network (LAN) conforming to IEEE 802.3/802.2,802.1 Q and the protocol shall be complied IEC 60870-5-101/104 standard (or) updated version. The communication between PLC for all control units and Intelligent Electronic Devices (IEDs) such as Digital governor, AVR excitation system, digital protective relaying system, digital metering equipment shall be MODBUS (TCP/IP) (or) RS485. All status, alarm, condition of the unit and control signals shall be relayed to operator control station through the LAN (or) RS 485 (or) instrument cables. RS 232 communications are not allowed to use so that the Bidder shall submit the communication system and protocol to be used shall be submitted with the Bid.

Failure to submit this information will subject to rejection of the Bid.

(h) Points of Control

Each valve, switch or other device shall be operable manually for maintenance purposes at the device. If the device is used for isolation purposes, it shall be fitted with provision for padlocking in the isolated position; indication of the device position shall be provided on the device. Electrical or pneumatic operation shall be provided where extended control is also required.

On the main control switchboard in the control room, control facilities shall be provided for starting, stopping and operational functions such as stopping, excitation, and load control.
Synchronizing facilities for the units shall be available at the control room on the separate synchronizing panel (or) in SCADA PLC Panel. Mimic monitoring

diagrams for the control and indication of high voltage equipment shall be also be fixed on the front panel.

In order to control and monitor the plant in future, the contractor shall provide the spare module of Automation System for the purpose of control from a remote location. The confirmation of this requirement shall be indicated in System Configuration Diagram submitted together with the Bid.

(i) Control Modes and Sequences

The system shall operate in two main operating modes, which are namely as local and remote (or) PLC operating modes. Operator can operate the generating set from operator control station PC inside control room as Remote Control Mode and operating the Unit from graphical interface HMI Touch Screen at Unit Control PLC namely Local Control mode. The selection shall be done at Unit control PLC Panel. The Contractor shall provide the selector switch on Unit Control PLC Panel as a local/remote selector switch.

The operator shall be able to select one of the following control modes from Operator Control Station PC: -

Manual mode:	The unit and associated equipment shall be manually controlled at control panel of each unit.
Auto mode:	All unit control sequences shall be carried out automatically once initiated by an operator.
Step mode:	The operator shall be able to "step" through each step of the Auto sequences by initiating each step.

Unit Control Sequences shall be capable of executing any control sequences selected and initiated by an operator in all control modes except the manual mode. Once a sequence is initiated, the sequence shall check that all permissive associated with the selected sequence have been satisfied prior to starting the control sequence.

Stopping shall be possible at any time via emergency push buttons located at each panel. Unit emergency shutdown shall positively override any other control sequence to bring the unit safely, independently and quickly to a de-energized and stationary state. Protection system operations and operation of the unit emergency shutdown controls shall initiate a unit emergency shutdown.

Starting of the unit shall be possible both fully automatically and manually at control board or at the devices.

Similarly, stopping shall be possible fully automatically and under operator guide control. It shall be possible to restart following commencement of a normal stop sequence without waiting for the stop sequence to be complete.

The programming sequence shall be a step-by-step as shown on below figure as preliminary for basic information however the Bidder shall indicate clearly for the Start, Stop Sequence, with the process diagram (or) Flow Chart together with the Bid verifying that the Bidder has enough knowledge and capability for performing this project.

The preliminary sequence for programming PLC will be as below: -



S11.03 PROTECTION DESIGN REQIREMENTS

(1) General

(a) The protection requirements are shown on the single line diagram and equipment details specified herein.

(b) Each trip relay or tripping circuit shall be separately protected by a fuse or miniature circuit breaker. All trip circuits shall be separately monitored. Protection circuits shall operate at 125V DC.

(c) It is operational important that some advance warning of impending trip action is given. This is generally to be achieved by the initiation of a first- stage alarm set to operate before the trip condition is reached: The aim of this is to allow the

operator time to take action which will correct the condition or to unload and stop the machine thereby avoiding a shutdown and minimizing damage. In the case of high-speed trip devices, such as overall differential protection relays, no first stage alarm is required.

(d) Protection devices shall operate either the emergency shutdown or the unit automatic stops latched trip relays. The emergency shutdown relays shall trip the machine off line instantly, shut it down and lock it out of service. The quick stop relay shall delay tripping of the circuit breaker until the unit is at no-load and thereby avoid disturbances to the power system and over speed conditions caused during the rejection of load. The turbine deflector closing and turbine inlet valve shall be tripped by closing immediately, but the generator circuit breaker shall not be tripped until the unit load is less than 10 percent of full load. A reliable means of signaling the no-load condition shall be used, preferably by means of a direct output from the governor controls. Both trip relays shall also prevent any attempt to restart the unit. The failure of the quick stop sequence shall cause a unit shutdown. Failure of the unit to trip on electrical fault or shutdown shall operate the appropriate circuit-breaker failure protection. It will be necessary for the operator to manually reset trip relays, usually following an investigation in the case of operation.

(e) The protection scheme shall detect all faults and operate to disconnect plant in a minimum of time to lessen permanent damage. All protection facilities necessary to achieve such a scheme are to be provided by the Contractor.

(f) The Contractor shall ensure-that each protection function is independent of others and can be individually isolated to allow each along to be taken out of service for testing or operational purposes. The Contractor shall provide facilities and equipment for in situ testing of protection systems. Facilities shall be provided in AC circuits to allow disconnection of protection relays and short circuit of current transformers so that testing by secondary injection can be performed. Test terminals shall also be provided in voltage transformer secondary circuits.

(g) All shutdown and quick stop devices require a fault operation indicator on the protection panel. Electrical protective devices and mechanical protective functions in general will require duplicate, electrically separate initiating contacts; one contact is required for tripping and the other for operating an alarm relay with sufficient contacts to perform the alarm functions plus 1 space normally open contact.

(2) Electrical Protection

The protective systems shall be of solid-state types for Unit and Line Protection, and either Conventional or solid-state type for other protections. The electrical protection scheme is outlined on Drawing except of the excitation system protection, for which only some basic functions have been specified.

Comprehensive electrical protection is required for the excitation system and the Bidder shall provide full details of the proposed scheme with the Bid.

(3) Mechanical Protection and Alarms

The Contractor shall provide all of the devices for protection and alarm shown on drawing together with all necessary piping, valves, fittings and the electrical connections. For initiating devices shown on the drawings as having Stage 1 and Stage 2 settings, the Stage 1 setting shall be set to give an alarm for advance warning of a potentially damaging condition. The Stage 2 setting shall be set to initiate a quick stop of the unit Both Stage 1 and Stage 2 contacts shall be suitable for operation a 125V DC.

(4) Equipment Details

The Contractor shall submit to the DEDE Engineer for approval, the proposed relay protective system that shall be based on the single line diagram submitted in his BID proposal.

The equipment listed here covers only the devices that are essential for proper operation. It is to be understood that all other associated auxiliary equipment and accessories, although not listed in this Specification, but necessary of the complete and sound functions of the main control board as described in this Specifications, and as generally accepted as the applicable standards, VSPP, shall be furnished by the Contractor.

Generator Protection Relays

a) Generator Differential Protection (87G): Generator differential relays shall be either a constant percentage or a high impedance differential, 3-element type, and shall provide protection against phase faults for 3 phases and ground faults. The percent differential type or relays shall have a slope characteristic of 10 percent.

   Volts/ Hertz (24): The protection element shall have both selectable definite/inverse time characteristic and could be used with a custom curve.

b) Generator Under voltage Protection (27G): Generator under voltage 50Hz relay for connection to the 110V secondary of the voltage transformer on the generator terminals on at least 2 phases.

c) Generator Reverse Power (32R) or Directional Over Current (67): Protect Generator against being motored by the Grid, where protection functions include a definite time trip at a pre-defined active power level.

d) Neutral Over Current (50N): The protection element shall have adjustable pickup current with an adjustable time delay settings. Pickup shall be <1.5 cycles.

e) Generator Overvoltage Protection (59G): An instantaneous 50Hz overvoltage relay with compensation for frequency shall be connected to the 110V secondary of the voltage transformer on the generator terminals. This protection element shall have 2 parts; a low set element will1 an adjustable time delay setting that closes its contacts on sustained moderate overvoltage and a high-set instantaneous element. The 2 elements shall have adjustable pickup voltage setting range. The low-set element shall have a high ratio at reset to pickup. The low-set and high-set elements shall be used for tripping.

f) Negative Sequence Protection (46G) - (if applicable): The negative sequence current and one sensitive to the integrated product $(I_2)^2$ x t = 40. The relays sensitive to the negative sequence current shall be definite time type adjustable within a range of 20-40% of asymmetry and 5 to 15 seconds of operating time. The relays sensitive to the integrated product $(I_2)^2$ x t shall be inverse time type.

g) Over current Ground Relay (51NT)(51NG): The protection element shall be at least two phases, inverse time current characteristics, 5A CT 50 Hz, 0 to 12A current setting, ICS, 125V DC, flush mount, adjustable operating time approximately 0.2 to 3 sec.

h) Non-directional Over current Relay (51G): The protection element shall be at least 2 phase, inverse time current characteristics, 5A CT 50 Hz, 0 to 12A current setting, flush mount, ICS, 125 V DC.

   Loss of Potential (60): The protection element is for detection of open voltage transformer fuses or other conditions that cause of loss of relay secondary voltage input.

i) Rate of Change of Frequency (81R): Protection element detect the changes in frequency either increasing or decreasing frequency and above or below nominal frequency.

j) Auxiliary Tripping and Lockout Relays (86E, 86M) - Each relay shall be of the high speed, DC voltage operated, manual reset control switch type with cut-off contact provided to interrupt the operating coil. Number of contacts required shall be 5 electrically separate normally closed contacts and 5 electrical separate normally open contacts. All contacts shall be field interchangeable. Four relays are required.

k) Under, Normal and Over speed relay (12, 13, and 14) for Turbine over speed protection.

l) 22kV Line Protection Relays
   a. Transformer Differential Protection (87T): In case each generating unit is more than 1MW output, the Contractor shall provide the transformer differential relay according to the VSPP rules and regulation of PEA. The protection element shall be high speed, variable percentage, differential type, and shall provide protection against phase faults and ground faults. The relays, using the second harmonic restraint principle, shall provide positive protection against tripping on magnetizing inrush current. Relays with 2 restraint windings shall be provided. The relays shall have a variable or an adjustable percentage characteristic of approximately 15 to 60 percent.
   b. Non-Directional Overcurrent Relay (50/51F): The non-directional overcurrent protection element shall be at least two phase, moderately inverse-time characteristics, SA, C.T., 5 0 Hz, polarizing current of 110V, 0 - to 12A current setting, flush mount, adjustable operating time approximately 0.2 to 3 sec at ten times current setting, 1A that is, 125 V DC.
   c. Non-Directional Overcurrent Ground Relay (51NF): The non- directional overcurrent ground relays shall be at least one phase, very inverse-time characteristics, 5A, C.T., 5 0 Hz, polarizing current of 110V, 0.5 - to 2.5A current setting, flush mount, adjustable operating time approximately 0.05 to 1.7 sec at ten times current setting, 1A, ICS, 125V DC.
   d. Current auxiliary Tripping Relays (5 1 X, 5 1 NX) -If applicable: For use with (a) and (b) above. These relays shall be high speed, self-reset, 125V DC, with four independent normally open contacts. The relay shall be designed to draw current at approximately 2.5A for the purpose of dropping ICS target of relays (a) and (b) above. Min. One relay is required.
   e. Line Lockout Relay (86): One (1) per feeder or more as required shall be supplied. The tripping logic and the detailed tripping circuits shall be submitted to the DEDE for approval.

S11.04 GROUP OPERATION INDICATOR

The indicator shall be of the lamp type, which contain two lamps in one window and shall be designed to indicate the sequence of operation of the control board automatically.

S11.05 FAULT INDICATOR AND AUDIBLE ALARM SYSTEM

The fault indicator combined with annunciator relays for alarm shall be used to show the operation of protective relays and items to be indicated shall be referred to the attached Drawings of protective relaying functions. The fault indicator shall be of the lamp type, which contains two lamps in one window.

The audible alarm equipment shall consist of an alarm bell for indicating fault, and shall be mounted inside the control board. The system shall be suited for operation by 125 V DC systems.

Fault indicating sequence shall be as follows:

When a fault occurs, the lamp shall light and flicker, and simultaneously an audible alarm shall be announced.

Manipulating by resetting push button switch shall stop the audible alarm.

Flickering of the lamp shall be stopped by manipulating the resetting push button switch, but the lamp will not go off if the fault continuous. When the fault is cleared the lamp will go off.

Red window indicator shall indicate heavy fault and white window indicator shall indicate heavy fault and white window indicator shall indicate light fault.

S11.06 CONTROL AND PROTECTION CUBICLES

(1) General

The control and protection switchboards shall be designed for control, indication, metering, recording, instrumentation, annunciation and protection according to these Specifications.

(2) Arrangement

The control and protection panels shall be of metal enclosure, free standing with back door for easy access to service and maintenance. Arrangement of auxiliary and related equipment and accessories are not indicated on the Bid drawings but the Contractor shall provide necessary information to complete and proper functions as per this section so that the Bidder shall submit the complete layout of Cubicle arrangement, front panel layout and construction showing the list of Components with the Bid.

Failure to submit this information will subject to rejection of the Bid.

Any modifications to the arrangement indicated or arrangement of equipment not shown on the drawings shall be subject to the approval of the DEDE Engineer.

(3) Details of Construction

Each main control panel section shall consist of an assembly made from not less than 3 mm leveled steel sheets and formed steel members as required to form a rigid self-supporting structure. No butt surface joints shall be made on the outside surfaces of the control board. No holes or fasteners shall be visible as viewed from the front of the panel. The control panel shall be designed without any permanent bottom braces and the bottom shall be opened. Each control panel shall be furnished with channel bases. The front and rear panels of the control board shall have bent angle or flanged edges with an outside radius not exceeding 10mm.

Control Panel/ Cubicle: The Control and Protection Panel shall consist of basic panel assemblies placed back-to-back at sufficient distance to provide a tunnel-type walkway between the assemblies. Bolted-on floor channels, top sheets, wiring trays, left and right end trims with access doors shall be provided to form a complete duplex control board with uninterrupted walkway running the entering length if the structure. The access doors shall be equipped with lock, launched and fully concealed hinges, and with handles for opening from the exterior and interior. End trims with access doors shall be readily removable so as to permit future boards to be installed at both ends.

All outgoing wiring and any inter-section wiring shall be routed and terminated to screw type terminal blocks mounted on the interior side panels.

Wiring for control, instrumentation, and relay circuits shall be stranded copper switchboard type with 600V insulation. Minimum wire size shall be 2.5 mm and for control and annunciation, and 4 mm^2 for current transformer leads.

All wiring shall be installed in wiring channels and ducts as far as possible. There shall be no splices in the wiring and all connections shall be made at terminal studs or terminal blocks.

Twenty (20) percent spare terminal points shall be provided for future use. All outgoing cable and wire shall be routed through floor openings.
A 20-watt fluorescent light fixture shall be furnished in each board section to provide proper interior illumination. One 3-way switch shall be provide at each end of the board and one 230VAC, single phase, 3-wire 50 Hz convenience outlet shall be provided for each section. The lighting and outlet circuits shall be wired in conduits and terminated in a suitable junction box at both ends of the boards to facilitate the completion of wiring of the circuit in the field.

A grounding bus made of copper and equivalent to 95 mm^2 copper conductors shall be provided arid fastened securely to the back panel inside of each section. All bus sections shall include provisions to facilitate ground, connection in the field. The extreme end of the ground bus shall have pressure type lugs suitable for 95mm^2 copper cable. All grounds in the structure shall be properly routed and terminated to the grounding bus.

All ventilating openings shall be provided with corrosion-resistant screens to prevent entrance of insects and rodents.

To prevent warping of panels, all heavy devices shall be adequately supported by means of rear-mounted brackets or straps. The equipment mounted on the panels shall be arranged and spaced to provide easy access for inspection and servicing.

The panels shall be constructed to meet all the applicable sections of IEC (or) NEMA (or) ANSI Standards.

Panel insides and outside surfaces shall be cleaned by rinsing or other suitable method and a rust inhibitor shall be applied prior to priming. The finishing coat shall be the same as main control board.

Terminal boards shall be provided on both side panels with suitable cable supports for incoming control cables.

Wiring between terminals and all relays shall be of the type commonly used in switchboards, with wiring ties at proper intervals.

Terminal markers shall be of the permanent type marker strip and shall bear the wire numbers according to the connection diagrams.

Wiring markers shall be provided on each end of each wire with the same identification appearing on the terminal boards.

Auxiliary self-reset relays shall be multi-contact, high-speed type.

Timing relays shall have adjustable time delay with independent circuit opening and circuit-closing contacts as required. The relays shall not depend on oil despots or other devices which are affected by temperature.

All relays shall be the surface mounted front connected type with a dust cover. Relays shall be fastened to small channels provided on the surface of the rear panel in each section of the board.

Every point of terminal block and wire shall be assigned a designation, with identical designation on each corresponding terminal block and wire. This same designation shall also be indicated in the schematic and wiring diagrams. As a rule, a designation will not change until the wire is terminated or connected to other equipment. All wiring shall be designated at both ends by printing on wire designation sleeves and the wire designation shall be by permanent method unaffected by heat, solvents, or steam and not easily dislodged. Each designation on the terminal blocks shall be machine-lettered. Stamped, engraved or neatly marked with permanent ink on the removable marking strips provided for each terminal block. Approx. 20 percent of spare wire designation sleeves shall be furnished. Adhesive labels are not acceptable.

The name of ANSI standard device numbers of each device shall be marked on the front or side of the relay or adjacent to the corresponding device.

All indicating and pilot lamp assemblies shall be of the low power, cool operating, 24V, switchboard type, with color caps and integrally mounted resistors. The color caps shall be red, green, white, blue or yellow as required. All lamp bulbs shall be inter-changeable and shall be replaceable from the front of the panels.

Test switches shall be of the built-in type or separate type as specified. Separate test switches shall be of the switchboard, back-connected type, finished in dull black for front-of-panel mounting. All test switches shall be arranged to isolate completely the instruments from the instrument transformers and other external circuits and provide means for testing either from an external source of energy or from the instrument transformers by means of multipole test plugs which shall be provided for the propose. A sufficient number of test plugs to make a complete test on one meter, instrument, or relay shall be furnished for each type of test switch. All test switches shall be arranged so that the current transformer secondary circuits cannot be open-circuited in any position while the test plugs or cover plugs are being inserted or removed.

The control boards shall be provided with terminal blocks for termination of all wiring devices mounted in the control boards and all external circuits. Terminal blocks for control wiring shall be of 600V approved molded-block type with molded insulating barrier between terminals. Terminal blocks shall be sized to accept $25mm^2$ to $1.5mm^2$ conductors. Each terminal block shall have movable white marking strip for marking circuit designation. One spare blank marking strip for marking circuit designation and one spare blank marking strip shall be, furnished with each terminal block.

The arrangement of all terminal blocks shall be such that incoming and outgoing can be easily arranged for connection to terminals. Terminal block shall be located so that the accessibility to them will not be lessened by interference from structural

members or panel instruments. Ample space shall be provided to terminal blocks for termination of all external circuits. Except as otherwise specified, extra terminals, in addition to that mentioned in Article 10.1, in quantity of riot less than 25 percent of the active terminals, shall be furnished and mounted for circuit modifications and for future use.

Nameplates shall be furnished and mounted by the Contractor. Each assembly, each piece of equipment mounted on an assembly, and each power and control circuit shall be provided with a nameplate. All nameplates shall be of laminated plastic material, black on the surface with a white internal layer. Lettering shall be machine-engraved into the nameplate to form white letters against a black background. All panel mounted nameplates shall be in accordance with the respective drawing. A sample nameplate, showing the style of engraving to be used, shall be submitted to the DEDE Engineer for approval. Nameplate engraving shall be subject to approval of the DEDE Engineer.

All symbols, devices and painted mimic buses, 10mm in width, shall be provided on the main control board to form single line diagrams which will simulate actual electrical connections as indicated on the drawing entitled "Main Control Board Equipment Layout". Mimic disconnect devices for disconnect switches shall be manually operated. The mimic buses shall be painted on the front of the panels with lacquer or enamel. Color of mimic buses shall be as follows:-

22 kV	- RED
3.3 kV	- RED
0.4 kV	- GREEN

The control and instrument switches shall be of the multistage, rotary type, rated 600V, 20A, continuous duty, for both AC and DC service, and shall be designed for switchboard mounting with all contact mechanisms behind the panels. All contacts shall be enclosed in a cover, or covers, which can be easily removed when installed on the control board to afford complete accessibility to contacts and terminals. Each contact shall be of the readily renewable, self-cleaning type arid shall- be of the wipe-type. A rectangular front-of-panel escutcheon plate shall be furnished and engraved showing the switch position of control and instrument switches. The switch identification shall be engraved on the escutcheon plate, or if necessary, on a separate adjacent nameplate furnished by the Contractor.

The types of control switch handles and colors preferred shall be provided as follows:

Circuit breaker control switches	- pistol grip (black)
Instrument selector switches	- round notched (black)
Synchronizing switches	- oval removable (yellow)

Raise-lower control	-	oval (black)
Control selector switches	-	oval (black)
Other cut-off switches	-	oval (black)

The total number of contacts and the total number of contact arrangements shall be adequate for their required functions and shall include two normally open and two normally closed spare contacts.

Each indicating instrument shall be semi-flush mounted, back connected, dustproof, fully tropicalized, switchboard type with a dull black case for mounting on a steel panel. Each shall be suitable for operation with the instrument transformers shown on the drawings under both normal and short circuit conditions.

Except as otherwise specified; all indicating instruments shall be approximately 96 x 96 mm in size except annunciator windows.

Scale plates shall have a permanent white finish with black graduations and numerals. VAR meter scale plates shall be marked "IN (-)" at the left of the scale, "-0-" at the center and "- (+) OUT" at the right.

Auxiliary transformers shall be furnished where required to produce the correct magnitude and phase angle of measured quantities for the indicating instruments.

The maximum error of each indicating instrument shall not be more than one percent of full-scale range.

All relay contacts shall be rated to withstand at least 30A, 600V for 3 seconds, and at least 5A, 600V on continuous duty; All -20 percent to +12 percent of rated DC voltage as specified and at a range of ambient temperatures of 10°C to 50°C. Each protective relay shall be suitable for operation with instrument transformer ratios and connections as shown on the metering and relaying diagrams under both normal and short circuit conditions.

Each electro-mechanical relay shall be of the semi flush-mounted, back- connected, dustproof, fully tropicalized, switchboard type, with dull-back rectangular case and shall have a removable transparent cover, or a cover with a transparent Window, with provision for sealing. Each protective relay shall be the withdrawal type with built-in test facilities. Each relay shall be equipped with an operation-indicating target and contacts for operation of DC voltage rating as specified for each phase, with external front-of switchboard resetting device. Loading resistors-, where needed to secure reliable target operation, shall be furnished.

Static relays shall be supplied as complete relaying system. All relays and components necessary to complete a system shall be fully tropicalized, contained in

a common enclosure, and shall be complete with all interconnections and wiring for back-connection. Enclosures shall be rectangular, finished dull-black, dustproof, suitable for semi-flush switchboard mounting, with a removable transparent cover, or a cover with a transparent window, with provision for sealing. Operation indicating lights and identifying labels shall be provided with each relaying system and shall be clearly visible and identifiable. External appearance of the enclosure shall be compatible with cases specified above for electro-mechanical relays. All static relays shall be adequately protected against damage from incoming surges. Each relaying system shall utilize a DC-to-DC converter-type regulated power supply to provide transient surge isolation between the station battery and the electronic components of the relaying system.

All modules of static-type protective relays shall consist of highly reliable logic circuits and circuit components. All modules shall be mounted on plug-in circuit cards. Wiring boards shall be epoxy-fiberglass construction. Printed circuit wiring shall be employed with soldered or welded connections to circuit components. Wiring board shall be provided with heavy-duty circuit connectors with gold-plated contacts.

Additional auxiliary and control relays shall be used to complete the function of power circuit breaker tripping and reclosing, trouble alarm, or any indication, etc. as required in this Specification.

The coils of standard-speed relays shall be suitable for continuous duty at their normal operating voltage. All contacts shall be of the renewable type with ample current-carrying and interrupting capacity for the application, and shall withstand at least 30A, 600V at 3 seconds and at 5A, 600V at continuous duty. Auxiliary tripping relays of the mechanically latched-in type shall have manual reset- devices operable from the front of the panel by means of a red oval handle and shall have an operating time not to exceed 25 milliseconds. Auxiliary relays of the self-reset, standard-speed type shall have an operating time not to exceed 40 milliseconds. Auxiliary relays of the self-reset, medium speed type shall have an operating time not to exceed 30 milliseconds. Auxiliary relays of the self-reset, high-speed type shall have an operating time not to exceed 15 milliseconds without objectionable contact bounce. All auxiliary relays shall have sufficient number of electrically separate contacts for tripping, lockout and annunciator circuits specified.

Unit Control Sequence shall be capable of executing any control sequence selected by operator in all Control Modes except Manual Mode. The design sequence shall be proposed with the Bid including the following steps of sequences: -

a) Start and Synchronize Sequence
b) Normal Shutdown Sequence
c) Emergency Shutdown Sequence

Data Recording, Logging and Reporting in Controller's HMI PC shall be provided with the simultaneously recording and trending up to 6 parameters received by Control System in any define period. The operator shall be able to select the section of interest including the following items: -

a) Status Alarm and Indication
b) Audible signals and messages
c) Alarm logging and Indication
d) Status alarm List
e) Trending and Report

S11.07 TESTS

(1) Factory Tests

All control system equipment shall be tested at factory under the witness of DEDE engineer and in case of Contractor supplies the equipment from other countries, the Contractor shall bare all travelling expenses (air tickets, accommodation, meal, allowance, etc.) for two (2) DEDE Engineers (as Witness) to attend the test at factory and sign for approval of test results.

Factory tests of complete cubicles shall include tests of continuity of all panel wiring, I/O individual functions; Graphical Indication simulation test at HMI PC, all control indications, annunciations and alarm devices, measurement of insulation resistance, etc. The Contractor shall submit the list of test to DEDE Engineer for approval.

In case of the system panels are manufactured in locally and components assembly with internal wiring at Thailand, the Contractor shall perform the complete dry test of the panels with setting parameters before the commissioning wet test.

(2) Site Tests

The following site tests shall be performed before start-up the unit: -

(a) Inspect and prove continuity of all control, indication, protection and alarm circuits;
(b) Test insulation resistance of all circuits, at appropriate voltages.
(c) Prove correct operation of all control, indication, protection and alarm circuits.
(d) Prove correct operation of all indicating instruments by secondary injection.

SECTION 12 - MAIN TRANSFORMER

S12.01 SCOPE OF WORK

The work to be done under this section consists of the design, manufacture, testing, delivery to site, installation, ISO 9001 certificate, TIS standard or PEA standard, placing in successful service and guarantee of Two (2) set of generator transformers of minimum capacity at 1,000 kVA.

S12.02 PURPOSE AND FUNCTION

The transformer will step up the generator voltage from 3300 (or) 690V (nominal) to the transmission line voltage of 22 kV (nominal). Transformer will transfer power from a generator, rated for 1,000 kVA, 0.8P.F, 3-phase and 50 Hz. The generator will be star-connected and grounded through a resistor.

The layout and component list with dimensional drawings from manufacturer shall be submitted with the Bid.

S12.03 STANDARDS

The transformer shall be manufactured and tested in accordance with the latest TIS 384, JEC 204, VDE and DIN, or equivalent; unless otherwise specified in these specification HV and LV bushing shall be in accordance with the latest DIN 42531 and DIN 42530 respective, or equivalent; unless otherwise specification.

S12.04 TYPE OF TRANSFORMER

The transformer shall be 3-phase, 50 Hz, two windings, outdoor type OA (oil-immersed, natural air-cooled circulation), and Hermetically Sealed corrugated tank (or) Conservator Tank with self-standing on concrete platform.

S12.05 MEGAVOLT AMPERE RATING

The continuous rating shall be at 1,000 kVA minimum, based on an average copper temperature rise of 60°C and hottest spot of 75°C over an ambient maximum temperature of 45°C. Thermally upgraded paper shall be used.

S12.06 VOLTAGE RATINGS, CONNECTIONS AND TAPS

The high voltage winding shall be Star connected with a solidly grounded neutral for operation at 22 kV, line-to-line, and shall be equipped with 4 full capacities, off-load taps at ± 2.5 percent, ± 5.0 percent based on 22kV.

The low voltage winding shall be delta connected for operation at 3300 (or) 0.69kV.

All voltages are based on the turn ratio of the transformer at no load.

S12.07 INSULATION LEVELS

The Insulation level of HV windings and connected parts of transformers shell be as follows: -

Nominal System Voltage (kV, rms)	Insulation	
	Impulse Test Voltage Full wave (kV, peak)	Power Frequency Test Voltage, 1-min (kV, rms)
22	125	50

The values according to PEA standards are also acceptable and the Contractor shall for DEDE approval during engineering stage.

S12.08 IMPEDANCE AND LOSSES

The percentage impedance shall be 6.0 percent at 75ºC, based on 1,000 kVA and rated voltage. No-load losses and load losses shall be not more PEA Standards respectively.

S12.09 SHORT CIRCUIT CAPABILITY

When connected for normal, full-load operation, the transformers shall be capable of withstanding, without injury, a 3-phase short circuit on the terminal of any winding for duration of 2 seconds. It shall be assumed that rated voltage shall be maintained behind the reactance of system and generators.

S12.10 SOUND LEVEL

The transformer shall be designed to operate without exceeding the average sound levels prescribed by NEMA TR 1.

S12.11 HIGH FREQUENCY INTERFERENCE

The transformer shall be designed to operate without causing interference directly or indirectly to television reception and telephone communication circuits and shall not cause radio interference in excess of the suggested tolerance limits of NEMA TR 1.

S12.12 BUSHINGS AND CONNECTORS

The transformer shall have the high voltage and low voltage leads brought out from the tank through bushings best suited for the voltage of the winding and with a high factor of safety.

Outdoor bushings shall be in accordance with ANSI or IEC or DIN standards. All bushings shall be provided with threaded bushing studs and connectors.

Suitable connectors for buses, etc., shall be NEMA 4 holes type for all bushing terminals connection to 22kV and 3300 (or) 690V cables, and also submitted to the DEDE Engineer's approval.

Neutral bushings will be connected to a copper bus or copper conductor. There shall be no connection of the neutral lead to the inside of the tank.

Bushing arrangements, stud dimensions and connectors shall be subject to the approval of the DEDE Engineer.

All bushings shall be designed to eliminate harmful stress of any parts due to temperature changes and to provide for conductor expansion. All porcelain used in the bushings shall be homogeneous, free from laminations, cavities, or dielectric quality. The glazing shall be uniform in color and free from blisters, burns and other defects. All porcelain parts shall be one piece, well vitrified, tough, and impervious to moisture.

S12.13 OFF-LOAD TAP CHANGER

The transformer shall be equipped with a full megavolt ampere capacity off-load tap switch. The top changer shall include operating wheel or handle, indicating pointer and dial, and means for locking in any desired position. The locking device shall be arranged to prevent locking the tap switch in an intermediate position. The tap switch position indicator shall be visible from ground level while operating the tap switch. The tap switch shall provide 4 full capacity 2-1/2 percent voltage adjusting steps-2 above and 2 below the 22kV.

The complete tap changing mechanism shall be built to meet all operating conditions and shall have high electrical, mechanical, and thermal safety factors to withstand the full short circuit current of the transformer without damage. The switch contacts shall be silver-plated.

S12.14 CONSTRUCTION

The core shall be manufactured of high-grade, grain-oriented, non-aging sheet steel laminations having smooth surfaces. The core steel and all insulation associated with the core shall be designed so that no detrimental changes in physical or electrical properties will occur during the life of the windings.

The laminations of core type transformers shall be glass tape wrapped or bolted. Core bolt insulation shall be suitable for 130°C (Class B) minimum.

The core stack shall be grounded internally through grounding links located on top of the core to permit testing of the individual core packages for grounds.

The core steel and windings shall be suitably braced to prevent displacement or distortion during transportation and conditioned for permissible short circuit and overload. Suitable lifting attachments shall be provided for untanking the core and coils with a minimum of headroom. The design and location of lifting points shall be such as to preclude distortion of the core or damage to the core bolt insulation under lifting stresses. Lifting stress shall not be transferred between top and bottom clamps through the core iron.

All windings shall be copper. The winding insulation materials throughout shall be thermally upgraded and shall be 105°C (Class A) or higher.

Non-brazed electrical connections shall be compression type, 2-bolt connectors.

All fabricated steel shall be free from distortion and constructed according to the approved Drawings.

All oil-filled compartments mounted on the side of the main tank shall have a 12mm minimum raised lip to prevent dripping oil with the covers removed.

To maintain oil tightness, gasketed joints shall be designed and constructed to ensure even and effective pressure without overstressing the gasket, even under conditions experienced during vacuum filling of the main tank. When installed in position, the outer edges shall be protected by metal-to-metal stops or fire-resistant stop gasket material.

A relief vent shall be mounted on the cover adjacent to and projected beyond the expansion tank, discharging at a level above it. A sealed diaphragm shall be installed in both the top and bottom of the vent. The vent shall be equipped with a screen to prevent fragments of ruptured diaphragm from entering the transformer. The vents shall have the highest point not less than the height of their conservators and shall be designed to have the vent outlets face towards the ground with this height approximately 50cm above ground level in order to protect splash over of oil in case the pressure relief device is operated. The pressure relief vents shall be equipped with alarm contacts.

Two ground pads shall be fitted diagonally opposite corners of the base. Each pad shall include a clamp type terminal and bolts suitable for a 95 mm^2 stranded cable. Bolt holes in the pads shall be 35mm deep.

A ladder shall be located on the side of the transformer tank for climbing onto the transformer. It shall extend from the base of the transformer to a minimum of 0.50 m above the cover, with an adjacent handhold to assist in moving from ladder to cover. The lower part of the ladder shall be equipped with a barrier and locking device to prevent its use by unauthorized personnel.

S12.15 BASE

The base shall be designed to permit moving the assembled and oil-filled transformers on skid plates or rollers. The length and spacing of each pair of reinforced parallel rolling areas shall be such that the fully assembled transformers, with or without oil, can be safely tilted 15 deg. Internal reinforcing shall not prevent draining of all liquid from the tank.

The transformers shall be provided with fixed structural steel skids suitable for skidding or rolling the transformers in any direction. Eyes for attaching hauling equipment shall be supplied on each side of the transformer, so that the transformer may be hauled in all four directions relative to the transformer tank. Location of the eyes shall be approved by the Engineer.

S12.16 TRANSFORMER TANK OR CORRUGATED TANK

The transformer tank and assembled radiators, the conservator tank, shall be suitable for filling with oil in the field. The completely assembled transformer with oil shall withstand a pressure of 1.00kg/cm^2 (or) 125 percent of maximum operating pressure measured at the elevation of the cores.

S12.17 CONSERVATOR TANK (If applicable)

A conservator tank shall be mounted above the radiator bank. The tank shall have a minimum capacity of 10 percent of the oil volume of the transformer tank and cooling system and shall be suitable for operating under vacuum. It shall be equipped with dehydrating breather, accessible from grade level and designed to permit capping, a 50-mm valve with plug at the top of the tank, a sump and 25-mm drain valve at the lower end of the tank, and a manhole for inspection and cleaning. The connecting pipe to the main tank shall be 50 mm diameter minimum and shall project at least 25 mm inside the expansion tank. A brass gate valve of the rising stem type with a handle which clearly indicates the position of the valve gate shall also be provided.

S12.18 RADIATORS OR CORRUGATED TANK

The transformer shall be provided with a sufficient number of radiators to permit operation at the self-cooled ratings without exceeding the specified temperature rise.

Radiators shall be mounted on the transformer tank or corrugated tank.

Radiator valves shall be provided on each radiator connection to the interconnecting pipe, so that any radiator may be removed for repairs without taking the transformer out of service. Not required for hermetically sealed type transformer.

Radiators shall be equipped with provisions for draining.

S12.19 CONTROL

Suitable terminal blocks with a minimum of 20 percent spare quantity shall be provided to accommodate all wiring and cables.

All conduit and wiring between each item of equipment and the main control cabinet shall be provided.

S12.20 OIL

A sufficient quantity of oil shall be supplied in drums with 10 percent extra to allow for spillage. The oil shall have a dielectric strength, when shipped, of are least 30kV as measured in accordance with latest specifications. The oil shall be mineral oil complying with the latest ANSI (or) IEC (or) DIN standards on insulating oils. Three certified copies of test reports stating the dielectric strength of the oil shall be supplied to the Administration prior to energizing the transformer.

S12.21 ACCESSORIES

The transformers shall be furnished and equipped with the following accessories:

(1) HV and LV bushings, with terminal connectors.
(2) Bird guard cap (bushing cover), ultra-violet and track resistant material, e.g. Polypropylene, neoprene, etc; which is suitable for exposure to sunlight.
(3) Arcing horns, corrosion-proof, according to DIN 42531

(4) Tap changer
(5) Thermometer pocket with contacts.
(6) Oil level gauge with contacts.
(7) Buchholz relay with contact.
(8) Pressure relief device with contact.
(9) Nameplate with connection diagram.
(10) Oil drain valve with plug or cup, installed at the lower part of the tank.
(11) Sludge drain plug, installed at the bottom of the tank.
(12) Earthing terminal, with solderless clamp type connector suitable for steel stranded conductor diameter of 9.0mm (size 50mm^2); complete with lock-washer of stainless steel or better.
(13) Lifting lugs.
(14) Lifting eyes on the cover
(15) Oil conservator with dehydrating breather and oil level gauge with contacts. The cylinder of dehydrating breather shall be transparent glass. The dehydrating breather shall be easily replaced and filled with silica-gel, not less than 1.0 kg. It is not required for hermetically sealed type transformer.

S12.22 TESTS

The transformers shall be tested at the Contractor's works in accordance with ANSI C57.12.90. The following tests shall be made on the transformer.

Routine test
(1) Resistance of high and low voltage windings on all taps.
(2) Exciting current and no-load loss on rated voltage connections at rated voltage and 110 percent of rated voltage (to be performed after impulse test).
(3) Impedance and load test at rated current on the rated voltage connection and on the tap extremes (1 transformer only for tap extremes).
(4) Polarity and phase relationship tests.
(5) Ratio of all taps.
(6) Control components and auxiliary wiring tests. Where applicable, tests shall be performed on each transformer in accordance with the relevant standard:
- Dielectric.
- Control wiring.
- Mechanical.
(7) Applied and induced voltage tests.
(8) Temperature rise test.
(9) Mechanical tests, including pressure tests to establish the integrity of the tank and cooling system.

SECTION 13 – LINE PROTECTION AND SWITCHYARD EQUIPMENT

S13.01 SCOPE OF WORK

The works to be done under this section consist of design, manufacture, supply, testing and delivery to site with installation and guarantee for: -

- 9 (nine) sets of 22kV drop out fuse with fuse link
- 9 (nine) sets of Lightning arrester
- 6 (six) sets of Voltage transformer for 22kV Outgoing Line Protection
- 3 (three) sets of Current transformers for 22kV Outgoing Line Protection
- 1 (one) set of Vacuum (or) SF6 circuit breaker for 22kV Outgoing Line
- 1 (one) set of Disconnecting Switch for 22kV Outgoing Line
- 3 (three) sets of Current transformers for 22kV PEA Metering
- 3 (three) sets of Voltage transformer for 22kV PEA Metering
- 1 (one) set of 22kV Line protection cubicle

S13.02 PURPOSE AND FUNCTION

The line circuit breaker shall conduct electrical power from powerhouse to PEA transmission line via step up power transformer. This specification covers the requirements for motor operated remote controlled; three phase Vacuum (or) SF6 Line Circuit Breaker for PEA 22kV distribution system which shall be operated by 22kV Line Protection Cubicle. Line CB configuration shall be design and the manufacturer shall be ISO 9001:2000 and ISO 14001:2000 certified.

S13.03 DESIGN RATINGS AND STANDARDS

22kV Line Equipment shall be designed, manufactured, and tested as per latest version of ANSI, NEMA or IEC standards. Certified type test reports shall be provided for DEDE approval. Line Circuit Breaker shall have the rating as below:

Rated voltage, kV……..….24
Impulse level (BIL), kV ……150
Continuous current, A……....400 (min)
Interrupting Current, kArms sym. …….25A
Closing and tripping coil voltage (DC)……..125
Motor spring charger voltage (DC)……125

S13.04 EQUIPMENTS

All equipment in this section shall comply with IEC, NEMA, ANSI (or) equivalent and they shall have the ratings as below: -

(1) Line circuit breaker, 22 kV, 400A, 25kA minimum

(2) Disconnecting switch, 25.8kV, min 400 A
(3) Lightning arrester, 21 kV, 10kA
(4) Current transformer, dry type class resin, 22kV, 100/5/5A
(5) Voltage transformer, dry type class resin, 22,000/110/110V
(6) Drop out fuse cutout, outdoor type, 27kV, 12kA, 50A
(7) Line protection cubicle having line protective function and remotely controlled and monitored from Control Room. Metering and Protective Relays shall be selected and supplied similar according to the requirements stated in Section-11 and also having reference in PEA.

Bidder can submit alternative proposal of Switchyard layout equipment with the ratings not to be less than shown in these specifications.

S13.05 DETAILED REQUIREMENTS

The 22kV switchyard equipment, metering and protection system shall meet the requirements and shall comply with the standards and the protection system shall be complied with and approved by DEDE (or) PEA.

The contractor shall design the 22kV line protection system and metering system which is to be installed in switchyard according to the well proven associations by the reputable international certification such as: -

- 10 CFR 50 Appendix B Nuclear Quality Program
- ABS Marine Type Approval
- CE (Europe)
- CSA (Canada)
- ENA (UK)
- IEC, including IEC 61850-10 Conformance
- IEEE, including IEEE 1613 Reliability
- ISO 9001:2008
- ISO/IEC 17025
- KEMA
- RUS (for rural electric cooperatives)
- UL
- VPP Star Safety

Control circuits including potential and current transformer secondary circuits, batteries, DC controls, AC auxiliary power supplies, supervisory alarms and communication circuits connected to the function of the protection equipment shall be protected against conductive, electrostatic, and electromagnetic influences of transients of neighbouring circuits.

Both ends of each cable connecting relays to voltage and current transformer secondary circuits, batteries, DC control, AC auxiliary power, supervisory alarms, tripping, and communication circuits, shall be marked with slip-over ferrules of different colours and numbering.

Each relay system shall be provided with test plug facilities for secondary injection testing and current circuits, potential circuits, tripping circuits and all other output contacts. All test switches shall be arranged so that the current transformer secondary circuit cannot be opened circuit in any position while the test plugs or cover plugs are being inserted or removed. Test plugs shall be furnished with each type of test switch. All digital relays shall be adequately protected against damage from incoming surges and shall meet ANSI SWC test standard.

All modules of digital type protective relays consist of highly reliable logic circuits and circuit components. All modules shall be mounted on plug-in circuit cards. Wiring boards shall be epoxy-fiberglass construction. Printed circuit wiring shall be employed with soldered or welded connection to circuit components. Wiring board shall be provided with heavy-duty circuit connectors with gold-plated contacts.

The instruction manuals shall be prepared with the object of providing sufficient detailed technical information of each type of protective relay to enable DEDE to efficiently carry out commissioning and routine testing, to provide guidance in the tracing of faults and to permit order of replacement parts. In this regard, each instruction manual shall give full details of circuit operation, circuitry, and components. All technical data, operating time curves, sample calculations and other characteristics shall be based upon 50 Hz Operation.

The settings for the relay functions shall be programmed by via software from laptop and it shall also be approved by PEA for setting values. And the method of parameter uploading, and correction shall be trained to DEDE operator before commercial operation of the plant.

Lock-out and Non-lockout Relays

Lock-out relays shall be high speed half-cycle type, solenoid operated, mechanically latched, with pistol grip manual reset handle. Non- lockout relays shall be similar but without the latch and reset features. Output contacts shall be rated for 2A at 125VDC. Sufficient contacts shall be supplied for all stated functions.

Auxiliary Relays

Auxiliary relays shall be rail-mounted socket type with sealed case and coils and contacts rated for 24 or 125VDC.

Protection Circuits

Relay protection circuits for 22kV line equipment shall be by 125 VDC and shall be supplied. Loss of supply relays shall monitor the supply and shall alarm the control system upon loss of DC. All VTs and CTs circuits shall be supplied with test switches for isolation during testing and shall be installed at 22kV Line Protection Cubicle.

Metering

Active and reactive energy metering shall be provided for revenue, statistical and efficiency measurement. High accuracy metering of kWhr and kVARhr are required at control room and it shall be connected to Unit PLC via data communication cable. Metering shall

comply with IEC 60687. Metering test block shall be provided in the CT and VT circuit to provide isolation and testing connection facilities for the meter.

All metering shall be a digital type meter with TCP/IP communication and can be recording information and shall be shown at HMI LCD Screen of operator control station and shall be printed out the data logging, alarm list, metering values and other information. Meters shall have a backlit LCD screen for display of quantities and phase vectors, and controls for selection of measured and calculated quantities. Meters used for monitoring distribution line electrical quantities shall be of revenue metering accuracy class.

Wiring, Setting and Testing

The Contractor shall supply, before elaborating the wiring diagrams, block diagrams in one drawing for each type of feeder protection. These block diagrams shall include schematic information concerning trip circuits, control circuits, secondary circuits of voltage and current transformers with polarity marks, DC power supply, supervisory alarms and teleprotection circuits, etc. These block diagrams shall be updated during the factory test, erection and commissioning phases.

The protection system shall be completely wired, tested, and inspected at the factory before shipment.

The wiring used within the switchboard shall conform to DEDE standard. The only work necessary to be performed at site shall be the connection of the external devices, the commissioning procedure, and the site tests.

Test devices shall be provided for relay test facilities. Each test device shall be furnished with each relay and arranged to isolate completely the relay from instrument transformers and other external source of energy or from instrument transformers by means of multipole test plugs which shall be provided for the purpose. A sufficient number of test plugs to make a complete test on one relay shall be furnished for each type of test device. All test devices shall be arranged so that the current-transformer secondary circuits cannot be open-circuited in any position while test plugs are being inserted or removed.

It shall be possible to perform complete test of a protective relay, interposing relays, if any, and circuit breaker by injection of analogue values through the test blocks, without disconnecting any wire (or) connector.

DC-Supply

The power supply shall be based on 125V lead-acid station batteries but other voltage ranges are acceptable and shall submit to DEDE for approval.

All relays shall be equipped with a self monitoring alarm system, especially for DC supply and abnormal level of stabilised DC voltages but not necessarily limited to only these two. The DC supply of all the protection relays and communication shall be monitored by means of an auxiliary contact of the related mini-CB’s which will provide an alarm in case of fault on the DC supply.

The DC supervision relays shall indicate a delayed, independent and separate alarm for each supervisory relay and also a local and remote alarm in case of a missing DC supply and DC/DC converter failure of DC supply.

Interface Requirements

The protection scheme(s) shall include all hardware and software to allow remote setting/configuration/fault analysis by connecting with Engineering Laptop and have to install software for maintenance purpose for the followings: -

- On and Offline communication
- Relay Settings
- Relay configuration
- Switching of setting group
- Extract disturbance records
- Access to relay monitored parameters

Access to relay display and setting parameters will be keyed by different authorization levels (password).

Disturbance records requirements

The internal disturbance recorder shall have the capability to store at least the last 5 disturbance records with a minimum total storage capacity of 3 seconds (typical). This records shall be stored in the relay memory, backed by a battery or non-volatile memory. Battery low voltage alarm facility shall be provided for monitoring of status of the battery.

S13.06 DEDICATED PROTECTION

In addition to dedicated protection devices described below, auxiliary tripping relays and auxiliary tripping and lockout relays shall be provided with line protection.

Each auxiliary tripping and lockout relay shall be of the high-speed type, DC voltage operated, electrical reset with cut-off contact provided to interrupt the operating coil. All contacts shall be electrically separate contacts and rated to carry 30A, 300V, for 3 seconds, 5A, 300V, continuous, and be capable of interrupting of 0.2A of inductive current (L/R ≤40 ms) in a 125V DC control circuit.

Loss of DC control circuit shall be monitored by loss-of-potentiala DC alarm relay. (27XB, 27XR). Each relay shall be provided with an auxiliary relay, standard speed with slow dropout characteristics.

Similarly, loss-of-AC control supply shall also be monitored by a loss-of alarm relay (27XM). Each relay shall also provide contacts for alarms similar to loss-of-DC alarm relay.

S13.07 LINE PROTECTION

The line protection relay shall be a digital microprocessor type providing the protection functions as per PEA standards and shall meet the requirements of updated PEA Power Network System Interconnection Code.

SECTION 14 - GROUNDING SYSTEM

S14.01 SCOPE OF WORK

The work to be done under this section consist of the design, manufacture, testing and installation of Grounding system in the Powerhouse and the transformer switchyard.

S14.02 GROUNDING WORKS

All metal parts such as steel structures, turbine casing, and all electrical equipment supplied by the Contractor including cable racks and conduits shall be connected to the ground mesh.

The Contractor shall design the grounding system, after studying of soil receptivity and maximum ground fault. The calculation shall be submitted to the Department. for approval.

The ground mesh shall be designed to keep total potential rise in the project area, step and touch voltages within allowable values during ground fault.

The actual ground resistance shall be measured after the ground mesh is installed.

SECTION 15 - ELECTRICAL AUXILIARY EQUIPMENT

S15.01 SCOPE OF WORK

The work to be done under this section consists of the design, manufacture, testing deliver to site, installation, commissioning and the guarantee of electrical auxiliary equipment within the powerhouse and related structures. The scope includes all engineering, materials and equipment required for the Works.

S15.02 WORK INCLUDED

The equipment covered under this section includes:

- cable trays and supports
- conduit, boxes and fittings
- HV cable
- 750 V wire and cable
- control cable
- master clock system with digital clock
- motor control center (If required)
- Surge tank water level transmitter (If required)

S15.03 CODES AND STANDARD

All materials, equipment and methods of work shall comply with the latest edition of applicable laws, codes and standards listed in this contact.

S15.04 CABLE TRAYS AND SUPPORTS

Cable trays complete with support system, fittings, barriers hardware, etc., shall be provided to facilitate and support of power, control and metering cables.

Cable trays shall be made of aluminum or galvanized steel. Sections of tray shall consist of a 1-piece corrugated, ventilated bottom contained within longitudinal side members supplied in convenient lengths. Elbows, tees, bends, etc., shall be of similar construction. Tray connectors shall provide a grounding path between tray connectors shall provide a grounding path between tray sections. The complete tray system shall provide a smooth surface free of sharp protrusions or nicks which could damage cables. Where cable trays are positioned so that cables may be subject to damage from above, ventilated covers shall be provided.

Trays shall be supported by suitable structural steel frames, brackets, rods, etc., as applicable, secured by concrete inserts to be provided in cable trenches. Distance between supports shall not exceed 2.6 m. The maximum deflection for fully loaded trays, midway between supports, shall not exceed 5 mm.

Power and control/metering cables shall be installed in separate trays to the degree practical, and in instances where combined, a solid dividing barrier shall be provided. Power cables shall be similarly divided with respect to voltage.

S15.05 CONDUIT, BOXES AND FITTINGS

Conduit, embedded in concrete and exposed, shall be provided to facilitate the installation of all conductors, cables and wires not contained in the cable tray system. Conduit shall be provided where the cable in the tray would be subject to damage and also provided from the cable tray system to motors, posh buttons, control equipment, etc.

All conduit shall be rigid heavy wall, galvanized steel according to ANSI C80.1 with threaded joints. Minimum size shall be 25-mm. inside diameter for embedded conduit and 20-mm inside diameter for exposed conduit.

Where conduit is to be installed in concrete structures, all joints or connections shall be watertight, each joint being painted with red lead paint and allowed today before being encased. Where services are concealed within an enclosure, the conduits shall be neatly arranged and coordinated with other service pipes.

Conduit runs which are exposed, or are run in open ceiling spaces, shall be neat in appearance and run parallel to the structural lines of the building, and suitable conduit fittings and covers shall be used. Where a single conduit run is attached to reinforced concrete walls or ceilings, it shall be fastened by lead or expansion type anchors only, using malleable iron 1-hole straps at intervals not greater than those given below.

Space Between Support Straps

Conduit Size (mm.)	Horizontal Run (m.)	Vertical Run (m)
20	1.50	2.0
25 and 30	1.75	2.5
over 30	2.50	2.5

Cover screws for all conduit fittings or junction boxes shall be carefully cut to length to avoid damage to wires.

At the completion of the installation, all blockages shall be cleared and all outlet and pull boxes cleaned out.

All open ends of conduit shall be capped with proper threaded caps or bushings with steel pennies immediately after installation. The use of wooden plugs will not be permitted. Empty conduit for future equipment shall be capped flush with the finished floor.

Conduit shall be of adequate size for all wires and cables which have to be pulled in. The number of wires or cable sin each conduit shall not exceed the requirements of the current edition of the National Electrical Code. The pull for any group of wires shall not be so excessive as to damage or distort them, and only an approved greaseless compound may be used to facilitate pulling.

All metallic conduit and fittings shall form a continuous bonded path and shall be grounded.

Wherever rigid conduit is to be underground, it shall be protected by 2 coats of approved bituminous paint.

Conduit runs shall be sloped to ensure suitable drainage. Conduit runs that may trap water shall be provided with drain plugs or other suitable means of draining off periodically.

Conduit shall be firmly secured at the entrance to all equipment, using 2 locknuts and a bushing, or the equivalent thereof, at each entrance.

Conduit terminations at equipment subject to vibration shall be liquid-tight, flexible type with a plastic jacket and of a length not exceeding 0.5 m.

All bends in conduit shall be made cold and the radius of bend shall not be less than 9 times the conduit diameter. No bend which flattens the conduit by more than one-tenth of its diameter shall be permitted.

All threads on conduit shall be cut neatly, the ends shall be square and the inside edge reamed smooth to remove burs.

When the number of right-angle bends in one run exceeds 3, junction or pull boxed shall be provided. In no case shall a conduit run be greater than 30 m. Pull boxes shall be used to break up longer runs.

Additional accessible pull boxes shall be installed where necessary, so that throughout the entire system wire or cables may be pulled in or withdrawn with reasonable ease.

The flexible conduit shall be secured to the rigid conduit and equipment terminal box by suitable connectors. A continuous ground shall be assured by bonding the equipment frame to the rigid conduit by a copper ground strap or by means of a bare copper conductor of size equal or larger than the equipment feeders.

The ground conductor shall be secured to the rigid conduit by a suitable grounding clamp, spiraled neatly around the flexible conduit and terminated in a suitable lug bolted to the equipment frame.

All conduit fittings and boxes for receptacles or switches in weatherproof areas, or when used on exposed conduit, shall be of case construction, with threaded conduit hubs. Pressed steel boxes with conduit knockouts used on exceeded conduit or flush fixtures in indoor ate as shall be properly secured with locknuts and bushings.

Wherever encased conduit crosses a structural expansion joint, approved expansion fittings with bonding jumpers shall be provided.

S15.06 750 V WIRE AND CABLE

Conductors, cables and wires shall be provided for a complete functioning installation, and shall include for power, control and metering systems.

In addition the Contractor shall supply and install 750 V cable for main power supply of lighting system, emergency valve and reservoir water level detector which supplied by other Contractor.

All conductors shall be stranded copper minimum No.12 AWG (4 mm^2) for power and No.14 AWG (2.5 mm^2) for control.

All conductors shall be sized for adequate loads connected and shall limit voltage drop to 2 percent in branch feeders and 1 percent in the main feeders and also be in conformance with the National Electrical Code.

Conductors for use on 400-V and 230-V systems shall have 750-V, Insulation voltage

Conductors for use in cable tray on 400 V and 230-V systems and for all control or metering shall be multi-conductor with a PVC jacket. Power conductors contained in conduit throughout their length (lighting, etc.) may be single conductor.

Wire connectors for systems up to 6 mm^2 shall utilize non-solder crimp type connectors applied with a tool approved for the connector. Larger connectors shall utilize split-bolt type connectors and be insulated with 3 one-half layers of vinyl electric tape.

Wire terminations shall utilize compressor type connectors other than at locations where screw clamp connectors are provided in equipment.

All conductors shall be identified at both ends with ferrule type slip-on plastic wire markers which shall clearly identify the wire numbers in agreement with schematic and wiring diagrams.

All cables shall be identified at both ends with permanent plastic or metal tags in agreement with wiring diagrams and circuit lists.

The cables for the resistance temperature detectors shall be shielded with twisted leads and have a minimum copper section of No.16 AWG (1.5 mm^2)

S15.07 CONTROL CABLES

The Contractor shall read the Drawings as a whole and make adequate provision for all conductors and connections, particularly so for the multi-conductor control cables required for interconnections between various control, metering and relaying panels in the powerhouse and control area. It shall be noted that the Drawings do not show the control and DC cables required for connections to the control, metering and relaying equipment. All control cables shall be brass shielded.

The Contractor shall supply and install the control cables for remote control, remote indication of emergency valve for penstock and control cables for reservoir water level detector and acoustic flow measuring instrument which supplied by other Contractor. The cables shall be installed from powerhouse to marshaling board in emergency valve house.

The Contractor shall supply and install the control cables with seven strands for control, metering and relaying interconnections between the equipment of powerhouse, switchyard and the control area.

The following minimum conductor sizes shall apply.

Control, instrumentation circuits	No.14 AWG (2.5 mm^2)
Current transformer circuits	No.10 AWG (6 mm^2)

All control, cables used for protection, metering and control shall have the following characteristics.

Type of installation	- cable trays
Voltage	- 750 volts
Number of conductors	- multiconductor as required (maxim 12 12 conductors)
Conductor size	- as required
Conductor material	- soft, annealed, tinned copper
Shielding material	- brass
Conductor insulation	- heat, moisture and ozone-resistant, cross-linked polyethylene, color coded

Conduction color sequence

Conductor Number	Base Color	Tracer Color
1	black	
2	white	
3	red	
4	green	
5	orange	
6	blue	
7	white	black
8	red	black
9	green	black
10	orange	black
11	blue	black
12	black	white

Outer jacket - PVC.

S15.08 MASTER CLOCK SYSTEM WITH DIGITAL CLOCK

Satellite time signal (GPS antenna) is given a standard time signal to connect various systems to the same time signal to increase accuracy shall be submitted for DEDE approval.

S15.09 MOTOR CONTROL CENTER (If required)

The enclosures shall be type 1 gasketed, in accordance with NEMAS ICS 1-110 Standards, indoor installation and made of steel sheet having a minimum thickness of 2.5 mm.

Module or compartment of enclosures shall be provided with a hinged door to allow full access to the inside mounted equipment, the doors shall be suitably gasketed to make the compartment dust-tight and provided with key locks.

Bus bars for power circuits shall be of copper liberally dimensioned for the specified current ratings, both short- circuit and continuous current, all joints and connections of bus bars shall be silver plated.

The phase arrangement shall be A, B, C, counting front to back, top to bottom, of left to right, as viewed from the front of the enclosure.

Each phase shall be suitably identified by marks as follows:

- Phase A - brown
- Phase B - black
- Phase C - gray
- Neutral - light blue
- earth - green/yellow

Admissible temperature rise shall be 65ºC above the ambient air temperature as per NEMA ICS 2-322 Standard.

Bus supports shall be suitable for polluted atmosphere and shall be made of flame retardant material.

Each enclosure shall be provided with a copper ground bus having a minimum cross section of 100 mm^2.

A suitably dimensioned ground bolt can be provided instead of the ground bus for the smallest panels, boards or cabinets.

The steel structure and all metallic parts of the enclosures shall be connected to the ground bus.

Grounding terminals and connectors for 95 mm^2 copper ground conductor shall also be provided at either end of the ground bus.

All enclosures shall be provided with thermostatically controlled space heaters operated at 230 V 50 Hz from an external source.

Heaters shall have individual automatic miniature circuit breakers.

Each vertical section shall be provided with one space heater.

The thermostat range shall preferably be 0-50ºC.

The cable entry shall be located at the bottom of the enclosures according to the actual layout.

Enclosures shall be supplied complete with cable glands. Removable plates for fitting the cable glands shall be provided preferably at bottom of the enclosures.

Suitable base channel frames complete with anchor bolts and nuts shall also supplied.

The motor control center will be used to supply the power and/or the control of 400 V motors up to 33 kW.

The motor control centers shall be class II type B in accordance with NEMA ICS 2-322 Standards.

Unless otherwise stated in the Special Technical Specifications or shown in the Contract Drawings, the power circuit of motor control centers shall have the following main characteristics:

- System — three-phase, four wires, grounded neutral
- Nominal voltage — 400 V
- One-minute power frequency withstand voltage — 2,200 V
- Rated frequency — 50 Hz
- Rated continuous current:
  - main bus bars — 400 A
  - vertical buses — 200 A
  - neutral bus — 200 A
  - branch circuits — as per the associated circuit breaker
- Rated short-time withstand current for 1 sec — 35 kV (RMS symm.) plug-in contacts included

Motor control centers shall be made up of individual modules arranged in vertical sections with separations between each other.

The vertical sections shall be bolted together to form a rigid, free standing assembly of uniform and neat appearance.

The module sizes shall be multiple of one basic unit to facilitate interchangeability.

Modules of similar function shall be interchangeable.

The door of each individual module shall have a key lock and shall be so constructed that it cannot be opened when the relevant main circuit breaker is in the "ON" position.

Modules provided for motor control (Combination Motor Control Units) shall be of the fully draw-out type, i.e., contacts for power terminals on both incoming and outgoing sides shall be draw-out type.

Modules provided for non-motor loads (Feeder Tap Units) shall also be of the fully draw-out type.

Power and control terminals shall be installed close to each module and physically separated from each other.

Suitable interlocks shall be provided to prevent on-load withdrawal of draw-out type units.

When the draw-out units are taken out, suitable devices shall avoid accidental contacts with live parts. Automatically operated shutters or similar devices would be accepted.

Motor control centers are typically composed by an Incoming Feeder, some Feeder Tap Units and some Combination Motor Units as required by the Contractor's load.

Contractor shall follow the prescriptions given here below.

The Incoming Feeder cubicle shall be of fixed type, equipped as follows:

- non-automatic molded case circuit breaker, draw-out or plug-in type;
- voltmeter with scale 0-500 V;
- Voltmeter switch to read the three line-to-line voltages upstream of main circuit breaker;
- voltage transformers 400/100 V;
- aux protective fuses.

The Feeder Tap Unit shall be draw-out type, equipped with molded case circuit breaker with built-in thermo-magnetic protective device.

Combination Motor Control Units shall be fully draw-out type. They shall consist of:

- molded case circuit breaker with built-in magnetic protective device;
- magnetic contactor (in the starters for reversing motors, two contactors mechanically and electrically interlocked shall be provided);
- auxiliary relays;
- timer relays;
- thermal overload relay;
- 400/230 V, single-phase, auxiliary transformer of adequate capacity to feed the control circuit;
- indicating lamps;
- auxiliary protective fuses.

The circuit of every Combination Motor Control Units shall include the necessary devices, contacts and/or relays for the remote signaling or draw-out not available due to operation of thermal and magnetic protective devices, control voltage loss, etc. A local indication shall also be provided by means of an indicating light with amber cap.

As a general rule, the motor control centers shall have only provisions for the signaling of motor operation.

The necessary push buttons, selector switches and/or any other necessary devices shall be supplied by the Contractor for control of the motors control center.

Control units for motors requested to re-start after a brief interruption of voltage supply shall be equipped with the necessary relays and/or devices.

The Contractor shall be fully responsible for the good coordination of equipment supplied under his scope of work.

Particular care shall be applied in coordinating the equipment for combination motor control units in order to protect the contractors and thermal overload relays in case of short circuit faults.

To provide facility for inclusion of interlocks, the motor control circuits shall be developed with suitably located breaks provided on the terminal block and bridged up with jumpers.

When requested, the Contractor shall supply the auxiliary relay required to multiply the auxiliary contacts of the main equipment, in order to reproduce the approved schematic diagrams.

S15.10 SURGE TANK WATER LEVEL TRANSMITTER (IF REQUIRED)

One Fore Bay water transmitters shall be provided. The transmitter shall sense the Fore Bay water level to the control room. A digital readout shall be provided in the control room to show the actual elevation of the water column in meters. All electronics, panels, and any special shielded cables shall be included in the supply.

S15.11 TELEPHONE SYSTEM (Not Applicable)

(1) Exchange

(a) A Private Automatic Exchange (PAX) of not less than 6 direct line and 20 lines extension capacity shall be installed in the Power Station Control Room with extensions listed in paragraph (f) below.

(b) The exchange shall conform to current design standards, emphasis being placed on maintenance and fault clearance by replacement of plug-in printed circuit boards. For this reason it is essential that the exchange should be of a type already in use in Thailand and supported by adequate manufacture's service facilities. One spare card of each type use including ring and tone generators shall be provided.

(c) The exchange shall be powered by the Power Station 125 VDC battery.

(d) The exchange shall be provided with an operator's console installed in the control room.

(e) The exchange shall have the following facilities:
(i) priority cut-in on selected extension;
(ii) barred access on selected extension to outgoing calls on tie circuits;
(iii) conference facilities ; and
(iv) two both-way dialing tie circuit connection for further use.

(f) The location of the extension telephones shall be as follows:

LOCATION	TELEPHONE TYPE	ADDITIONAL EQUIPMENT	Qty
Office	Desk		1
Diesel Room	Heavy duty industrial	Noise concealing mic. acoustic shield. Loud ringing bell.	1
Machine Bays	Heavy duty industrial	Noise canceling mic. acoustic shield. Loud ringing bell.	2
Main Transformer Bay	Heavy duty industrial	Noise canceling mic. Weatherproof acoustic shield. Loud ringing bell	1
Residence	Desk		6
Control Room	Operator's Console		1

(g) The Contractor shall supply and install as above specified and also wiring, cabling, conduits to make the completed system and proper functions.

S15.12 TESTS

In addition to the equipment tests specified elsewhere, the following tests of the electrical equipment shall be conduced when the installation is complete, but prior to commissioning.

- Check direction of rotation of all motors and reverse connection, if necessary.
- Check all motors for correct clearances and alignment and for correct lubrication. Lubricate in accordance with manufacturer's instructions.
- Megger all bus ways, cables and control connections to prove insulation resistance is of acceptable value. minimum acceptable resistance is 1 megaohm.
- Check each motor controller and contractor before placing same in continuous service, and make adjustments as required. Check all overload relay ratings and breaker trip settings. Check all control, interlocking and instrument wiring for proper operation.
- Provide a tabulated list of all overload relay heaters and fuses installed and their various locations.
- Test each lighting control and power circuit with 1,000-V megger for short circuits, improper grounds, insulation and operation. Each panel shall be tested with mains disconnected form the feeder, branch circuits connected and switches closed, all fixtures in place and permanently connected, lamps removed or omitted from the sockets and all wall switches closed.
- Test feeders with the feeders disconnected from the branch circuit panels. Each individual power equipment connected for proper operation. In no case shall the insulation resistance be less than 1 megaohm.

  Where tests indicate that the insulation was damaged by handling or during installation, such wires and cables shall be repaired or replaced at no cost to the client.

  - Prove correct operation of surge tank water level transmitter.
  - Prove correct operation of single side band transceiver with antenna.
  - Prove correct operation of telephone system.

S15.13 HV CABLE END TREATING MATERIAL

The HV cable end treating material shall be used for indoor and outdoor end treatment of cross linked polyethylene insulated power cables described in the preceding clause.

The end treatment shall conform to the applicable requirements of ICEA Standards 5-66-524.